

AD-A136 229


LAKE DARLING FLOOD CONTROL PROJECT SOURIS RIVER NORTH
DAKOTA GENERAL PROJ..(U) CORPS OF ENGINEERS ST PAUL MN
ST PAUL DISTRICT JUN 83


1/3

UNCLASSIFIED

F/G 8/7

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A



US Army Corps
of Engineers
St. Paul District



**DESIGN MEMORANDUM NO. 3
GENERAL-PROJECT DESIGN**

APPENDIX B - GEOLOGY AND SOILS

AD-A136229

Copy available to DTIC does not
permit fully legible reproduction

**LAKE DARLING
FLOOD CONTROL PROJECT
SOURIS RIVER, NORTH DAKOTA**

DTIC FILE COPY

JUNE 1983

**DTIC
ELECTE
DEC 21 1983**
S D

83 12 20 198

DISTRIBUTION STATEMENT A
Approved for public release;
Distribution Unlimited

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|--|-----------------------|--|
| 1. REPORT NUMBER Design memorandum #3 | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) LAKE DARLING FLOOD CONTROL PROJECT, SOURIS RIVER NORTH DAKOTA: General-project design. Appendix B-Geology and Soils. | | 5. TYPE OF REPORT & PERIOD COVERED |
| | | 6. PERFORMING ORG. REPORT NUMBER |
| 7. AUTHOR(s) | | 8. CONTRACT OR GRANT NUMBER(s) |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Paul 1135 USPO & Custom House St. Paul, MN 55101 | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 11. CONTROLLING OFFICE NAME AND ADDRESS | | 12. REPORT DATE June 1983 |
| | | 13. NUMBER OF PAGES 101 |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) | | 15. SECURITY CLASS. (of this report) |
| | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE |
| 16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited. | | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) | | |
| 18. SUPPLEMENTARY NOTES | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) FLOOD CONTROL SOURIS RIVER GEOLOGY SOILS | | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The Lake Darling project is the second phase of the total flood control plan for the Souris Valley in North Dakota. Appendix B addresses physiography, geology, ground water, site topography, water table, and plates of the Lake Darling Dam, including stability analysis and borings. | | |

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

BLANK PAGE

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

FLOOD CONTROL
LAKE DARLING
SOURIS RIVER, NORTH DAKOTA

DESIGN MEMORANDUM NO. 3
GENERAL PROJECT DESIGN

APPENDIX B
GEOLOGY AND SOILS

| | |
|--------------------|--|
| Accession For | |
| NTIS GRA&I | <input checked="checked" type="checkbox"/> |
| DTIC TAB | <input type="checkbox"/> |
| Unannounced | <input type="checkbox"/> |
| Justification | |
| By | |
| Distribution/ | |
| Availability Codes | |
| Dist | Avail and/or Special |
| A/1 | Code 23 207 |



DEPARTMENT OF THE ARMY
St. Paul District Corps of Engineers
1135 U.S. Post Office and Custom House
St. Paul, Minnesota 55101

FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
DESIGN MEMORANDUM NO. 3 - GENERAL
PROJECT DESIGN

APPENDIX B
GEOLOGY AND SOILS

TABLE OF CONTENTS

| <u>Paragraph</u> | <u>Item</u> | <u>Page</u> |
|------------------|--|-------------|
| 1-5 | PHYSIOGRAPHY | B-1 |
| 6-12 | GENERAL GEOLOGY | B-1 |
| 13-17 | GROUND WATER | B-4 |
| 18-29 | SITE TOPOGRAPHY, SUBSURFACE CONDITIONS, AND FOUNDATIONS MATERIALS | B-5 |
| 19 | RIVER ALLUVIUM | B-5 |
| 20 | GLACIAL SEDIMENTS | B-5 |
| 21-29 | TONGUE RIVER FORMATION | B-5 |
| 22 | <u>Permeability</u> | B-6 |
| 23 | <u>Faulting</u> | B-6 |
| 24 | <u>Jointing</u> | B-6 |
| 25 | <u>Excavation Properties</u> | B-6 |
| 26 | <u>Bearing Capacity</u> | B-6 |
| 27 | <u>Rebound</u> | B-7 |
| 28 | <u>Slope Stability</u> | B-7 |
| 29 | <u>Foundation Protection</u> | B-7 |
| 30 | WATER TABLE | B-7 |
| 31-32 | SOURCES OF STONE AND AGGREGATE CONSTRUCTION MATERIALS | B-7 |

TABLE OF CONTENTS (con.)

| <u>Paragraph</u> | <u>Item</u> | <u>Page</u> |
|------------------|---|-------------|
| 33-37 | ECONOMIC GEOLOGY | B-8 |
| 34 | SAND AND GRAVEL | B-8 |
| 35 | GLACIAL TILL | B-8 |
| 36 | GLACIAL BOULDERS | B-8 |
| 37 | PETROLEUM | B-8 |
| 38-41 | SUBSURFACE INFORMATION AND TESTING | B-9 |
| 42-52 | LAKE DARLING DAM | B-10 |
| 42-44 | GENERAL | B-10 |
| 45 | EMBANKMENT DESIGN | B-10 |
| 46 | SEEPAGE CONTROL | B-10 |
| 47-48 | STABILITY | B-11 |
| 49 | SETTLEMENT OF EMBANKMENT FOUNDATION SOILS | B-12 |
| 50 | CONTROL STRUCTURE | B-12 |
| 51 | PROPOSED DISTRIBUTION OF REQUIRED EXCAVATION | B-12 |
| 52 | CONSTRUCTION SEQUENCE AND DIVERSION PLAN | B-13 |
| 53-57 | SOO LINE RAILROAD RAISE | B-13 |
| 53 | GENERAL | B-13 |
| 54 | EMBANKMENT DESIGN | B-14 |
| 55 | STABILITY | B-14 |
| 56 | SETTLEMENT OF EMBANKMENT FOUNDATION SOILS | B-14 |
| 57 | PROPOSED DISTRIBUTION OF REQUIRED EXCAVATION AND BORROW | B-15 |
| 58 | ROAD RAISES - STATE HIGHWAY 28 AND FAS ROUTES 3809 AND 3828 | B-15 |
| 59-60 | STATE HIGHWAY NO. 5 ROAD RAISE | B-16 |
| 61 | ECKERT RANCH AND MCKINNEY CEMETERY LEVEES | B-16 |
| 62 | RENVILLE COUNTY PARK | B-17 |
| 63 | BURLINGTON TO MINOT LEVEES | B-17 |

PLATES

| <u>Number</u> | <u>Item</u> |
|---------------|---|
| B-1 | LAKE DARLING DAM - GENERAL PLAN |
| B-2 | LAKE DARLING DAM - TYPICAL SECTIONS |
| B-3 | LAKE DARLING DAM - SUBSURFACE PROFILE EMBANKMENT CENTERLINE |
| B-4 | LAKE DARLING DAM - SUBSURFACE PROFILE SPILLWAY CENTERLINE |
| B-5 | LAKE DARLING DAM - STABILITY ANALYSIS - END OF CONSTRUCTION |
| B-6 | LAKE DARLING DAM STABILITY ANALYSIS - PARTIAL POOL AND SUDDEN DRAWDOWN |
| B-7 | LAKE DARLING DAM STABILITY ANALYSIS - STEADY SEEPAGE MAXIMUM POOL AND SURCHARGE POOL |
| B-8 | LAKE DARLING DAM FOUNDATION STRENGTHS - LOWER UNIT |
| B-9 | LAKE DARLING DAM FOUNDATION STRENGTHS - UPPER UNIT |
| B-10 | LAKE DARLING DAM EXISTING EMBANKMENT - UNDISTURBED R AND S TESTS |
| B-11 | LAKE DARLING DAM EMBANKMENT FILL - REMOLDED Q, R AND S TESTS |
| B-12 | LAKE DARLING DAM - PRELIMINARY GEOLOGIC COLUMNS AND BORING LOG LEGEND |
| B-13 | LAKE DARLING DAM - BORINGS 74-51M THRU 74-53M, 74-62M AND 74-63M |
| B-14 | LAKE DARLING DAM - BORINGS 76-81M THRU 76-87M |
| B-15 | LAKE DARLING DAM - BORINGS 76-88M THRU 76-93M |
| B-16 | LAKE DARLING DAM - BORINGS 76-94M THRU 76-101M |
| B-17 | LAKE DARLING DAM - BORINGS 76-102M THRU 76-111M |
| B-18 | LAKE DARLING DAM - BORINGS 78-112M THRU 78-117M |
| B-19 | LAKE DARLING DAM - BORINGS 79-144M THRU 79-145M |
| B-20 | SOO LINE RAILROAD RELOCATION |
| B-21 | SOO LINE RAILROAD FOUNDATION STRENGTHS |
| B-22 | SOO LINE RAILROAD - BORINGS 64-9M, and 76-75M THRU 76-80M |
| B-23 | GRAND CROSSING RELOCATION |
| B-24 | STATE HIGHWAY NO. 28 RELOCATION |
| B-25 | STATE HIGHWAY NO. 5 RELOCATION |
| B-26 | STATE HIGHWAY NO. 5 REMOLDED STRENGTHS - GLACIAL TILL FROM RIGHT ABUTMENT |
| B-27 | STATE HIGHWAY NO. 5 FOUNDATION STRENGTHS |
| B-28 | STATE HIGHWAY NO. 5 - BORINGS 64-10M, 74-43M THRU 74-45M, TEST PITS 74-46TP THRU 74-48TP, AND BORINGS 74-49M AND 74-50M |

PLATES (con.)


| <u>Number</u> | <u>Item</u> |
|----------------------|--|
| B-29 | ECKERT RANCH - GENERAL PLAN |
| B-30 | ECKERT RANCH - BORINGS 83-7M THRU 83-9M |
| B-31 | MCKINNEY CEMETERY LEVEE - BORING 83-6M |
| B-32 | RENVILLE COUNTY PARK - GENERAL PLAN |
| B-33 | RENVILLE COUNTY PARK - BORINGS 83-1M THRU 83-5M |
| B-34 | GENERAL PLAN - MAJOR DOWNSTREAM WORKS |
| B-35 | JOHNSON'S ADDITION |
| B-36 | BROOKS ADDITION |
| B-37 | TALBOT'S NURSERY AND COUNTRY CLUB ACRES |
| B-38 | COUNTRY CLUB ACRES AND ROBINWOOD ESTATES |
| B-39 | KINGS COURT AND ROSTAD'S ADDITION |
| B-40 | TIERRECITO VALLEJO |
| B-41 | BURLINGTON TO MINOT LEVEES - BORINGS 74-1M THRU 74-11M |
| B-42 | SAWYER |
| B-43 | SAWYER - BORINGS |
| B-44 THRU B-65 | SOIL TEST DATA - LAKE DARLING DAM |
| B-66 THRU B-75 | SOIL TEST DATA - SOO LINE RAILROAD |
| B-76 THRU B-84 | SOIL TEST DATA - STATE HIGHWAY NO. 5 |

PHYSIOGRAPHY

1. The Souris River basin lies in the Drift Prairie section of the Central Lowland Physiographic province and the Coteau Du Missouri which forms the eastern border of the Great Plains physiographic province. Four major geologic and topographic features are present to further subdivide these major sections. These are the Missouri Escarpment, ground-moraine plain, the lake bed of glacial Lake Souris and the southwest portion of the Turtle Mountain (see Figure 1).
2. The entire length of the Des Lacs River valley and that portion of the Souris River valley upstream from Verendrye are in the area of the ground-moraine plain. Both valleys in this area were cut when the rivers were swollen with glacial meltwater and were subsequently aggraded to their present levels after the glaciers receded from the area. The existing condition in both valleys is, therefore, one of a small stream in an oversized valley. The floor of the Souris River valley lies 100 to 200 feet below the ground-moraine plain, and the valley walls are fairly steep-sided. The presence of short, intermittent drainages that head only a few miles from the river give the valley walls a slightly dendritic form with little or no correlative terrace development. The valley floor averages 3/4-mile in width and forms a relatively flat surface which is broken by a sinuous river channel, meander scars and small alluvial fans. The Des Lacs River valley is similar in form to the Souris River valley in the ground-moraine plain. The valley floor averages 1/2-mile in width and is incised up to 275 feet below the surrounding plains.
3. The Souris River valley downstream from Verendrye is formed in the glacial Lake Souris area. The valley form in this area varies drastically from that in the ground-moraine plain. The valley is 1/2 to 3 miles wide and is entrenched less than 100 feet below the surrounding plain. In places, a valley form is barely perceptible.
4. Except for the Missouri Escarpment and areas bordering stream valleys, much of the drainage pattern within the Souris River basin varies from poorly defined to noncontributing. Many of the noncontributing areas include numerous small depressions where surface water is trapped.
5. The only naturally wooded areas in the basin exist along drainages, the slopes of the Turtle Mountain, and some duned areas in the Lake Souris area. Elsewhere in the basin, the surface is unwooded except where trees have been planted near dwellings and for windbreaks. The basin is sparsely populated with most of the land surface used for pasture or cultivation.

GENERAL GEOLOGY

6. Glaciers invaded the Souris River basin several times during the Pleistocene Epoch. The most significant invasion was the Mankato Substage of the Wisconsin glaciation which laid down thick deposits of drift that obscured much of the preglacial topography. The valleys of the Souris and Des Lacs Rivers were carved, or enlarged, by great quantities of water supplied by the melting ice and were subsequently filled to their present levels as the flows diminished.



7. No sharp demarcation separates Recent from Pleistocene time. After the last retreat of glacial ice, conditions gradually gave way to those existing today. The glacial features have suffered little from erosion so that present topography is composed essentially of unaltered glacial forms. Integrated drainage has not yet been established in much of the basin.

8. Unconsolidated surface deposits in the basin are of two types: recent alluvium and Pleistocene glacial deposits. Recent alluvium comprises only a small portion of the surface materials and consists of clay, silt, fine-to-medium sand with minor amounts of coarse sand, and gravel. Significant alluvial deposits are restricted to the valleys of the Souris and Des Lacs Rivers where they generally exceed 50 feet in thickness. The glacial material consists primarily of morainal deposits and sediments of glacial Lake Souris. Morainal deposits are composed of an impervious, stoney clay till with thin seams, lenses, and channels of sand and gravel. This material occurs under the Coteau Du Missouri with an average thickness of 100 to 200 feet and varies from 50 to 300 feet in thickness throughout the ground-moraine plain and under the sediments of glacial Lake Souris. The till is often absent in the river valleys. Buried preglacial valleys, outwash channels, kames, eskers, overridden ice-contact deposits, river terrace deposits, diversion channels, and undifferentiated glaciofluvial deposits occur throughout the ground-moraine plain and contain a higher sand and gravel content than the glacial till. The deposits of glacial Lake Souris range in thickness from a feather-edge to more than 70 feet. Material in the Lake Souris area is predominantly silt and moderately to poorly graded sand with sand and gravel beach and other near-shore deposits.

9. The bedrock units exposed or forming the buried preglacial erosional surface in the Souris River basin are, in descending order, the Sentinel Butte, Tongue River and Cannonball Formations of the Fort Union Group of the Tertiary System and the Hell Creek and Fox Hills Formations of the Cretaceous System. Older Mesozoic and Paleozoic beds underlie these formations and consist primarily of shales, limestones, sandstones, siltstones, and evaporites with a total thickness of several thousand feet.

10. The Sentinel Butte Formation, the uppermost bedrock unit in the basin, is present only under the Coteau Du Missouri and is lithologically similar to the underlying Tongue River Formation. The Tongue River Formation is present in the western two-thirds of the basin and in the Turtle Mountain and underlies glacial and alluvial sediments in the proposed project areas. This formation is described in detail in the discussion of foundation materials. Exposures of the Cannonball Formation occur in the Souris River valley from Verendrye upstream to Sawyer. This unit is a marine deposit which consists of thin, alternate beds of sandstone, siltstone, and sandy shale. The total thickness of the uneroded Cannonball Formation is not known, but the thickness of exposed beds in the vicinity of Sawyer is approximately 40 feet. The underlying, or older, rock formations are below the influence of the proposed work and are, therefore, not discussed.

11. The structural geology of the Souris River basin has not been determined in detail. Regionally, the subsurface structure consists of south-westerly dipping Paleozoic beds truncated by Mesozoic beds that dip less

steeply to the southwest. The regional dip of all the beds is gentle and is obscured by local variations in some areas. Tertiary beds available for study at the surface exhibit local structural irregularities and lithologic variations that make detailed correlation and structural analysis questionable.

12. The basin is structurally stable and without tectonic disturbances of regional or local magnitude. Current seismic risk references show the basin to lie in zone 1 or a non-critical area that could expect only minor damage from any probable earthquake.

GROUND WATER

13. Groundwater is an important natural resource in the Souris River basin where its occurrence and quality vary with location and depth. Considerable detailed information on the ground-water conditions in most areas of the basin is available. The scope of this study, however, does not warrant a presentation of more than a summary of ground-water conditions.

14. Ground water in the basin is obtained from glacial deposits, recent alluvium and bedrock aquifers. Wells in the glacial deposits are developed in sand and gravel lenses or beds, debris-filled valleys, glacial outwash channels on the till plains, and glaciofluvial deposits in the river valleys. In a few places these aquifers will yield more than 500 gallons per minute of good quality water, but such yields are rare. In many places the aquifers are too thin, are of small areal extent, or the rate of natural recharge is too slow to provide sustained yields of more than a few gallons per minute. Shallow or surficial deposits of sand and river-valley aquifers generally produce water of good quality, but water from the more deeply buried aquifers commonly contains objectionable concentrations of iron, sulfate and dissolved solids.

15. Development of wells in recent alluvium is restricted to the river valleys. Water-bearing strata in the alluvium are generally thin and are not considered important sources of water.

16. Bedrock aquifers in the basin consist of the Cretaceous Dakota Group, Fox Hills and Hell Creek Formations, and Tertiary Fort Union Group. Water from the Dakota Group is generally saline and is used mainly for pressurizing oil fields. Water from the Fox Hills and Hell Creek is a soft, sodium bicarbonate or sodium chloride type and is not recommended for human consumption. Gas is present with the water in the Fort Union Group and basal drift aquifers in eastern Renville and western Bottineau Counties. When sufficient gas is present, it lifts the water in a well to the ground surface and causes the well to flow. This gas-lift phenomenon was once common in the area but has decreased appreciably with development of the aquifer.

17. Sufficient ground water sources have been developed throughout the basin to maintain adequate municipal and domestic supplies; although, in some cases the quality of the water in domestic wells probably does not

meet standards recommended by the U.S. Public Health Service. The largest user of water in the basin is the city of Minot which obtains adequate water supplies from the Souris River along with buried-channel and glaciofluvial aquifers known as the Minot, North Hill, South Hill, North-east buried-channel, Lower Souris and Sundre Aquifers. The combined aquifer system has a large areal extent and storage capacity, but unmanaged withdrawals could easily exceed natural recharge. Therefore, the aquifers must be properly managed to insure a continued supply of water for the future.

SITE TOPOGRAPHY, SUBSURFACE CONDITIONS, AND FOUNDATIONS MATERIALS

18. The topography and subsurface conditions for each site are presented in this report by site topographic maps showing the proposed structures and generalized foundation profiles that show the interpreted subsurface conditions. Foundation materials for all of the proposed structures may be classified in the broad categories of River Alluvium, Glacial Sediments or Tongue River Formation. Except for minor variations in the alluvium, the general properties of each category are similar at all sites; therefore, a discussion of the materials by category is adequate for this study and is presented in the following paragraphs.

19. RIVER ALLUVIUM

The River Alluvium was deposited during aggradation of the Souris and Des Lacs River valleys following the recession of glaciers from the area. Material in the Souris Valley averages over 100 feet thick with a maximum known thickness of 160 feet. This material is predominantly medium to high plasticity clays with occasional interbeds of fine sand and silty fine sand. Some of the more plastic clays resemble lacustrine clays and may have been deposited in temporary valley lakes. River Alluvium in the Des Lacs valley has a maximum known thickness of 70 feet and consists of interbedded silty sand, clay and silt with occasional beds of clean sand.

20. GLACIAL SEDIMENTS

Except for a sand and gravel terrace deposit at Lake Darling Dam, the glacial sediments consist almost entirely of heterogeneous sandy clay till. Scattered gravel and occasional cobbles or boulders, thin beds, lenses, and channels of sand occur throughout the till. The sand and gravel terrace at Lake Darling Dam is located on the left abutment and exhibits a wide range of grain sizes, varies from silty to clean and has an abundance of cobbles and boulders.

21. TONGUE RIVER FORMATION

The Tongue River Formation is a terrestrial deposit laid down in lakes, swamps and broad floodplains of eastward flowing rivers during the Paleocene Epoch of the Tertiary Period. The formation is characterized by vertical and horizontal variations in lithology consisting essentially of mixtures of clay-, silt- and sand-sized particles. These constituent materials not only occur in numerous combinations but also exhibit sedi-

mentary structures ranging from finely laminated to massive. In addition, a change from one dominant particle size or sedimentary structure to another is often gradational or subtle so that classification into correlative units is difficult. The formation is often described as an "immature" rock that exhibits both the properties of a soil and the properties of a rock. Rock terms were used for this study based on apparent preference for these terms in the literature and previous usage with other Corps of Engineers investigations in the same formation. A classification system was developed for the Tongue River Formation which consists of five major lithologic types--shale, laminated siltstone, homogeneous siltstone, sandstone and carbonate concretions. The lithologic units are described on Plate B-12. The engineering properties and considerations are summarized as follows:

22. Permeability

The primary permeability of all units except the cleanest sandstones is so low the units are considered impervious. The primary permeability of the best sandstone encountered is estimated at less than 7×10^{-4} cm per second. Secondary permeability is expected to be a significant consideration in lignite beds. Fractured lignites account for drilling fluid losses and are sources of springs in outcrop areas. A low frequency of secondary interstices observed in the drill cores suggests that water problems will be restricted to lignites which may serve as seepage paths from reservoirs or sources of water if encountered in excavations.

23. Faulting

Several fault planes were identified as slickensided planes in the drill cores. More probably exist but were not identified due to difficulty of finding them without destroying the core samples. The depth of previous erosion in the valley and steep erosional surface on the buried Tongue River Formation indicate conditions favorable for the development of Proglacial slump blocks which parallel the trend of the valleys. Fault planes should, therefore, be expected in any excavation near river valley walls.

24. Jointing

A low frequency of jointing and fracturing was encountered in the borings and is considered a good representation of the subsurface condition. The presence of stress-relief joints that parallel the valley trend should, however, be expected in any excavation near a valley wall.

25. Excavation Properties

All material except cemented sandstone and limestone (carbonate concretions) can be excavated easily by ripping or can be tunneled by machine. Structural excavations, with the same exceptions, can be cut to close tolerance with a coal saw.

26. Bearing Capacity

The most critical unit as far as bearing capacity is concerned is

shale. It is recommended that unweathered shale be considered to have an allowable bearing capacity of 4 tons per square foot. The bearing capacity of weathered shale is considered to be equivalent to the overlying glacial till.

27. Rebound

The Tongue River beds exist in an over-consolidated state due to previous sediment and ice loads greatly in excess of the load exerted by the existing cover of sediments. For this reason, rebound of the Tongue River Formation in deep excavations has caused problems on other projects. Rebound must be considered a potential problem in any major excavation.

28. Slope Stability

Slope failures in the Tongue River are evident in the region but are generally due to steepening of a stable slope by erosion or excavation. Designed slopes in the Tongue River Formation at Garrison Dam have reportedly remained stable for 27 years. The most critical element anticipated to cause slope stability problems at the proposed facilities is exposure of the glacial till-Tongue River contact.

29. Foundation Protection

Protection of structural foundations is necessary to prevent deterioration of the foundation between the time of excavation and concrete placement. This is expected to be especially critical for laminated siltstone and shale. Initial underexcavation with excavation to final grade immediately before concrete placement is recommended for these units.

WATER TABLE

30. An accurate water table has not been determined at any of the proposed sites. An inferred water table is, therefore, shown on the foundation profiles and is based on limited water level data from borings and the base of the zone of oxidation. The water table is inferred from these data to be quite high and in most cases well above the base of excavation. Ground water is, however, not expected to be a major problem in any excavations due to the overall low permeability of the materials. Minor discharge from sand and gravel seams in the till and occasional sandstone beds in the Tongue River Formation is expected. Fractured lignite seams in the Tongue River should cause the greatest water problem in excavations but are not expected to be a significant concern. The delineation of the water table and water-bearing characteristics of the more pervious beds and lignite seams will be refined in the investigations for detailed design.

SOURCES OF STONE AND AGGREGATE CONSTRUCTION MATERIALS

31. Concrete aggregate of acceptable quality can be produced locally from gravel pits in glacial terrace deposits along the Souris and Des Lac Rivers. The material must, however, be carefully processed to remove iron-oxide concretions and shale.

32. Riprap and bedding are available locally. Riprap must be obtained from field stone piles of glacial boulders within a radius of 15 miles from the projects and from oversized material screened from gravel production. The supply of boulders in the area is being consumed and will eventually be depleted. At that time, riprap would have to be shipped in from outside the area. The closest reliable source of quarried stone is Ortonville, Minnesota, a distance of 400 miles. Bedding material can be produced from local gravel pits.

ECONOMIC GEOLOGY

33. Mineral resources in the Souris River basin that either have economic value, have had economic value or have economic potential include lignite, sand and gravel, glacial till, glacial boulders, brick clay, petroleum, natural gas, and salt. Those resources within the reasonable area of influence of the proposed facilities are sand and gravel, glacial till, glacial boulders and petroleum.

34. SAND AND GRAVEL

Sand and gravel deposits are abundant throughout the basin. Commercial operations are usually developed in river-terrace and diversion-channel deposits. Ice-marginal and outwash-channel deposits are next in importance. Kames, eskers, and overridden ice-contact deposits contain sufficient material for small, local projects. The southern part of the Lake Souris area contains huge quantities of sand that are essentially undeveloped. Material from nearly all deposits is adequate for road gravel, and material from most larger deposits can be processed for concrete aggregate. Except for the sand and gravel consumed in construction, the proposed projects would have no effect on future development of sand and gravel resources.

35. GLACIAL TILL

Sandy gravelly clay till is available in unlimited quantities. Its value as a resource would, therefore, not be affected by the proposed projects.

36. GLACIAL BOULDERS

Glacial boulders are scattered on the surface throughout the Coteau Du Missouri, ground-moraine plain, and river terraces. The boulders are the only source of riprap in the basin and must be collected from scattered piles cleared from farmers' fields or where they are naturally abundant on the surface of uncultivated areas. Stockpiles of oversized material screened from the numerous gravel operations in the basin are also important sources of boulders. Construction of the proposed projects would consume a significant amount of the boulders within a radius of several miles.

37. PETROLEUM

Producing oil wells have been developed near the Souris River valley

in the vicinity of Lake Darling. Further development of oil resources is possible near the proposed projects. Such development would, however, be compatible with the construction and operation of the facilities as proposed.

SUBSURFACE INFORMATION AND TESTING

38. Borings have been taken at the Lake Darling Dam site, as well as at the following sites:

Below Lake Darling Dam

- 1) Johnson's Addition
- 2) Brooks' Addition
- 3) Talbot's Nursery
- 4) Country Club Acres and Robinwood Estates
- 5) King's Court and Rostad's Addition
- 6) Tierrecito Vallejo
- 7) Sawyer

Above Lake Darling Dam

- 1) Eckerts Ranch
- 2) Soo Line Railroad Crossing
- 3) Highway 5 Crossing
- 4) McKinney Cemetery
- 5) Renville County Park

To date no borings have been taken at the State Highway 28, FAS 3809 (Old FAS 729) and FAS 3828 (Old FAS 471) road raises, or at the Fish and Wildlife Service's wildlife refuge dams. Subsurface information, testing and improvements for Velva, North Dakota, have been presented in Lake Darling Flood Control Project, Souris River, North Dakota, DM No. 4, Feature, Velva Improvements, dated November 1982, and are, therefore, not discussed in this appendix.

39. A total of 82 borings and test pits have been taken at the various structure sites. The locations of the borings are shown on the plans of the individual structures. Logs of the borings for each structure are presented in order of increasing boring numbers on plates following the plan for each structure or each combination of structures.

40. Laboratory tests performed to date include in situ moisture contents, liquid and plastic limits, mechanical analyses, undisturbed and remolded strengths, consolidation and compaction. In situ moisture contents and liquid and plastic limits are shown on the boring logs. Other individual laboratory test results are presented as follows: Lake Darling Dam, Plates B-44 through B-65; Soo Line Railroad, Plates B-66 through B-75; and State Highway 5, Plates B-76 through B-84.

41. The individual strength test results were used to develop summary strength plots. The plates showing the summary strength plots for the materials at a given structure are grouped with other plates that pertain to that particular structure.

LAKE DARLING DAM

42. GENERAL

Currently, the top of dam elevation is 1606.0, the upstream slope is approximately 1V on 2.7H, and the downstream slope is approximately 1V on 2.2H. The existing Lake Darling Dam has an ungated primary spillway on the left abutment and an ungated, grass-lined, emergency spillway on the right abutment.

43. The existing Lake Darling Dam will be extensively modified. The top of the dam will be raised 8 feet, from elevation 1606.0 to elevation 1614.0. A new gated spillway with low flow outlets located in the gate piers will be constructed on the left abutment replacing the old outlet works and two ungated spillways.

44. The plan of the Lake Darling Dam is shown on Plate B-1. Foundation conditions at the site are shown on the geologic profiles on Plates B-3 and B-4.

45. EMBANKMENT DESIGN

A typical embankment section is shown on Plate B-2. The embankment will have a top width of 40 feet, the same width as the existing embankment, and will be surfaced with a 24-foot wide paved roadway. The existing upstream slope, which averages 1V on 2.7H, will be flattened to 1V on 3.75H to meet sudden drawdown criteria. Rockfill will be used to flatten the underwater portion of the slope. To minimize the rockfill section the centerline of the raised embankment has been moved downstream of the existing embankment centerline. Above elevation 1600 much of the existing riprap is undersized, and coverage of the slope is inadequate. Existing riprap in this zone will be removed and placed in the rockfill section. In general, the embankment contact areas will be stripped to either a 6-inch or 12-inch depth as considered appropriate. The upstream half of the crest of the existing dam will be stripped to a depth of 2 feet to assure good contact with the impervious fill in the upstream portion of the existing embankment. A sand drain will be incorporated in the modified embankment, as shown on Plate B-2. The downstream slope of the existing embankment, which averages 1V on 2.2H, will be flattened to 1V on 3.75H. A berm will be placed on the downstream slope beginning at elevation 1603.3, extending downstream at a 1V on 50H slope, for 180 feet. The large berm provides a disposal area for excess excavation from the new spillway on the left abutment, and is not required for stability.

46. SEEPAGE CONTROL

Old drawings indicate that the existing embankment was designed as a zoned embankment. The upstream 40± percent of the embankment consisted of relatively impervious fill and the downstream 60± percent of the embankment consisted of pervious bank-run rock, gravel and sand. Stripping of the original ground surface to an unknown depth to be determined by the engineer was required upstream of the embankment centerline. No stripping was required downstream of the embankment centerline. About 45 feet up-

stream of the centerline a muck trench (cut-off trench) was excavated into the foundation soils. The bottom width of the trench was 6 feet but the depth was to be determined by the engineer. In the river channel section the trench was about 75 feet upstream of the centerline and a wood sheet-pile cutoff was driven on the trench centerline. Subsequent to the original construction, pervious fill was placed on the upstream slope to increase the top width of the dam from 31 feet to 40 feet and to provide a uniform upstream slope on which to place new riprap. Borings taken at the downstream shoulder of the dam encountered both pervious and impervious fill, indicating that the actual embankment zoning was not as pure as shown on the drawings. On the basis of existing drawings alone, it is difficult to judge the adequacy of the seepage cutoff in the existing embankment and foundation soils. A somewhat higher quantity of seepage than would normally be expected from a well designed earth dam has been noted during field inspections of the embankment both during and following recent floods, especially in the reach between the outlet works and the right abutment. However, there has been no evidence of seepage exiting on the downstream slope of the embankment nor has there been any evidence of material transport or other seepage-related instability. Borings along the embankment alignment indicate that the near surface foundation soils in the valley consist of SM or finer materials. One relatively thin SP layer, considered to be discontinuous, was encountered in boring 76-98M at a depth of about 10 feet beneath the existing embankment. No highly pervious zones that would have a direct connection to the pool are evident. The proposed modification of the embankment will not significantly affect the existing quantity of seepage, but better control of the seepage will be provided by the internal sand drain and toe drain. In addition the seepage path through the foundation soils to the toe of the modified embankment will be increased more than 2-1/2 times. Planned seepage control for the modified embankment will, therefore, consist of assuring good contact between the upstream relatively impervious zone of the existing embankment and new impervious fill placed to raise the embankment. In addition, the internal sand drain shown on Plate B-2 will be constructed to control seepage through the embankment and/or foundation soils. A perforated pipe toe drain will be installed near the downstream end of the horizontal sand drain to permit collection and monitoring of seepage. The pipe toe drain will discharge either into the spillway discharge channel or into the old river channel downstream of the modified embankment. A short section of cut-off trench will be required on the left abutment to cut off the sand and gravel terrace deposit on the left abutment shown on Plate B-3.

47. STABILITY

Available soil strength data have been summarized on Plates B-8 through B-11. The preliminary design strength parameters and, where necessary, assumed design strength parameters were used to perform stability analyses of the modified valley embankment section. The strength parameters used are shown on Plate B-5.

48. The stability analyses were performed using the Corps' Computer Library Program 10013 (old St. Paul District 741-X6-F5030) entitled, "Slip Circle Slope Stability with Side Forces." Results of the stability

analyses have been summarized on Plates B-5 through B-7. Any further stability analysis will be completed at a later date for inclusion in the Lake Darling Dam Embankment Feature DM.

49. SETTLEMENT OF EMBANKMENT FOUNDATION SOILS

The maximum depth of the river alluvium is about 140 feet at the Lake Darling Dam site, and some of the river alluvium is made up of highly compressible (CH) clays. Preliminary settlement calculations were completed for GDM No. 2, "Flood Control Burlington Dam," at two locations beneath the modified embankment proposed in that report. The computations indicated that for the modified embankment, 20 inches of settlement could occur at the downstream toe of the existing embankment. This indicates that for the currently proposed modified embankment settlements on the order of 20 inches will occur. Required overbuild will, therefore, be in the range of 12 to 18 inches. Revised settlement calculations will be presented in the Lake Darling Dam Embankment Feature DM. The settlement will be sufficiently large to preclude the placement of concrete structures in the valley. The new concrete gated control structure will, therefore, be placed in the left abutment so that it can be founded on the overconsolidated Tongue River formation. The existing outlet works, which is located in the valley, will be removed once the new control structure is operational. Since the existing outlet supplies water to Ponds A, B, and C just downstream of the dam, a new water supply structure will be required. The new structure will be a gated, 42-inch diameter, reinforced concrete pipe which will be located in the right abutment to avoid settlement-related problems.

50. CONTROL STRUCTURE

The topography and the foundation conditions at the site favor placing the new control structure in the left abutment. The geologic profile at the centerline of the structure is shown on Plate B-4. The structure will be founded on the overconsolidated Tongue River Formation. Pervious layers near the base of concrete structure will be drained with pipes and/or sand drains to prevent uplift pressures from developing beneath the structure. Lignite seams near the base of concrete structure may require excavation or grouting for structural reasons. Rebound of the overconsolidated Tongue River Formation in the structure excavation is not expected to be a significant problem because of the relatively shallow depth of the excavation. However, the potential for rebound will be investigated further for the Feature DM.

51. PROPOSED DISTRIBUTION OF REQUIRED EXCAVATION

The total required excavation for the control structure and associated approach and discharge channels will be about 746,830 cubic yards. The required excavation will consist primarily of glacial till and Tongue River materials; however, some river alluvium will be excavated at the ends of the approach and discharge channels. Most of the glacial till and Tongue River materials from the excavations will be suitable for embankment construction. Some of the glacial till and Tongue River material and probably all of the river alluvium will be too wet to use in the

embankment and will have to be wasted. The amount of wet material is estimated to be about 20 percent of the total required excavation, or about 149,370 cubic yards. The remaining 597,460 cubic yards of required excavation is considered usable for embankment construction and backfill for the new structures. Required fill quantities include 25,460 cubic yards of backfill, 134,270 cubic yards of random fill and 227,900 cubic yards of impervious fill. Total required fill is, therefore, 387,630 cubic yards. The remaining 359,200 cubic yards of required excavation will be used to construct a berm on the downstream side of the embankment as shown on Plate B-2. The proposed distribution of materials is preliminary and may be changed following completion of the next phase of the boring and testing program at this site.

52. CONSTRUCTION SEQUENCE AND DIVERSION PLAN

The following preliminary construction sequence has been developed for modification of Lake Darling Dam. The existing secondary spillway on the right abutment will be enlarged, with concrete and sheetpile crest protection installed, so that flow can be diverted through the secondary spillway and the existing low flow outlet while the new control structure is being built on the left abutment. Following modification of the secondary spillway, the primary spillway will be cofferdamed off to permit construction of the new control structure and as much of the new discharge channel as practical. Excavation for the new spillway and discharge channel will be used to complete the required embankment modifications to the maximum extent practical. When the new control structure is completed, the downstream cofferdam will then be removed and the discharge channel completed. The upstream cofferdam will then be removed and the approach channel completed. The new control structure will then be operational and diversion will no longer be required. A cellular sheetpile cofferdam can then be installed around the upstream end of the existing low flow structure, the structure excavated, removed, and the excavation backfilled. Removal of the cellular cofferdam and completion of the embankment and right abutment approach roads can then be accomplished.

SOO LINE RAILROAD RAISE

53. GENERAL

The existing Soo Line railroad embankment across Lake Darling will be raised about 3 feet. The subgrade elevation of the raised embankment will be 1607.0 so that with the placement of ballast and trackage the top of rail will be 1608.0. The centerline of the raised embankment has been located downstream of the existing embankment centerline to permit the existing track to remain in service during construction. The existing bridge, located in the river valley, will be replaced with a new bridge which, because of foundation conditions, has been located in the right abutment. The new bridge will be constructed on the downstream side of the track so that service can be maintained on the present track during construction. The plan, profiles, and sections of the proposed modifications are shown on Plate B-20.

54. EMBANKMENT DESIGN

The raised embankment will be constructed adjacent to the downstream slope of the existing embankment. The riprap on the downstream slope of the existing embankment will be salvaged to the extent practical and used on the raised embankment. Because the embankment crosses Lake Darling, which has a conservation pool elevation of approximately 1596, underwater placement of the lower portion of the fill will be required. Pervious fill will, therefore, be used to construct that portion of the embankment below elevation 1597. Above elevation 1597 the embankment will be constructed of random fill. The upstream slope of the raised embankment will be 1V on 3H above the top of existing embankment and will be protected with 15 inches of riprap placed on 9 inches of bedding. The downstream slope of the raised embankment will be 1V on 3-1/2H and will be protected with 18 inches of riprap placed on 15 inches of bedding.

55. STABILITY

Existing borings at the site indicate that the river alluvium has a maximum depth of about 55 feet and that the majority of the river alluvium consists of high plasticity (CH) clays. Available strength data for the river alluvium has been summarized on Plate B-21. End of construction and sudden drawdown stability analyses were performed for an embankment constructed to elevation 1610.0 (for the Phase II GDM No. 2, entitled, "Flood Control Burlington Dam"). The currently proposed embankment is 3 feet lower and thus will also meet criteria for those two stability cases. A complete stability analysis will be furnished in the Feature DM on the Soo Line Railroad Embankment.

56. SETTLEMENT OF EMBANKMENT FOUNDATION SOILS

The majority of the river alluvium is high plasticity (CH) clays. These clays are highly compressible, but the loading and other factors are such that settlement of the embankment will be relatively small. Since the existing embankment occupies about 45 percent of the volume of the total embankment, and since 5 to 7 feet of the pervious fill will be placed underwater, effective stress increase in the foundation soils will be significantly less than if the complete embankment was constructed at one time and underwater placement was not involved. Under present conditions the river alluvium is also preconsolidated to some extent because of the reduction in effective stress caused by the submergence of the upper zone of the river alluvium by the Lake Darling pool. This preconsolidation also helps to reduce the settlement. Calculations indicate that construction of the raised embankment will cause about 5 inches of settlement at the centerline of the existing embankment and about 12 inches of settlement at the centerline of the raised embankment. The settlement is considered sufficient to justify locating the new bridge in the right abutment where the fill height will be less and the bridge can be founded on the much stronger glacial till.

57. PROPOSED DISTRIBUTION OF REQUIRED EXCAVATION AND BORROW

The 109,510 cubic yards of pervious fill required to construct the portion of the main embankment below elevation 1597.0 can be obtained from a sand and gravel terrace deposit on the right bank just upstream of the embankment. The 288,700 cubic yards of required excavation contains sufficient glacial till to provide the 105,810 cubic yards of random fill required to complete the main embankment. Present plans are to waste the 182,890 cubic yards of excess excavation along the right abutment. However, consideration will be given to the possibility of using some of the excess excavation as random fill for the State Highway 28 road raise which is about 1 mile upstream of the Soo Line crossing.

ROAD RAISES - STATE HIGHWAY 28 AND FAS ROUTES 3809 AND 3828

58. These road relocations have been grouped together for discussion purposes since the raises will be relatively small and embankment designs will be similar. FAS 3809 (old FAS 729) and State Highway 28 are north-south roads that cross the Souris River valley 3 miles north of State Highway 5 and 1 mile north of the Soo Line crossing, respectively. FAS 3828 (old FAS 471) is an east-west road that crosses the Souris River valley 2-1/2 miles south of the Soo Line crossing. State Highway 28 and FAS 3828 will be raised to elevation 1607.0 to decrease the frequency of inundation. The maximum embankment raise will be about 2 feet for State Highway 28 and about 5 feet for FAS 3828. The centerlines of the raised embankments will coincide with the centerlines of the existing embankments to the maximum extent practical in order to minimize settlements and fill quantities. Although subsurface data at these sites is lacking, it is believed that 1V on 3H slopes will provide stable embankments and that settlements caused by the relatively small raises will not be excessive. The slopes of the embankments will be riprapped to provide protection from wave action. Fill for the embankments will be obtained from borrow areas since there will be no significant amount of required excavation at the road raises. Random fill can be obtained from glacial till deposits at either end of the road raises. Pervious fill will be required for those portions of the State Highway 28 and FAS 3828 embankments below elevation 1597 since the two roads cross Lake Darling. The pervious fill can be obtained from sand and gravel terrace deposits at the right abutment of both raises. A new bridge will be constructed to replace the existing bridge on State Highway 28. On FAS route 3828 the superstructure of the existing bridge will be raised to elevation 1608.5. Prior to the preparation of the Feature DM on these road raises, boring and testing will be required to obtain the soil parameters needed for final design of the embankments and the new bridge on State Highway 28. The plan view for State Highway 28 and FAS route 3828 are shown on Plates B-23 and B-24, respectively. These two roads will not be scheduled for simultaneous construction because of their proximity to each other and the need to provide alternate routes for construction detours. Improvements of FAS route 3809 will consist of placing 4 inches of new stabilized aggregate surfacing and placing riprap and bedding on the existing embankment slopes to provide wave protection when Lake Darling is high. Additional design and analyses will be included in the Feature DMs on the road relocations.

STATE HIGHWAY NO. 5 ROAD RAISE

59. State Highway 5 is the major east-west highway crossing over the Souris River in the reach between the Canadian border and Lake Darling Dam. Present plans call for raising the crossing from about elevation 1605.0 to a minimum elevation of 1607.5. Two spans will be added to the existing bridge and the bridge deck will be raised to provide a roadway surface elevation of 1610.5. It is assumed that an older Highway 5 bridge, which is still in place just upstream of the present bridge, can be used to detour traffic around the present bridge while required modifications are made. The remaining embankment will be raised by raising 1/2 of the embankment at a time, thus keeping one lane open for traffic. The plan, profile, and sections for the raise are shown on Plate B-25. The embankment will be constructed of random fill and will have a top width of 40 feet with 1V on 3H side slopes. Prior to fill placement the existing ground will be stripped 6 inches. Upstream and downstream slope protection will consist of 18 inches of rip-rap placed on 9 inches of bedding. The existing pavement will be removed and replaced by a bituminous paved surface 32 feet wide. Existing borings at the site indicate that the river alluvium has a maximum depth of 60 feet and consists primarily of low to high plasticity clays. Available strength data for the river alluvium has been summarized on Plate B-27. The random fill for the embankment will consist of glacial till obtained from a borrow area on the right abutment. Remolded strength parameters are summarized on Plate B-26. A partial stability analysis was run on this embankment in Phase II GDM No. 2, entitled, "Flood Control Burlington Dam," which indicated satisfactory factors of safety for the embankment at a top elevation 1626.0. Since plans currently call for an embankment with a top elevation that varies from 1607.5 to 1610.5, no stability problems are anticipated. The reference cited previously indicated that 20 inches of settlement would occur if the embankment were raised to elevation 1626.0 (a 21-foot raise). Current plans call for a raise of only 2.5 to 5.0 feet, and thus much smaller settlements are anticipated. Detailed analyses of the embankment will be furnished in the Feature DM on Highway 5.

60. A total of 38,960 cubic yards of random fill is required to construct the embankment and detour. Only about 10,920 cubic yards of this total will be obtained from required excavation. The remaining 28,040 cubic yards of random fill will be obtained from a borrow area on the right abutment. About 88,680 cubic yards of channel excavation will be required for the new bridge; however, the channel excavation will be primarily river alluvium that is too wet for use as random fill. Channel excavation that is unsuitable for embankment fill will be disposed along the right valley wall upstream and/or downstream of the embankment.

ECKERT RANCH AND MCKINNEY CEMETERY LEVEES

61. These two sites have been grouped together for discussion purposes since the levee designs at each site will be similar. Plate B-29 shows the proposed plan for Eckert Ranch, and Plate B-31 shows the plan,

boring log, and section for McKinney Cemetery. Borings for Eckert Ranch are shown on Plate B-30. The Eckert Ranch site is on the left side of the valley about 2 miles north of the Lake Darling Dam, while the McKinney Cemetery is located 1/2 mile south of State Highway No. 5. Each site will be protected from the increase in the Lake Darling pool by a levee. The levees will have a top elevation of about 1610.0, with 1V on 3H side slopes. Although some subsurface data has been obtained for each site, no testing is available. Consequently, no stability or settlement analyses have been completed. However, it is believed that 1V on 3H slopes will provide stable embankments and that only minor settlements will occur. The riverward slopes of the levees will be riprapped to provide protection from wave action. Required borrow will be obtained from the glacial till deposits on the valley walls. Further testing, design and analysis will be presented in the Feature DM for each site.

RENVILLE COUNTY PARK


62. Renville County Park is located about 2-1/2 miles north of State Highway No. 5. Present plans are to protect the area with a levee and a cut-off channel. The plan for Renville County Park is shown on Plate B-32. The levee will be constructed to elevation 1610.0, with 1V on 3H side slopes. The riverward levee slope will be riprapped to provide protection from wave action. Slopes of the cut-off channel will be 1V on 3H, and a control structure will be located at the upstream end of the cut-off. Five borings, shown on Plate B-33, have been taken along the proposed alignments. They indicate that much of the material excavated from the cut-off channel can be used to construct the levee. Excavated material that is unsuitable for levee construction will be disposed along the cut-off channel. Required borrow will be obtained from glacial till deposits on the left valley wall. No stability or settlement analyses have been completed to date, but experience indicates that the 1V on 3H slopes will be stable, and settlements will be relatively minor. Further testing, design and analysis will be presented in the Feature DM.


BURLINGTON TO MINOT LEVEES

63. Several residential areas below Lake Darling will require protection from the discharges of the reservoir under the present operation plan. These sites are as follows:



- a. Johnson's Addition
- b. Brooks' Addition
- c. Talbot's Nursery
- d. Country Club Acres
- e. Robinwood Estates
- f. Kings Court
- g. Rostad's Addition
- h. Tierrecito Vallejo
- i. Sawyer

Plans for sites 1 through 8 are shown on Plates B-34 through B-40. The plan for site 9 is shown on Plate B-42. Each site will be protected with a levee with 1V on 3H side slopes. Some borings have been taken at each site and are shown on Plates B-41 and B-43. There is no test data available, therefore, no stability analyses or settlement computations have been performed. However, past experience in the area indicates that the embankments will be stable and settlements will be relatively minor. Required borrow for construction of the levees can be obtained from the glacial till deposits on either valley wall. Further boring, testing, design and analysis will be completed for each site in the appropriate Feature DM.





| | | |
|---|---------------------------------|----------|
| DESIGNATION | DATE | APPROVED |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | |
| DESIGNED BY L.H.B. | DESIGN MEMORANDUM NO. 3 GENERAL | |
| DRAWN BY J.M.J. | FLOOD CONTROL - LAKE DARLING | |
| CHECKED BY M.M.B. | SOURIS RIVER, NORTH DAKOTA | |
| SUBMITTED BY <i>[Signature]</i> | LAKE DARLING DAM | |
| APPROVED <i>[Signature]</i> | GENERAL PLAN | |
| DATE: JUNE 1963 | | |
| AS SHOWN | DATE | |
| DRAWING NUMBER RI-R-5/700 | | |
| SHEET OF | | |



PMF TAILWATER EL 1598.3

EXISTING GROUND
WIDTH VARIES FROM 255.0 TO 460.0

RIPRAP TERMINATES AT STATION 9+00 AS PER DETAIL B

2' RIPRAP ON 6" BEDDING

DETAIL A


ELEVATION VARIES
AT ELEVATIONS LESS
THAN EL 1601.3 RIPRAP WILL
TERMINATE AS IN DETAIL A

EL 601.3

TYPICAL DISCHARGE CHANNEL SECTION
SCALE AS SHOWN BELOW
(SECTION TAKEN LOOKING U/S)

EL VARIES

DETAIL 'A'



DETAIL 'B'

BASE AND 6" SUBBASE COURSE

180' 0"

4" TOPSOIL AND SEED

BERM FILL

5' 0"

FINGER DRAINS, 10" WIDE,
50' ON CENTER

EL 1599.7

PMF TAILWATER EL 1594.3

15" RIPRAP ON 6" BEDDING

18" PERFORATED CMP PIPE TOE DRAIN,
MANHOLE AT 300' 0" INTERVALS
PLASTIC FILTER CLOTH
DEPTH VARIES (4' 0" MIN)

SECTION

FEET

TOPSOIL AND SEED

10.0

35' 0"

3/4" BITUMINOUS PAVEMENT ON 6" BASE AND SUBBASE COURSES
ROAD 24' WIDE WITH 5' SHOULDERS

EL 1614.0

4" TOPSOIL AND SEED

RANDOM FILL

ELEVATION VARIES

RANDOM FILL AS REQUIRED

6" STRIPPING

TYPICAL SECTION - LEFT ABUTMENT APPROACH ROAD


SCALE AS SHOWN ABOVE




| | | | |
|---------------|--------|--|-----------|
| DESIGNED BY: | LHB | DESIGN MEMORANDUM NO. 3 | GENERAL |
| DRAWN BY: | LHB | FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA | |
| CHECKED BY: | M.M.B. | TYPICAL SECTIONS - LAKE DARLING DAM AND SPILLWAY | |
| SUBMITTED BY: | | APPROVED: | DATE: |
| | | | JUNE 1983 |
| | | AS SHOWN | DATE TO |
| | | DRAWING NUMBER RI-R-5/701 | |
| | | SHEET OF | |

17 ATT 3-7



2







100 0 100 200
HORIZONTAL SCALE IN FEET


NOTES:

1. Profile is viewed looking downstream.
2. Boring locations are shown on Plate B-1.
3. See Plate B-12 for Boring legend.
4. The water table is shown on the profile by the symbol . The water table is inferred based on limited water-level data from borings and the base of the zone of oxidation.
Water levels in the borings marked with an asterisk indicate pervious water-bearing seams in the impervious till.
Borings with no water level indicated and not shown as dry are those in which no water levels were determined.
5. Distance of borings upstream and downstream from the profile line are indicated by U.S. and D.S.
6. Foundation or excavation limits shown by this symbol .

| | | | |
|---|----------------------------|---------|----------|
| DESIGNED BY | DESCRIPTION | DATE | APPROVAL |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | |
| DESIGNED BY R.L.W. | DESIGN MEMORANDUM NO 5 | GENERAL | |
| DRAWN BY J.H.L. | FLOOD CONTROL | | |
| CHECKED BY R.L.W. | LAKE DARLING, NORTH DAKOTA | | |
| SUBMITTED BY | LAKE DARLING DAM | | |
| APPROVED | SUBSURFACE PROFILE | | |
| | EMBANKMENT CENTERLINE | | |
| | DATE | | |
| | JUNE 83 | | |
| | AS SHOWN | | |
| | DRAWING NUMBER | | |
| | RI-R-5/702 | | |
| | PLATE NO. B-3 | | |



100 0 100 200
HORIZONTAL SCALE IN FEET



NOTES:

1. Foundation and excavation limits shown by dashed lines.
2. Water table explained on plate B-3



100 0 100 200
HORIZONTAL SCALE IN FEET



| | | | | | |
|---|--|--|--|------|----------|
| DESIGN | | SUBMITTAL | | DATE | APPROVAL |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | | | |
| DESIGN MEMORANDUM NO. 3 | | GENERAL | | | |
| FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA LAKE DARLING SUBSURFACE PROFILE SPILLWAY CENTERLINE | | DATE: JUNE 1963 | | | |
| DRAWN BY: R.L.W. CHECKED BY: J.M.J. SUBMITTED BY: R.L.W. APPROVED BY: [Signature] DATE: [Signature] | | SHEET AS SHOWN DRAWING NUMBER RI-R-5/703 SHEET OF | | | |

PLATE NO. B-4

2



SOIL PARAMETERS


| SOIL DESCRIPTION NO. | UNIT MOIST | WEIGHTS SATURATED | O TEST | | R TEST | | S TEST | | (R-S)/2 | |
|-------------------------|---------------|----------------------|-----------------------|---------------------|----------------------|---------------------|--------------------|---------------------|----------------------|----------------------|
| | | | C (PSF) | φ (DEG) | C (PSF) | φ (DEG) | C (PSF) | φ (DEG) | C (PSF) | φ (DEG) |
| 1 NEW EMBK. FILL | 126.0 | 133.0 | 1730.0 ⁽¹⁾ | 2.0 | 200.0 | 12.0 | 0.0 | 29.5 | 100.0 | 20.75 |
| 2 EXISTING EMBK. FILL | 118.0 | 123.0 | 1300.0 ⁽¹⁾ | 4.3 ⁽¹⁾ | 640.0 | 11.7 | 0.0 | 29.5 | 320.0 | 20.60 |
| 3 ROCKFILL | 135.0 | 135.0 | 0.0 ⁽²⁾ | 36.0 ⁽²⁾ | 0.0 ⁽²⁾ | 36.0 ⁽²⁾ | 0.0 ⁽²⁾ | 36.0 ⁽²⁾ | 0.0 ⁽²⁾ | 36.00 ⁽²⁾ |
| 4 UPPER UNIT-ALLUVIUM | 123.0 | 123.0 | 700.0 | 0.0 | 560.0 | 23.0 | 0.0 | 30.0 | 280.0 | 26.50 |
| 5 LOWER UNIT-ALLUVIUM | 24.0 | 124.0 | 1100.0 | 0.0 | 1120.0 | 11.0 | 0.0 | 30.0 | 560.0 | 20.50 |
| 6 BERM FILL | 109.0 | 122.0 | 500.0 ⁽²⁾ | 0.0 ⁽²⁾ | 500.0 ⁽²⁾ | 0.0 ⁽²⁾ | 0.0 ⁽²⁾ | 22.0 ⁽²⁾ | 250.0 ⁽²⁾ | 11.00 ⁽²⁾ |
| 7 SAND | 130.0 | 130.0 | 0.0 ⁽¹⁾ | 30.0 ⁽¹⁾ | 0.0 ⁽²⁾ | 30.0 ⁽²⁾ | 0.0 ⁽²⁾ | 30.0 ⁽²⁾ | 0.0 ⁽²⁾ | 30.00 ⁽²⁾ |

1 THESE SOIL PARAMETERS ARE ASSUMED VALUES BASED ON REMOLDED SOIL TESTS (CONDUCTED FOR THE BURLINGTON DAM STUDY).

2 ROCKFILL, BERM FILL, AND SAND PARAMETERS ARE ASSUMED VALUES.


| TABULATION OF ARC DATA | | | |
|------------------------|---------------------------|------------------|---------------------|
| ARC NO | CENTER COORDINATES X Y | TANGENT ELEV. | FACTOR OF SAFETY |
| ① | -81.60 1658.2 | 1540.0 | 2.02 |
| ② | -81.80 1665.8 | 1543.0 | 1.83 * |
| ③ | -80.00 1700.0 | 1560.0 | 2.03 |
| ④ | -69.30 1688.3 | 1585.0 | 4.38 |
| ① | 260.60 1652.5 | 1540.0 | 2.34 |
| ② | 259.70 1699.1 | 1543.0 | 2.15 * |
| ③ | 262.60 1642.6 | 1560.0 | 2.26 |
| ④ | 261.60 1632.5 | 1585.0 | 3.13 |
| ⑤ | 79.00 1674.5 | 1543.0 | 3.17 |

*REQUIRED FACTOR OF SAFETY = 1.30



| TABULATION OF ARC DATA | | | |
|------------------------|---------------------------|------------------|---------------------|
| ARC NO | CENTER COORDINATES X Y | TANGENT ELEV. | FACTOR OF SAFETY |
| ① | -79.80 1678.0 | 1540.0 | 1.65 |
| ② | -79.80 1674.0 | 1543.0 | 1.49 * |
| ③ | -80.00 1700.0 | 1560.0 | 1.71 |
| ④ | -65.70 1684.4 | 1585.0 | 3.85 |
| ① | 253.30 1663.7 | 1540.0 | 1.90 |
| ② | 249.50 1680.6 | 1543.0 | 1.71 * |
| ③ | 261.60 1651.9 | 1560.0 | 1.93 |
| ④ | 262.10 1646.6 | 1585.0 | 2.85 |
| ⑤ | 95.40 1703.3 | 1543.0 | 2.25 |

*REQUIRED FACTOR OF SAFETY = 1.00



RUCTION W/ EARTHQUAKE




| | | | |
|------------------------------|--------------|---|--|
| DESIGN MEMORANDUM NO. 3 | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING | | SOURIS RIVER, NORTH DAKOTA | |
| STABILITY ANALYSIS | | END OF CONSTRUCTION AND END OF CONSTRUCTION WITH EARTHQUAKE | |
| APPROVED: | DATE: | JUNE 1983 | |
| AS SHOWN | DESIGNED BY: | R-R1-5/704 | |
| SHEET | | OF | |

PLATE NO. B-5

| MAXIMUM POOL ARC TABULATION | | | | | |
|-----------------------------|--------------------|--------|---------------|------------------|--------|
| ARC NO. | CENTER COORDINATES | | TANGENT ELEV. | FACTOR OF SAFETY | |
| | X | Y | | BEFORE | AFTER |
| A | -102.9 | 1682.3 | 1570.0 | 2.580 | 1.43 |
| B | -123.1 | 1723.3 | 1580.0 | 2.331 | 1.21 * |
| C | -109.0 | 1720.0 | 1585.0 | 2.402 | 1.28 |
| D | -41.8 | 1633.5 | 1606.0 | 2.155 | 1.87 |

| TOP OF GATES ARC TABULATION | | | | | |
|-----------------------------|--------------------|--------|---------------|------------------|--------|
| ARC NO. | CENTER COORDINATES | | TANGENT ELEV. | FACTOR OF SAFETY | |
| | X | Y | | BEFORE | AFTER |
| 1 | -107.3 | 1672.7 | 1570.0 | 2.619 | 1.47 |
| 2 | -114.3 | 1678.7 | 1575.0 | 2.526 | 1.32 |
| 3 | -122.2 | 1718.9 | 1580.0 | 2.318 | 1.22 * |
| 4 | -115.1 | 1726.6 | 1585.0 | 2.390 | 1.28 |


* NOTE - ARC 3 AND ARC B ARE DRAWN AS ONE ARC. THE REQD MINIMUM FACTORS OF SAFETY FOR ARC B IS 1.0, AND 1.2 FOR ARC 3.





NOTES

1. REFERENCE PLATE B-5 - SOIL PARAMETERS


POOL ELEVATION





| | | | |
|------------------------------------|--|-----------------------------------|--|
| DESIGN MEMORANDUM NO 3 | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING | | SOURIS RIVER, NORTH DAKOTA | |
| STABILITY ANALYSIS | | PARTIAL POOL, AND SUDDEN DRAWDOWN | |
| FROM TOP OF GATES AND MAXIMUM POOL | | DATE: JUNE 1983 | |
| APPROVED: <i>[Signature]</i> | | DATE: JUNE 1983 | |
| AS SHOWN | | DRAWING NUMBER | |
| R-R1-5/705 | | SHEET OF | |

PLATE NO B-6




TABULATION OF ARC DATA

| ARC NO. | CENTER COORDINATES X | CENTER COORDINATES Y | TANGENT ELEV. | FACTOR OF SAFETY |
|----------------------------|----------------------|----------------------|---------------|------------------|
| SURCHARGE POOL | | | | |
| 1 | 197.4 | 1811.7 | 1510.0 | 4.34 |
| 2 | 185.8 | 1805.8 | 1515.0 | 4.33 * |
| 3 | 184.5 | 1812.3 | 1520.0 | 4.35 |
| SURCHARGE AND MAXIMUM POOL | | | | |
| 4 | 58.6 | 1652.7 | 1603.0 | 2.23 |
| 5 | 50.0 | 1644.0 | 1600.0 | 2.35 |
| 6 | 295.9 | 1695.2 | 1584.0 | 1.30 ** |
| 7 | 290.9 | 1662.5 | 1580.0 | 1.67 * |
| 8 | 282.7 | 1630.6 | 1560.0 | 2.75 |
| 9 | 279.3 | 1636.0 | 1543.0 | 3.74 |
| MAXIMUM POOL | | | | |
| 10 | 201.0 | 1815.3 | 1515.0 | 4.37 |
| 11 | 200.0 | 1810.0 | 1520.0 | 4.37 * |
| 12 | 195.2 | 1819.1 | 1525.0 | 4.38 |

* THE REQ'D FACTOR OF SAFETY FOR MAXIMUM POOL IS 1.50, AND 1.40 FOR SURCHARGE POOL.
 ** SEE NOTE 2

NOTES

1. REFERENCE PLATE B-5 FOR SOIL PARAMETERS
2. ARC 6 DOES NOT MEET THE DESIGN CRITERIA FOR STEADY SEEPAGE STABILITY ANALYSIS, HOWEVER, IT IS A SHALLOW ARC IN A BERM WITH ASSUMED SOIL PARAMETERS, AND A FACTOR OF SAFETY OF 1.30 IS ACCEPTABLE FOR THE GIVEN CONDITIONS.



| | | | |
|------------------------------------|--|---|--|
| DESIGNED BY: L.H.B. | | DEPARTMENT OF THE ARMY ST. PAUL DISTRICT, CORPS OF ENGINEERS ST. PAUL, MINNESOTA | |
| CHECKED BY: L.H.B. | | DESIGN MEMORANDUM NO. 3 FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA | |
| SUBMITTED BY: M.B. | | GENERAL STABILITY ANALYSIS-STEADY SEEPAGE MAXIMUM STORAGE POOL AND SURCHARGE POOL | |
| APPROVED BY: <i>[Signature]</i> | | DATE: JUNE 1963 | |
| APPROVED BY: <i>[Signature]</i> | | DATE: JUNE 1963 | |
| DRAWING NUMBER R-RI-5/706 | | SHEET OF | |

PLATE NO B-7

Q-TESTS




| TEST NO. | BORING NO. | SAMPLE NO. | % MOISTURE CONTENT | LIQUID LIMIT | PLASTIC LIMIT | AVERAGE VOID RATIO | % INITIAL SATURATION |
|----------|------------|------------|--------------------|--------------|---------------|--------------------|----------------------|
| ① | 74-62H | S-5 | 24.1 | 35 | 19 | 0.680 | 98.3 |
| ② | 74-62H | S-6 | 25.1 | 31 | 17 | 0.660 | 100.0 |
| ③ | 74-62H | S-7 | 30.4 | 46 | 17 | 0.900 | 92.7 |
| ④ | 74-63H | S-21 | 22.7 | 22 | 18 | 0.643 | 98.7 |
| ⑤ | 74-61H | S-8 | 37.8 | 63 | 24 | 0.977 | 100.0 |

R-TESTS


| TEST NO. | BORING NO. | SAMPLE NO. | % MOISTURE CONTENT | LIQUID LIMIT | PLASTIC LIMIT | AVERAGE VOID RATIO | % INITIAL SATURATION |
|----------|------------|------------|--------------------|--------------|---------------|--------------------|----------------------|
| ① | 74-62H | S-6 | 27.8 | 31 | 17 | 0.733 | 100.0 |
| ② | 74-62H | S-7 | 29.3 | 46 | 17 | 0.820 | 98.7 |
| ③ | 74-63H | S-21 | 25.5 | 23 | 19 | 0.717 | 95.0 |
| ④ | 74-63H | S-29 | 25.4 | 22 | 18 | 0.748 | 95.3 |
| ⑤ | 74-61H | S-8 | 37.4 | 63 | 24 | 0.977 | 100.0 |

S-TESTS


| TEST NO. | BORING NO. | SAMPLE NO. | % MOISTURE CONTENT | LIQUID LIMIT | PLASTIC LIMIT | AVERAGE VOID RATIO | % INITIAL SATURATION |
|----------|------------|------------|--------------------|--------------|---------------|--------------------|----------------------|
| ① | 74-62H | S-5 | 22.8 | 35 | 19 | 0.770 | 91.3 |
| ② | 74-62H | S-6 | 24.4 | 31 | 17 | 0.733 | 88.0 |
| ③ | 74-62H | S-7 | 27.3 | 46 | 17 | 0.870 | 84.7 |
| ④ | 74-63H | S-21 | 24.7 | 23 | 19 | 0.687 | 96.7 |
| ⑤ | 74-63H | S-29 | 22.6 | 22 | 18 | 0.703 | 86.3 |




DESIGN STRENGTH
 $c = 1100 \text{ psf}$ $\phi = 0^\circ$



DESIGN STRENGTH
 $c = 1120 \text{ psf}$ $\phi = 11^\circ$




DESIGN STRENGTH
 $c = 0 \text{ psf}$ $\phi = 30^\circ$



| | | | | | |
|---|-------|------------------------------|--|----------------------------|----------|
| SYMBOL | | DESCRIPTION | | DATE | APPROVAL |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | | | |
| DESIGNED BY | M. B. | DESIGN MEMORANDUM NO. 1 | | GENERAL | |
| DRAWN BY | J. L. | FLOOD CONTROL - LAKE DARLING | | SOURIS RIVER, NORTH DAKOTA | |
| CHECKED BY | L. D. | LAKE DARLING DAM | | FOUNDATION STRENGTHS | |
| SUBMITTED BY: | | LOWER UNIT | | DATE: | |
| APPROVED: | | [Signature] | | JUNE 1983 | |
| SCALE: | | AS SHOWN | | DRAWING NUMBER | |
| | | | | RI-R-5/707 | |
| SHEET | | OF | | PLATE NO. 8-8 | |


Q-TESTS

| TEST NO | BORING NO. | SAMPLE NO. | MOISTURE CONTENT % | LIQUID LIMIT | PLASTIC LIMIT | AVG VOIDS RATIO | INITIAL SATURATION % |
|---------|------------|------------|--------------------|--------------|---------------|-----------------|----------------------|
| 1 | 74-62M | S-3 | 23.7 | 29 | 17 | 0.643 | 99.7 |
| 2 | 74-62M | S-4 | 25.3 | 25 | 19 | 0.670 | 99.7 |
| 3 | 74-63M | S-5 | 21.6 | 29 | 15 | 0.653 | 90.0 |
| 4 | 74-63M | S-8 | 16.9 | 24 | 19 | 0.495 | 92.0 |
| 5 | 74-63M | S-12 | 23.0 | 27 | 16 | 0.640 | 98.3 |
| 6 | 76-81M | S-1 | 39.6 | 34 | 17 | 1.163 | 90.3 |
| 7 | 76-81M | S-3 | 27.5 | 29 | 15 | 0.787 | 93.3 |
| 8 | 76-81M | S-4 | 30.2 | 30 | 22 | 0.850 | 94.3 |
| 9 | 76-93M | S-1 | 27.5 | 30 | 19 | 0.753 | 98.0 |
| 10 | 76-93M | S-2 | 27.3 | 26 | 14 | 0.767 | 98.3 |
| 11 | 76-93M | S-3 | 21.2 | 24 | 13 | 0.577 | 97.3 |
| 12 | 76-93M | S-4 | 32.7 | 45 | 19 | 0.860 | 100.0 |
| 13 | 76-93M | S-5 | 22.4 | 25 | 13 | 0.567 | 100.0 |




R-TESTS

| TEST NO | BORING NO. | SAMPLE NO. | MOISTURE CONTENT % | LIQUID LIMIT | PLASTIC LIMIT | AVG VOIDS RATIO | INITIAL SATURATION % |
|---------|------------|------------|--------------------|--------------|---------------|-----------------|----------------------|
| 1 | 74-62M | S-3 | 24.1 | 29 | 17 | 0.635 | 100.0 |
| 2 | 74-63M | S-5 | 21.7 | 29 | 15 | 0.657 | 90.3 |
| 3 | 74-63M | S-12 | 22.6 | 27 | 16 | 0.627 | 98.0 |
| 4 | 76-81M | S-1 | 47.3 | 34 | 17 | 1.350 | 90.3 |
| 5 | 76-81M | S-2 | 28.0 | 45 | 24 | 0.880 | 88.3 |
| 6 | 76-81M | S-3 | 26.2 | 27 | 15 | 0.677 | 100.0 |
| 7 | 76-81M | S-4 | 37.7 | 44 | 21 | 1.027 | 98.7 |
| 8 | 76-81M | S-5 | 29.0 | 43 | 17 | 0.780 | 100.0 |
| 9 | 76-93M | S-2 | 27.6 | 26 | 14 | 0.653 | 100.0 |




S-TESTS


| TEST NO | BORING NO. | SAMPLE NO. | MOISTURE CONTENT % | LIQUID LIMIT | PLASTIC LIMIT | AVG VOIDS RATIO | INITIAL SATURATION % |
|---------|------------|------------|--------------------|--------------|---------------|-----------------|----------------------|
| 1 | 74-62M | S-3 | 24.8 | 29 | 17 | 0.687 | 97.0 |
| 2 | 74-62M | S-4 | 18.5 | 25 | 19 | 0.560 | 86.7 |
| 3 | 74-63M | S-8 | 19.8 | 24 | 19 | 0.617 | 86.7 |
| 4 | 74-63M | S-12 | 21.3 | 27 | 16 | 0.610 | 96.3 |
| 5 | 74-63M | S-15 | 20.3 | 25 | 18 | 0.567 | 96.3 |
| 6 | 76-81M | S-1 | 29.2 | 34 | 17 | 0.913 | 85.7 |
| 7 | 76-81M | S-2 | 29.7 | 45 | 24 | 0.990 | 82.3 |
| 8 | 76-81M | S-4 | 31.2 | 50 | 22 | 1.017 | 81.7 |
| 9 | 76-93M | S-1 | 27.9 | 30 | 19 | 0.807 | 94.0 |
| 10 | 76-93M | S-2 | 25.0 | 26 | 14 | 0.750 | 88.0 |




DESIGN STRENGTH
 $c = 700 \text{ psf } \phi = 0^\circ$



DESIGN STRENGTH
 $c = 560 \text{ psf } \phi = 23^\circ$




DESIGN STRENGTH
 $c = 0 \phi = 3^\circ$



| | | | |
|--|-------------------------|------------------------------|----------|
| SYMBOL | DESCRIPTION | DATE | APPROVAL |
| <p>DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA</p> | | | |
| DESIGNED BY: M B | DESIGN MEMORANDUM NO. 3 | GENERAL | |
| DRAWN BY: A P | | FLOOD CONTROL - LAKE DARLING | |
| CHECKED BY: L D | | SOURIS RIVER, NORTH DAKOTA | |
| SUBMITTED BY: | | LAKE DARLING DAM | |
| APPROVED: | | FOUNDATION STRENGTHS | |
| | | UPPER UNIT | |
| | | DATE | |
| | | JUN 1983 | |
| | | AS SHOWN | |
| | | DRAWING NUMBER | |
| | | RI-R-5/708 | |
| | | SHEET OF | |


R-TESTS

| TEST NO | BORING NO | SAMPLE NO | MOISTURE CONTENT (%) | LIQUID LIMIT | PLASTIC LIMIT | VOID RATIO | INITIAL SATURATION (%) |
|---------|-----------|-----------|----------------------------|-----------------|------------------|---------------|------------------------------|
| 1 | 74-62M | 1 | 19.9 | 41 | 15 | 0.637 | 83.3 |
| 2 | 74-62M | 2 | 25.4 | 45 | 19 | 0.857 | 79.7 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |



S-TESTS

| TEST NO | BORING NO | SAMPLE NO | MOISTURE CONTENT (%) | LIQUID LIMIT | PLASTIC LIMIT | VOID RATIO | INITIAL SATURATION (%) |
|---------|-----------|-----------|----------------------------|-----------------|------------------|---------------|------------------------------|
| 1 | 74-62M | 1 | 19.4 | 41 | 15 | 0.773 | 67.3 |
| 2 | 74-62M | 2 | 20.9 | 45 | 19 | 0.700 | 81.7 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |



DESIGN STRENGTH
 $C=640 \text{ psf } \phi=11.7^\circ$

NORMAL STRESS (TSF)

DESIGN STRENGTH
 $C=0, \phi=29.5^\circ$

NORMAL STRESS (TSF)



| SYMBOL | DESCRIPTION | DATE | APPROVAL |
|--|-------------|------------------------------|------------|
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | |
| DESIGNED BY | M B | DESIGN MEMORANDUM NO 3 | GENERAL |
| DRAWN BY | L M P | FLOOD CONTROL - LAKE DARLING | |
| CHECKED BY | L D | SOURIS RIVER, NORTH DAKOTA | |
| SUBMITTED BY | | LAKE DARLING DAM | |
| APPROVED | | EXISTING EMBANKMENT | |
| | | UNDISTURBED R AND S TESTS | |
| | | DATE | JUNE 1983 |
| | | AS SHOWN | |
| | | DRAWING NUMBER | RI-R-5/709 |
| | | SHEET | OF |

PLATE NO B-10

Q-TEST




| TEST NO. | BORING NO. | SAMPLE NO. | LIQUID LIMIT | PLASTIC LIMIT | OPTIMUM M.C. (%) | SAMPLE M.C. (%) |
|----------|------------|------------|--------------|---------------|------------------|-----------------|
| ① | 78-117M | 13+14 | 26 | 14 | 8.1 | 8.0 |
| ② | 78-117M | 15+16 | 42 | 14 | 15.5 | 15.1 |
| ③ | 78-117M | 17+18+19 | 41 | 27 | 15.3 | 15.6 |




R-TEST

| TEST NO. | BORING NO. | SAMPLE NO. | LIQUID LIMIT | PLASTIC LIMIT | OPTIMUM M.C. (%) | SAMPLE M.C. (%) |
|----------|------------|------------|--------------|---------------|------------------|-----------------|
| ① | 78-117M | 13+14 | 26 | 14 | 8.1 | 8.3 |
| ② | 78-117M | 15+16 | 42 | 14 | 15.5 | 15.4 |
| ③ | 78-117M | 17+18+19 | 41 | 27 | 15.3 | 16.2 |

S-TEST


| TEST NO. | BORING NO. | SAMPLE NO. | LIQUID LIMIT | PLASTIC LIMIT | OPTIMUM M.C. (%) | SAMPLE M.C. (%) |
|----------|------------|------------|--------------|---------------|------------------|-----------------|
| ① | 78-117M | 13+14 | 26 | 14 | 8.1 | 8.3 |
| ② | 78-117M | 15+16 | 42 | 14 | 15.5 | 15.9 |
| ③ | 78-117M | 17+18+19 | 41 | 27 | 15.3 | 16.7 |





| | | | |
|----------------------------------|--|----------------------------|--|
| DESIGN MEMORANDUM NO. 3 | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING | | SOURIS RIVER, NORTH DAKOTA | |
| LAKE DARLING DAM | | NEW EMBANKMENT FILL | |
| REMOVED O, R, AND S TESTS | | DATE: JUNE 1963 | |
| APPROVED: <i>[Signature]</i> | | DATE: <i>[Signature]</i> | |
| SUBMITTED BY: <i>[Signature]</i> | | DRAWING NUMBER: RI-R-5/710 | |
| SHEET OF | | PLATE NO. 8-11 | |

PRELIMINARY GEOLOGIC COLUMN, LEFT ABUTMENT



LEGEND



SHALE (AY)



LAMINATED SILTSTONE



HOMOGENEOUS SILTSTONE

SANDSTONE

10

[REDACTED]
 LIGHT

CARBONATE INCRETION







EXPLANATION OF GEOLOGIC COLUMNS

THE GEOLOGIC HISTORY OF THE TONGUE MOUNT FORMATION FROM VISUAL INSPECTION OF CORE SAMPLES TAKEN AT THE APPLICABLE ONLY TO THE IMMEDIATE AREAS INDICATED. THE ONLY OF A PRELIMINARY ATTEMPT AT INTERPRETATION OF THE INTENDED TO SERVE AS A BASIS FROM WHICH INFORMATION COULD BE ACCOMPLISHED. THE ELEVATIONS SHOWN ARE APPROXIMATE, AND ARE NOT AN OVER-ESTIMATION OF THE ACTUAL ELEVATIONS.

The tonalite is very fine grained, in a textural, deposit known laterally as well as vertically. This characteristic is readily inspected of the igneous and the materials are undoubtedly more limited areas of the deposit than the columns. No clear exageneration of variability stems from the fact that the igneous origin is small, amorphous sediments, homogeneous, they are not very different, and the igneous origin is small, amorphous sediments, homogeneous, they are not very different, and the igneous origin is small, amorphous sediments, homogeneous, they are not very different.

LEGEND FOR BOW

TONGUE RIVER FM

-  SHALE
-  LAMINATED SILTSTONE
-  MONOGAMOUS SILTSTONE
-  SANDSTONE
-  CEMENTED SANDSTONE
-  LIGNITE
-  CARBONATE CONCRETIONS

THE BORNOS SHOWN IN THE BORNOS STAFF RELATE THE BORNOS TO THE GENERAL CLASS SHOWN ON THE GEORGIAN CODE DESCRIPTIONS ARE SHOWN IN THE BORNOS STAFF.

NATURAL BREAKS IN THE CORE
NUMBER IN PARENT-ESIS INDICATES CLOSELY

LOCATION OF JOINT WITH DEGREE OF D.P.

LOCATION OF BUCKENSHIRE WITH DEGREE OF D.P.

FRACTURED ZONE

 ZONE OF LOST CORE

U-6 MARKER BED IDENTIFICATION

LLD UNIT DESIGNATION

GENERAL NOTES

PERCENT CORE RECOVERY IS SHOWN TO THE LEFT OF THE BORING TAPE. UNLESS SPECIFIED OTHERWISE, ALL CORE IS 4-INCH DIAMETER.

2 ROCK QUALITY DESIGNATION RQD, IS SHOWN TO THE LEFT OF THE PERCENT RECOVERY COLUMN. RQD IS THE PERCENT RECOVERY CONSISTING OF UNFRACTURED PIECES GREATER THAN 0.3 FOOT IN LENGTH.

3 NOTES PERTAINING TO 4 SPECIFIC BORINGS ARE SHOWN BELOW THE BORING STAFF

4. NOTES PERTAINING TO ALL BORINGS IN A SERIES OF BORINGS ARE SHOWN ON THE SHEET WITH THE FIRST BORING OF THAT SERIES.

DEFINITIONS OF TERMS USED ON THE BURNING LOGS

THEYUNGLI RIVER FORMATION IS AN "IMMATURE" ROCK THAT EXHIBITS BOTH ROCK AND SOIL CHARACTERISTICS. ROCK TERMS SUCH AS SANDSTONE, SILTSTONE AND SHALE ARE USED IN THE BORING LOGS RATHER THAN THE EQUIVALENT SOIL TERMS. THE CHOICE OF TERMS IS BASED ON THE PRECEDENCE OF AN ANALOGY IN THE LITERATURE AND OTHER CORPS OF ENGINEERING PRACTICE.

BEDDING CHARACTERISTICS

HOMOGENEOUS - CONSTITUENT PARTS IN FORM A UNIFORM
CHARACTERIZED BY A LACK OF APPARENT BLENDING
STRATIFICATION HAS TWO SILL LIKE APPEARANCE

LAMINATED COMPONENT BEDS GENERALLY LESS THAN 9
WERE CLASSIFIED AS LAMINATED ALTHOUGH MANY
BEDS EXCEEDED THE LIMITING THICKNESS

VERY THIN BEDDED - COMPONENT BEDS 1/4" - 2 INCHES THICK
THIN BEDDED - COMPONENT BEDS 1 INCHES TO 1 1/2 FEET THICK
MEDIUM BEDDED - COMPONENT BEDS 2 TO 4 FEET THICK
THICK BEDDED - COMPONENT BEDS 4 TO 8 FEET THICK
MASSIVE - COMPONENT BEDS OVER 8 FEET THICK

HARDNESS AND FLEXIBILITY CEMENTATION
PLASTIC - CAN BE EASILY DEFORMED WITH FINGER
FRIABLE - CAN BE EASILY CRUMBED AND SHATTERS
BRITTLE - CAN BE EASILY BROKEN WITHOUT FINGER OR PLI
VERY TOUGH - CAN BE EASILY SCRATCHED WITH FINGER NA
5 FINGER AND SCRATCHED WITH FINGER NAIL
MODERATELY HARD - CAN BE EASILY SCRATCHED WITH KE
SCRATCHED WITH FINGER NAIL

MODERATELY WEAKENED - CAN BE CRUSHED OR BROKEN
DIFFICULT

ALL CEMENTED CALLS BE BROKEN BY HAND

EXPLANATION OF GEOLOGIC COLUMNS

THE GEOLOGIC COLUMNS OF THE TONGUE RIVER FORMATION WERE DEVELOPED ENTIRELY FROM A DUAL INSPECTION OF CORE SAMPLES TAKEN AT THE BURLINGTON DAMSITE AND ARE APPLICABLE ONLY TO THE IMMEDIATE AREAS INDICATED. THE COLUMNS WERE DEVELOPED AS PART OF A PRELIMINARY ATTEMPT AT SYSTEMATIC CORRELATION OF THE SITE BORINGS. THEY ARE ALSO INTENDED TO SERVE AS A BASE FROM WHICH UNIFORMITY IN SUBSEQUENT CLASSIFICATIONS CAN BE ACCOMPLISHED. THE ELEVATIONS SHOWN ARE APPROXIMATE, AND THE ACTUAL OCCURRENCE OF A BED AT ANY GIVEN ELEVATION MAY VARY CONSIDERABLY FROM THAT SHOWN IN THE COLUMNS.

THE TONGUE RIVER FORMATION IS A TERRESTRIAL DEPOSIT KNOWN TO BE HIGHLY VARIABLE LATERALLY AS WELL AS VERTICALLY. THIS CHARACTERISTIC IS READILY APPARENT FROM A CASUAL INSPECTION OF THE COLUMNS. THE MATERIALS ARE UNDOUBTEDLY MORE UNIFORM WITHIN THE LIMITED AREA OF THE DAMSITE THAN THE COLUMNS INDICATE. THE COLUMNS' APPARENT BRAGGADITION OF VARIABILITY STEMS FROM THE FACT THAT THEY SHOW ONLY FIVE BASIC LITHOLOGIC UNITS: SHALE, LAMINATED SILTSTONE, HOMOGENEOUS SILTSTONE, SANDSTONE AND LIGHTS. EACH UNIT, EXCEPT LONITE, CONTAINS A WIDE RANGE OF MATERIALS WHICH GRADES ALMOST IMPERCEPTIBLY INTO ADJACENT LITHOLOGIC UNITS. FOR EXAMPLE, A LAMINATED SILTSTONE WITH A HIGH CLAY CONTENT GRADES INTO SHALE AT ONE EXTREME, BUT A LAMINATED SILTSTONE WITH A HIGH CLAY OR SILT CONTENT GRADES INTO HOMOGENEOUS SILTSTONE AT THE OTHER EXTREME. SINCE THE CLASSIFICATION IS BASED ON VISUAL INSPECTION, INCONSISTENCY IN CLASSIFICATION OF BORDER LINE MATERIALS IS UNAVOIDABLE. IF THE COLUMNS ARE VIEWED WITH THE CONCEPTS OF GRADATIONAL UNIT BOUNDARIES AND OVERLAPPING CLASSIFICATIONS IN MIND, THEY BECOME LESS CONFUSING.

LEGEND FOR BORING LOGS

TONGUE RIVER FM

- SHALE
- LAMINATED SILTSTONE
- HOMOGENEOUS SILTSTONE
- SANDSTONE
- CEMENTED SANDSTONE
- LIGNITE
- CARBONATE CONCRETIONS

THE SYMBOLS SHOWN IN THE BORING STAFF RELATE THE BORING TO THE GENERAL CLASSIFICATION SYSTEM SHOWN ON THE GEOLOGIC COLUMNS. DETAILED DESCRIPTIONS ARE SHOWN TO THE RIGHT OF THE BORING STAFF.

- NATURAL BREAKS IN THE CORE. NUMBER IN PARENTHESES INDICATES CLOSELY SPACED BREAKS.
- LOCATION OF JOINT WITH DEGREE OF DIP.
- LOCATION OF SLICKENSIDE WITH DEGREE OF DIP.
- FRACTURED ZONE.
- ZONE OF LOST CORE.
- LIGNITE MARKER BED IDENTIFICATION.

UNIT DESIGNATION

GENERAL NOTES

1. PERCENT CORE RECOVERY IS SHOWN TO THE LEFT OF THE BORING STAFF. UNLESS SPECIFIED OTHERWISE, ALL CORE IS 4 INCH DIAMETER.
2. ROCK QUALITY DESIGNATION (RQD) IS SHOWN TO THE LEFT OF THE PERCENT RECOVERY COLUMN. RQD IS THE PERCENT RECOVERY CONSISTING OF UNFRACTURED PIECES GREATER THAN 0.3 FOOT IN LENGTH.
3. NOTES PERTAINING TO A SPECIFIC BORING ARE SHOWN BELOW THE BORING STAFF.
4. NOTES PERTAINING TO ALL BORINGS IN A SERIES OF BORINGS ARE SHOWN ON THE SHEET WITH THE FIRST BORING OF THAT SERIES.

DEFINITIONS OF TERMS USED IN THE BORING LOGS

THE TONGUE RIVER FORMATION IS AN "IMMATURE" ROCK THAT EXHIBITS BOTH ROCK AND SOIL CHARACTERISTICS. ROCK TERMS SUCH AS SANDSTONE, SILTSTONE AND SHALE ARE USED IN THE BORING LOGS RATHER THAN THE EQUIVALENT SOIL TERMS. THE CHOICE OF TERMS IS BASED ON PRECEDENCE ESTABLISHED IN THE LITERATURE AND OTHER CORPS OF ENGINEERS' PROJECTS.

BEDDING CHARACTERISTICS

HOMOGENEOUS: CONSTITUENT PARTICLES FORM A UNIFORM MASS WHICH IS CHARACTERIZED BY A LACK OF APPARENT BEDDING. MATERIAL IN WHICH STRATIFICATION WAS TOO SUBTLE TO BE APPARENT IN UNBROKEN CORE WAS CLASSIFIED HOMOGENEOUS.

LAMINATED: COMPONENT BEDS GENERALLY LESS THAN 3/8 INCH THICK. SOME WERE CLASSIFIED AS LAMINATED WITHOUT MANY OF THE CHARACTERISTICS BEDS EXCEEDED THE LIMITING THICKNESS.

VERY THIN BEDDED: COMPONENT BEDS 1/8 TO 1/4 INCHES THICK.
THIN BEDDED: COMPONENT BEDS 1/4 TO 1/2 INCHES THICK.
MEDIUM BEDDED: COMPONENT BEDS 1/2 TO 1 FOOT THICK.
THICK BEDDED: COMPONENT BEDS 1 TO 5 FEET THICK.
MASSIVE: COMPONENT BEDS OVER 5 FEET THICK.

HARDNESS AND DEGREE OF CEMENTATION

PLASTIC: CAN BE EASILY DEFORMED WITH FINGER.
FRIABLE: CAN BE EASILY RUMLED WITH FINGERS.
BRITTLE: CAN BE EASILY BROKEN WITHOUT PERCEIVING PLASTIC DEFORMATION.
VERY SOFT: CAN BE EASILY SCRATCHED WITH FINGER NAIL.
SOFT: CAN BE SCRATCHED WITH FINGER NAIL.
MODERATELY HARD: CAN BE EASILY SCRATCHED WITH KNIFE, CAN NOT BE SCRATCHED WITH FINGER NAIL.
NONCEMENTED: NONCEMENTING AT 1 TO 3 POUNDS.
POORLY CEMENTED: CAN BE RUSHEN OR BROKEN BY FINGER WITH VERY LITTLE DIFFICULTY.
MODERATELY CEMENTED: CAN BE CRUSHED OR BROKEN BY HAND WITH DIFFICULTY.
WELL CEMENTED: CANNOT BE BROKEN BY HAND.

SOILS (UNIFIED SOIL CLASSIFICATION SYSTEM)


- WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES.
- POORLY-GRADED GRAVELS OR GRAVEL-SAND MIXTURES, LITTLE OR NO FINES.
- SILTY GRAVELS, GRAVEL-SAND SILT MIXTURE.
- CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURE.
- WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES.
- POORLY-GRADED SANDS OR GRAVELLY SANDS, LITTLE OR NO FINES.
- SILTY SANDS, SAND-SILT MIXTURE.
- CLAYEY SANDS, SAND-CLAY MIXTURES.
- INORGANIC SILTS, LIQUID LIMIT LESS THAN 50.
- INORGANIC CLAYS, LIQUID LIMIT LESS THAN 50.
- INORGANIC SILTS, LIQUID LIMIT GREATER THAN 50.
- INORGANIC CLAYS, LIQUID LIMIT GREATER THAN 50.
- ORGANIC SILTS OR CLAYS, LIQUID LIMIT LESS THAN 50.
- ORGANIC SILTS OR CLAYS, LIQUID LIMIT GREATER THAN 50.
- PEAT.
- BORDERLINE MATERIAL.
- STRATIFIED MATERIAL.
- WATER LEVEL ON DATE OF BORING.
- SOIL IDENTIFICATION MADE FROM MACHINE ACTION AND DRILL CUTTINGS.



74-BIT MACHINE BORING
74-481P TEST PIT

GENERAL NOTES



1. THE LEGEND REPRESENTS ONLY THE BASIC SOIL TYPES. DETAILED INFORMATION IS SHOWN AT THE RIGHT OF THE BORING LOG.
2. THE NATURAL WATER CONTENT IN PERCENT OF THE DRY WEIGHT IS SHOWN AT THE LEFT OF THE BORING STAFF.
3. AFTERBURN LIMITS (LL), AND PLASTIC LIMIT (PL), ARE SHOWN TO THE RIGHT OF THE BORING STAFF.
4. BLOW COUNT IS SHOWN TO THE EXTREME LEFT OF THE BORING STAFF. SEVERAL HAMMER WEIGHTS, SAMPLER SIZES AND LENGTHS OF HAMMER DROP ALSO USED. BLOW COUNT IS, THEREFORE, EXPLAINED IN THE NOTES FOR EACH SERIES OF BORINGS.

| SYMBOL | DESCRIPTION | DATE | APPROVAL |
|--|-------------|------|----------|
| <p>DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA</p> <p>DESIGN MEMORANDUM NO. 3 GENERAL</p> <p>FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA</p> <p>PRELIMINARY GEOLOGIC COLUMNS AND BORING LOG LEGEND</p> <p>DATE: JUNE 1983</p> <p>AS SHOWN: DRAWING NUMBER: RI-R-5/711</p> <p>SHEET: OF</p> | | | |






NOTE:
1. FIRST HOLE ABANDONED DUE TO CROOKED HOLE AT EL. 1542.7. MOVED 5.0 FEET & DRILLED NEW HOLE.
2. UNABLE TO CORE THE TONGUE RIVER FM DUE TO CROOKED HOLE. COMPLETED BORING BY DRIVING 2-INCH O.D. SAMPLER EVERY 5 FEET. CLEANING OUT WITH ROILER BIT.
3. HOLE BACKFILLED WITH CEMENT.




NOTE:
1. WATER LEVEL LOGGED DURING
2. CORE FRACTURES NOT LOGGED
3. CASING SET TO EL. 1579.2.



NOTE:
1. DRY HOLE.
2. CASING SET TO EL. 1610.2
3. THE TONGUE RIVER FM NOT THEREFORE NO CORE BORE




76-88M
26-27 MAR 1976



NOTE:

1. APPROXIMATELY 400 GAL. WATER LOSS, IN LIGNITE BED AT EL. 1547.1
2. CASING SET TO EL. 1639.0. ALL CASINGS PULLED.
3. HOLE BACKFILLED WITH CEMENT.


76-89M
15 MAR 1976



NOTE:

1. NO CASINGS USED IN HOLE
2. TONGUE RIVER FM DRIVE SAMPLED, THEREFORE NO CORE BREAKS OR FRACTURES WERE LOGGED.


76-90M
29 MAR 1976



NOTE:

1. CASINGS SET TO EL. 1596.5. ALL
2. LOST CORE DUE TO CHOKED WELL
3. HOLE BACKFILLED W/CEMENT.


76-92M
3 MAR 1976



NOTE:


1. WATER LEVEL INDICATES FIRST APPEARANCE OF WATER IN THE DRILL HOLE. SOURCE APPARENTLY A THIN ZONE OF LIGNITE SEAMS.
2. CORE BREAKS NOT LOGGED.
3. CASING SET TO EL. 1588.4. ALL CASINGS PULLED.










76-93M
3 MAR 1976



NOTE:

1. CASINGS SET TO EL. 1570.5. ALL CASINGS PULLED.





76-104M
10 APRIL 1976

TOPSOIL, MOIST, DL. BRN. ROOT HAIRS
OUTWASH, BROKEN ROCK & ROCK DUST
LOOSE, DRY, WHITE-TAN
25% GRAVEL, LOOSE, DRY-SL-DAMP
LT. BRN. OUTWASH
50% GRAVEL, LOOSE, WET, DL.
RUSTY BRN., FEW COBBLES

CASING SET TO EL. 1604.3. ALL
CASING PULLED.

76-105M
10 APRIL 1976

TOPSOIL
OUTWASH, BROKEN & ROCK DUST
LOOSE, DRY, WHITE-LT. BRN.
OC. SILT, SAND FRAGMENTS
GRAVELLY, LOOSE, WET, LT. BRN.
OC. COBBLE
SANDY, MED. SOFT, LT. BRN. GRAVELLY
SILTY, V. STIFF TLL. MOIST, DL. GRAY

CASING SET TO DEPTH 10.5 FT.
ALL CASINGS PULLED.

76-105M
10 APRIL 1976

EST. M.C. 6.5 1623.0
4" BARREL
FINE
TOPSOIL, MOIST, BRN. ROOT HAIRS
OUTWASH, BROKEN ROCK & DUST
LOOSE, DRY, WHITE-TAN
OUTWASH, LOOSE, DRY, LT. BRN.
OUTWASH, LOOSE, DRY, WHITE-TAN- MANY SAND
SIZED FRAGMENTS
LOOSE, DRY, LT. BRN. PEBBLES
LOOSE, WET, SAT., LT. MUSTY, BRN.
PEBBLES, OCC. COBBLES
SILTY, V. STIFF HARD TLL. MOIST, DL. GRAY,
SANDY, PEBBLES
V. STIFF, HARD, MOIST, DL. GRAY, SANDY
LOOSE, WET, SAT., LT. MUSTY BRN.

NOTE:
1. CASING SET TO EL. 1599.1.
ALL CASING PULLED.

76-106M
12 APRIL 1976



EST. M.C. 6.5 1503.0
4" BARREL
FINE
ACCESS RD. FILL GRAVELLY, HARD, DRY, BRN.
SILTY, HARD, FILL, DRY, LT. BRN.
SANDY, V. STIFF, MOIST, DL. GRAY-BRN. BOTTLED SILTY
PEBBLES & GRAVEL
SILTY, SANDY, COMPACT, MOIST, WET, LT. BRN.
SANDY, SILTY, MED.-SOFT, WET, LT. BRN.
SANDY, SILTY, V. SOFT, MOIST-WET, LT. BRN.
SANDY, SILTY, V. SOFT, MOIST-WET, LT. BRN. W/FEW DL. BRN.
STREAKS
V. SOFT, WET, SS GRAVEL
SILTY, MED. MOIST, LT. BRN.
SANDY, 1/2 GRAVEL, V. SOFT, MOIST, WET, LT. BRN.
SOMWHAT COMPACT, WET, LT. BRN. GRAVEL & PEBBLES
SOMWHAT COMPACT, WET, LT. BRN.
LOOSE, SAT., LT. BRN. 1/2 GRAVEL
GRAVELLY, SOMWHAT COMPACT, STIFF, LT. BRN.
TOP OF TONGUE RIVER PM
SHALE CLAYS, WEATHERED, SILTY
SANDY AND GRAVELLY AT TOP, SLIGHTLY PEBBLE
DAMP, DL. BRN. TO LT. GRAY-BRN.

NOTE:
CASING SET TO EL. 1563.9. ALL CASING PULLED.




| | |
|---|--------------------------------|
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | |
| DESIGNED BY: LHB | DESIGN MEMORANDUM NO 3 GENERAL |
| DRAWN BY: JMB | FLOOD CONTROL - LAKE DARLING |
| CHECKED BY: MMB | SOURIS RIVER, NORTH DAKOTA |
| SUBMITTED BY: [Signature] | LAKE DARLING DAM |
| APPROVED: [Signature] | 76-102M THRU 76-111M |
| DATE: JUNE 1983 | |
| DRAWING NUMBER RI-R-5/716 | |
| SHEET OF | |

PLATE NO B-17




Note
The material between elevation 1578.4 and 1579.3 appears indistinguishable from that found in the underlying Tongue River formation and probably has been directly removed from that unit.




General Notes
Blow counts are recorded to the extreme left of each boring shaft. Values given represent a blow count where obtained in that manner. Sandblast sampler driven by a 140 lb hammer falling 30". Blow counts obtained by use of a 100 lb hammer falling 30" are indicated by an asterisk (*). Blow counts obtained by use of a 100 lb hammer falling 30" are indicated by an asterisk (*). Blow counts obtained by use of a 100 lb hammer falling 30" are indicated by an asterisk (*).




| | | | |
|--|----------|------|----------|
| DESIGNED BY | REVISION | DATE | APPROVAL |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT, 1 CORPS OF ENGINEERS ST PAUL, MINNESOTA DESIGN MEMORANDUM NO 3 GENERAL FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA LAKE DARLING DAM 78-112M THRU 78-117M DATE: JUNE 1983 DRAWING NUMBER: RI-R-5/717 SHEET OF | | | |



79-145M
14 SEPT. 1963





| | | | |
|--|--------------------------------|-----------------|--|
| DESIGN MEMORANDUM NO. 3 | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA LAKE DARLING DAM 79-144M AND 79-145 M | | | |
| DESIGNED BY: L.H.B. | APPROVED: <i>[Signature]</i> | DATE: JUNE 1963 | |
| DRAWN BY: L.H.B. | SCALE: 1" = 10' | | |
| CHECKED BY: M.M.B. | SIGNATURE NUMBER RI-R-5/718 | | |
| SUBMITTED BY: | SHEET 1 OF 1 | | |




PLAN VIEW OF RELOCATION




HORIZONTAL SCALE 0 500 1000 1500 2000 FEET




PLAN VIEW OF BRIDGE LOCATION CHANNEL DIVERSION

SCALE 0 100 300 500 FEET








SECTION A-A
TYPICAL EMBANKMENT
SCALE 20' 0 20' FEET






PROFILE ALONG Δ OF NEW CHANNEL
SECTION B-B
SCALE 20' 0 20' FEET




| | | | | | |
|---|--|--------------------------------|--|--|--|
| DESIGNED BY H. G. T. C. C. | | CHECKED BY J. J. | | DRAWN BY G. R. S. M. B. | |
| SUBMITTED BY <i>[Signature]</i> | | APPROVED <i>[Signature]</i> | | DATE JUNE 1963 | |
| DEPARTMENT OF THE ARMY ST. PAUL DISTRICT CORPS OF ENGINEERS ST. PAUL, MINNESOTA | | | | DESIGN MEMORANDUM NO. 3 FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA SOO LINE RAILROAD RELOCATION | |
| DRAWING NUMBER RI-R-5/719 | | | | SHEET OF | |





[illegible][illegible][illegible]




| | | | |
|---|-------------|------------------------------|----------|
| SYMBOL | DESCRIPTION | DATE | APPROVAL |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | |
| DESIGNED BY: M.B. | | GENERAL | |
| CHECKED BY: D.A.E. | | FLOOD CONTROL - LAKE DARLING | |
| DRAWN BY: L.D. | | SOURIS RIVER, NORTH DAKOTA | |
| SUBMITTED BY: [Signature] | | SOO LINE RAILROAD | |
| APPROVED BY: [Signature] | | FOUNDATION STRENGTHS | |
| | | DATE: JUNE 1983 | |
| | | SCALE: AS SHOWN | |
| | | DRAWING NUMBER: RI-R-5/720 | |
| | | SHEET OF | |

PLATE NO.B-21







| | | |
|---|---|----------|
| DESIGNED BY | DATE | APPROVED |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | |
| DRAWN BY: LHB CHECKED BY: J.M.J. SUBMITTED BY: MMB | DESIGN MEMORANDUM NO. 3 FLOOD CONTROL - LAKE DARLING SOUTHERN RIVER, NORTH DAKOTA SOO LINE RAILROAD 64-9M, 76-75M THRU 76-80M | |
| DATE: JUNE 1983 SCALE: 1" = 10' SHEET: 1 OF 1 | DRAWING NUMBER: RI-R-5/721 | |




PLAN




PROFILE
GRAND CROSSING BRIDGE RAISE


SCALE 0 100 500 1000 FEET




ELEVATION
GRAND CROSSING BRIDGE RAISE
NOT TO SCALE



LAKE DARLING



PLAN



EAST →

PROPOSED ROAD PROFILE

EL. 1607.0

APPROXIMATE PROFILE EXISTING ROAD

LAKE DARLING
POOL ELEVATION

APPROXIMATE ORIGINAL GROUND PROFILE


SOURIS RIVER

PROFILE


BRIDGE RAISE



3804.4






| | | | |
|--|-------------|------------------------------------|----------|
| SYMBOL | DESCRIPTION | DATE | APPROVAL |
| DEPARTMENT OF THE ARMY ST. PAUL DISTRICT CORPS OF ENGINEERS ST. PAUL, MINNESOTA | | | |
| DESIGN MEMORANDUM NO. 3 | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA GRANO CROSSING RELOCATION | | | |
| SUBMITTED BY: J.J.B. CHECKED BY: J.M.J. SUBMITTED BY: G.R.S. APPROVED: [Signature] DATE: JUNE 1963 | | AS SHOWN RI-R-5/722 SHEET OF | |




PLAN
SCALE 0 400 800 FEET

ELEVATION - FEET
1640
1630
1620
1610
1600
1590
1580
1570
1560




HIGHWAY 28
TYPICAL EMBANKMENT SECTION

SCALE IN FEET
20' 0 20'






NOT TO SCALE

DETAIL A




TYPICAL HALF SECTION
SCALE 0 4



| | |
|---|-------------------------|
| PROJECT NO. 20 FLOOD CONTROL - LAKE BARKING SOUTH RIVER, NORTH CAROLINA STATE HIGHWAY NO. 20 RELOCATION | |
| DATE JUNE 1960 | DRAWN BY R. E. V. 20 |




1 2




ROAD RAISE PLAN

SCALE 0 200'




PROFILE

HORIZ. SCALE 0 200'
VERT. SCALE 0 20'









SECTION A-A
TYPICAL EMBANKMENT SECTION
HWY. NO. 5

SCALE 0 5 10'









PROFILE OF RAISE
SCALE 0



| | | | | | |
|-----------------------------|--|------------------------------|--|---------|--|
| DESIGNED BY: MLC | | DESIGN MEMORANDUM NO. 3 | | GENERAL | |
| CHECKED BY: MLC | | FLOOD CONTROL - LAKE DARLING | | | |
| APPROVED BY: SRS MLC | | SOURIS RIVER, NORTH DAKOTA | | | |
| SUBMITTED BY: Helen O'Brien | | HIGHWAY 5 | | | |
| DATE: June 1963 | | RELOCATION | | | |
| DRAWN BY: AS SHOWN | | SHEET NO. 1 | | | |
| PROJECT NO. R1-R-5/724 | | SHEET OF | | | |



[illegible][illegible][illegible]



LEGEND

- ① - TESTS WERE RUN AT APPROXIMATELY OPTIMUM MOISTURE CONTENT.
- ② - TEST WERE RUN AT ABOUT 1% BELOW OPTIMUM MOISTURE CONTENT
- △ - TESTS WERE RUN AT ABOUT 2% ABOVE OPTIMUM MOISTURE CONTENT





| | | | | | |
|---|------------------------|---|---------|------------|----------|
| SYMBOL | | DESCRIPTION | | DATE | APPROVAL |
| <p>DEPARTMENT OF THE ARMY ST PAUL DISTRICT, CORPS OF ENGINEERS ST PAUL, MINNESOTA</p> | | | | | |
| DESIGNED BY | M.B. | DESIGN MEMORANDUM NO. 3 | GENERAL | | |
| DRAWN BY | J.M.J. | FLOOD CONTROL | | | |
| CHECKED BY | L.D. | LAKE DARLING DAM-SOURIS RIVER, NORTH DAKOTA | | | |
| SUBMITTED BY | <i>John J. Schmitt</i> | STATE HIGHWAY NO. 5 | | | |
| DATE | 6-10-68 | REMOLDED STRENGTHS | | | |
| APPROVED | <i>John J. Schmitt</i> | GLACIAL TILL FROM RIGHT ABUTMENT | | | |
| DATE | 6-10-68 | DATE | | JUNE 1968 | |
| AS SHOWN | | DRAWING NUMBER | | RI-R-5/725 | |
| SHEET | | OF | | | |

Q-TESTS


| TEST NO. | BORING NO. | SAMPLE NO. | MOISTURE CONTENT (%) | LIQUID LIMIT | PLASTIC LIMIT | AVERAGE VOID RATIO | INITIAL SATURATION (%) |
|----------|------------|------------|----------------------|--------------|---------------|--------------------|------------------------|
| ① | 74-50H | 6 | 32.5 | 57 | 21.0 | 0.890 | 96.0 |
| ② | 74-50H | 7 | 26.1 | 40 | 16.0 | 0.710 | 99.2 |
| ③ | 74-50H | 11 | 28.9 | 45 | 20.0 | 0.800 | 97.3 |
| ④ | 74-50H | 15 | 27.3 | 29 | 20.0 | 0.743 | 99.3 |
| ⑤ | 74-50H | 18 | 32.8 | 45 | 18.0 | 0.877 | 100.0 |
| ⑥ | 64-10H | 4 | 30.5 | 35 | 19.5 | 0.863 | 96.0 |

R-TESTS


| TEST NO. | BORING NO. | SAMPLE NO. | MOISTURE CONTENT (%) | LIQUID LIMIT | PLASTIC LIMIT | AVERAGE VOID RATIO | INITIAL SATURATION (%) |
|----------|------------|------------|----------------------|--------------|---------------|--------------------|------------------------|
| ① | 74-50H | 7 | 29.3 | 40 | 16 | 0.623 | 96.0 |
| ② | 74-50H | 11 | 31.9 | 45 | 20 | 0.670 | 98.7 |
| ③ | 74-50H | 15 | 26.7 | 29 | 20 | 0.717 | 100.0 |
| ④ | 74-50H | 18 | 28.8 | 45 | 18 | 0.783 | 99.7 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |



DESIGN STRENGTH
 $C = 250 \text{ psf}$, $\phi = 0$









DESIGN STRENGTH
 $C = 600 \text{ psf}$, $\phi = 13.4^\circ$



| | | | |
|---|------------------------------|----------------|------------|
| SYMBOL | DESCRIPTION | DATE | APPROVED |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | |
| DESIGNED BY: M B | DESIGN MEMORANDUM NO. 3 | GENERAL | |
| DRAWN BY: DAE | FLOOD CONTROL - LAKE DARLING | | |
| CHECKED BY: L D | SOURIS RIVER, NORTH DAKOTA | | |
| SUBMITTED BY: [Signature] | STATE HIGHWAY NO. 5 | | |
| APPROVED: [Signature] | FOUNDATION STRENGTHS | | |
| | | DATE | JUNE 1983 |
| | | SCALE | AS SHOWN |
| | | DRAWING NUMBER | RI-R-5/726 |
| | | SHEET | OF |


PLATE NO. B-27






SECTION A-A
STORAGE AREA

SECTION




100 50 0 100 200
SCALE IN FEET




| | | | |
|--|------------------------------|----------------|------------|
| DESIGNATION | | DATE | APPROVAL |
| DEPARTMENT OF THE ARMY ST. PAUL DISTRICT, CORPS OF ENGINEERS ST. PAUL, MINNESOTA | | | |
| DESIGNED BY: WJMB/LHBB/JF | DESIGN MEMORANDUM NO. 3 | | GENERAL |
| DRAWN BY: J.M.J. | FLOOD CONTROL - LAKE DARLING | | |
| CHECKED BY: WJMB/NMB/BAMK | SOURIS RIVER, NORTH DAKOTA | | |
| SUBMITTED BY: [Signature] | PLAN | | |
| APPROVED BY: [Signature] | ECKERT RANCH | | |
| | | DATE: | JUNE 1983 |
| | | DRAWING NUMBER | RI-R-5/728 |
| | | SHEET | OF |

83-7M
09 FEBRUARY 1983


83-8M
09 FEBRUARY 1983



SANDY, SILTY, MOIST, STIFF, BROWN
F-V.F., DRV, DENSE, BROWN
SANDY, GRAVELLY, SILTY, MOIST, V. STIFF, BROWN, SAND AND SILT LENSES.
SANDY, GRAVELLY, SILTY, MOIST, V. STIFF, BROWNISH GRAY, IRON STAINED SAND LENSES.
SANDY, GRAVELLY, SILTY, V. MOIST, V. STIFF, GRAY
SANDY, GRAVELLY, SILTY, V. MOIST, V. STIFF, GRAY





83-9M
10 FEBRUARY 1983





| | | | |
|--|---------------------------------------|-----------------|--|
| DESIGN MEMORANDUM NO 3 | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA ECKERT RANCH BORINGS 83-7M THRU 83-9M | | | |
| DESIGNED BY: LMB | APPROVED: <i>Peter A. [Signature]</i> | DATE: JUNE 1983 | |
| DESIGNED BY: LMB | | | |
| DESIGNED BY: MMB | | | |
| SUBMITTED BY: <i>[Signature]</i> | | | |
| DRAWING NUMBER RI-R-5/729 | | SHEET OF | |

PLATE NO. B-30




| | | |
|-----------------------------|------------------------------|---------|
| DESIGNED BY: L.H.B. | DESIGN MEMORANDUM NO. 3 | GENERAL |
| DRAWN BY: ONE | FLOOD CONTROL - LAKE DARLING | |
| CHECKED BY: G.M.B. | SOURIS RIVER, NORTH DAKOTA | |
| APPROVED BY: [Signature] | PLAN AND SECTIONS | |
| DATE: JUNE 1963 | MCKINNEY CEMETERY LEVEE | |
| AS SHOWN | DRAWING NUMBER RI-R-5/730 | |
| SHEET OF | | |







83-1M
02 FEBRUARY 1983



83-2M
03 FEBRUARY 1983



83-5M
05 FEBRUARY 1983



83-3M
04 FEBRUARY 1983

| BORING/PT. | STD. | MC | LL | PL | D ₁₀ |
|------------|------|----|----|----|-----------------|
| 9 | CL | | | | |
| 14. 1596.1 | CL | | | | |
| 7 | | | | | |
| 3 | CL | | | | |
| 8 | | | | | |
| 7 | CL | | | | |
| 9 | CL | | | | |
| 1572.5 | | | | | |

SILTY, DK. BROWN, ROOTS

SANDY (F), SILTY, BROWN

SILTY, STIFF, BROWN

SANDY (F), SILTY, SAT., V. SOFT, BROWN

THIN SAND (F) SEAMS, GRAYS AND BROWNS

ZONES OF CHANGING SILT AND CLAY CONTENT
SOFT, GRAYS AND BROWNS

SILTY, STIFF, GRAY, WOOD CHIPS AND BROWN
SHELL FRAGMENTS

SANDY, SILTY, SAT., STIFF, WOOD CHIPS,
SHELL FRAGMENTS, DK. GRAY

SEAMS OF SILT AND SILTY SAND

GREEN, SEAMS OF SILT AND SILTY SAND

83-4M
04 FEBRUARY 1983

| BORING/PT. | STD. | MC | LL | PL | D ₁₀ |
|------------|------|----|----|----|-----------------|
| 8 | CL | | | | |
| 1595.5 | | | | | |
| 8 | CL | | | | |
| 5 | SM | | | | |
| 7 | CL | | | | |
| 7 | CL | | | | |
| 7 | ML | | | | |
| 7 | SM | | | | |
| 7 | GM | | | | |
| 7 | SP | | | | |
| 7 | GP | | | | |
| 7 | GC | | | | |
| 1570.0 | | | | | |

SILTY, DK. BROWN - BLACK

SANDY (F), SILTY, STIFF, BROWN

C-F, SAT., LOOSE, BROWN

SANDY (F), SILTY, STIFF, BROWN

SAT., LOOSE, BROWN

SANDY (F), SILTY, STIFF, BROWN

CLAYEY, SANDY, V. SOFT, BROWN

F, SAT., LOOSE, BROWN

C-F, SILTY, SANDY (C-F), SAT.,

DENSE, IRON STAINED COLOR

M-C, V. DENSE, SAT., BROWN

F, SAT., V. DENSE, BROWN


F, SAT., DENSE, BROWN

C-F, SILTY, SANDY (C-F),


SAT., V. DENSE, BROWN



| | | | |
|------------------------------|--|----------------|--|
| DESIGN MEMORANDUM NO 3 | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING | | | |
| SOURIS RIVER, NORTH DAKOTA | | | |
| RENNVILLE CO. PARK LEVEE | | | |
| BORINGS 83-1M THRU 83-5M | | | |
| SUBMITTED BY: | | DATE: | |
| LHB | | JUNE 1983 | |
| MMB | | | |
| APPROVED: | | DRAWING NUMBER | |
| [Signature] | | RI-R-5/732 | |
| DATE: | | SHEET OF | |
| JUNE 1983 | | | |



SOURIS RIVER REACH F - BETWEEN BURLINGTON




SOURIS RIVER REACH AT SAWYER


LEGEND

- LEVEE ALIGNMENT
- CHANNEL MODIFICATION
- PUMPING STATION SITE
- GRAVITY OUTLET


SCALE 0 1000 2000 3000 4000 FEET



SOURIS



REACH F - BETWEEN BURLINGTON AND MINOT.



SOURIS RIVER REACH AT VELVA

4000 FEET




| | | |
|--|--|---------|
| DESIGN MEMORANDUM NO 3 | | GENERAL |
| FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA GENERAL PLAN MAJOR DOWNSTREAM WORKS | | |
| DATE | | |
| DRAWING NUMBER | | |
| SHEET | | OF |

| | |
|----------------------------------|------------------------|
| DESIGNED BY: WJM LNB JAF | DESIGNED BY: J.M.E. |
| CHECKED BY: MNB AMK JMM | SUBMITTED BY: H |
| APPROVED: L.H. A. [Signature] | DATE: |

RI-R-8/733

PLATE NO B-34



AD-A136 229


LAKE DARLING FLOOD CONTROL PROJECT SOURIS RIVER NORTH
DAKOTA GENERAL PROJ..(U) CORPS OF ENGINEERS ST PAUL MN
ST PAUL DISTRICT JUN 83


2/3

UNCLASSIFIED


F/G 8/7

NL






MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A




RI-R-8/734

PLATE NO. B-35


1 2





| | |
|--|--|
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | |
| DESIGNED BY W. N. LMB 44P CHECKED BY J.M.A. DRAWN BY R.M.A. 44M COUNTER BY [Signature] APPROVED [Signature] | DESIGN MEMORANDUM NO 3 GENERAL FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA PLAN BROOK'S ADDITION DATE: |
| SCALE 0 50 100 200 FEET | DRAWING NUMBER SHEET OF |









RI-R-8/736


PLATE NO. 37






| | | | | | |
|---|--|----------------|--|---------------|--|
| DESIGNER | | DATE | | APPROVED | |
| DEPARTMENT OF THE ARMY ST. PAUL DISTRICT CORPS OF ENGINEERS ST. PAUL, MINNESOTA | | | | | |
| DESIGN MEMORANDUM NO. 3 | | | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING | | | | | |
| SOURIS RIVER, NORTH DAKOTA | | | | | |
| PLAN | | | | | |
| COUNTRY CLUB ACRES | | | | | |
| AND ROBINWOOD ESTATES | | | | | |
| DATE: | | | | | |
| V.M. L.M.B. J.A.F. | | J.M.A. | | J.M.A. J.E.M. | |
| DESIGNED BY: | | CHECKED BY: | | APPROVED BY: | |
| SCALE 0 50 100 200 FEET | | DRAWING NUMBER | | SHEET | |

2







| | | |
|--|---------|----------|
| DESIGNER | DATE | APPROVED |
| DEPARTMENT OF THE ARMY ST. PAUL DISTRICT CORPS OF ENGINEERS ST. PAUL, MINNESOTA | | |
| DESIGN MEMORANDUM NO. 3 | GENERAL | |
| FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA PLAN KING'S COURT AND ROSTAD'S ADDITION | | |
| DATE: | | |
| SCALE 0 50 100 200 FEET SHEET 1 OF 1 | | |



RI-R-8/738

PLATE NO. B-39









TIERRECITO VALLEJO




JOHNSON'S ADDITION




COUNTRY CLUB ACRES AND ROBINWOOD ESTATES

TALBOTS NURSERY



KINGS COURT AND ROSTAD'S ADDITION




TALBOTS NURSERY

BROOK'S ADDITION



| | | | |
|--|--|----------------------------|--|
| DESIGNED BY: L.H.B. | | CHECKED BY: J.M.J. | |
| DRAWN BY: M.M.B. | | APPROVED BY: [Signature] | |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | |
| DESIGN MEMORANDUM NO. 3 GENERAL FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA LEVEE - BURLINGTON TO MINOT BORINGS 74-1M THRU 74-11M | | | |
| DATE: JUNE 1983 | | DRAWING NUMBER: RI-R-5/740 | |
| SHEET: 1 | | OF: 1 | |



CULTIVATED

41.8+1.33
1322.7
1317.705

EMERGENCY LEVEE FILL WILL BE UTILIZED IN
NEW LEVEE AND CROSS DRAINAGE WILL BE PROVIDED

STATION 30+00

REMOVE STRUCTURES

STATION 20+00

INV. EL. 1500.0

RELOCATE SHED

MAXIMUM WATER SURFACE EL.

POND

RELOCATE BLDG.

ROAD TO EL. 1520.5

RELOCATE SHED

STATION 22+25

VERT. 24' 0" U.S. SLOPE 0.8

FILL TO EL.

1.290942


42.294.2
425.233



| | | | |
|--|--|----------|--|
| DESIGNER | | DATE | |
| CHECKED | | DATE | |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT, CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | |
| DESIGN MEMORANDUM NO. 3 | | GENERAL | |
| FLOOD CONTROL - LAKE DARLING SOURIS RIVER, NORTH DAKOTA PLAN SAWYER | | | |
| DATE | | DATE | |
| SCALE 0 50 100 200 FEET | | SHEET OF | |

1 2

CORPS OF ENGINEERS



1520

Clay, 5' Moist to Moist, Brn, Sil

1520

Clay w/ Org Mat, Moist, Brn

Sand, Moist to v Moist, Brn

Clay, Moist to Wet, Brn

Moist to v Moist, Brn

Clay, w 75% sM, Sat, Brn

Sand, v Soft to Soft, Sat, Brn

Clay

Sand, Sat, Brn

Clay, w Shift, Sat, Gray

Clay, Wet, Gray

Gravel, Sat, Gray

Clay, Wet, Gray

Sand, Sat, Gray

Gravelly Sand, Sat, Brn and Gray

Gravel, Sat, Brn

Red Sandy Gravel and Sand, Gray

Clay, Wet, Gray

1480



| | | | | | |
|---|----------------------|------------------------------|--|-------------------|----------|
| SYMBOL | | DESCRIPTION | | DATE | APPROVAL |
| DEPARTMENT OF THE ARMY ST PAUL DISTRICT CORPS OF ENGINEERS ST PAUL, MINNESOTA | | | | | |
| DESIGNED BY | LHB | DESIGN MEMORANDUM NO 3 | | GENERAL | |
| DRAWN BY | J.M.J. | FLOOD CONTROL - LAKE DARLING | | | |
| CHECKED BY | M.M.D. | SOURIS RIVER, NORTH DAKOTA | | | |
| SUBMITTED BY | <i>John J. Smith</i> | SAWYER | | | |
| APPROVED | <i>R. A. Smith</i> | BORINGS 74-15M 74-17M | | DATE JUNE 1983 | |
| SCALE | | SHEET NO | | DRAWING NUMBER | |
| | | | | RI-R-5/742 | |
| SHEET | | OF | | | |






Figure 3


①




②



③



④







Figure 2




Figure 3




Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4

Figure 4


DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
LAKE DARLING DAM
BORING 74-62M

ST PAUL, MINN. DISTRICT

APR 1963

PLATE NO. 8-44

RI-R-8/763



CONTROLLED-STRAIN TEST


DESCRIPTION OF SPECIMENS: Sandy clay, CL

LL 30 PL 17 PI 15 Co = 2.70 TYPE SPECIMEN: UNDISTURBED TYPE TEST 1


REMARKS: MACHINE PRINT OUT
FORMAT AFTER ESO FORM 2089
8 NOT ON 1.0 V/W when principal
stresses had equipment malfunction
during shear.

PROJECT: Lake Darling Dam HSD-55-75-45-2
Bureau River MS-7
BORING NO: 74-628 SAMPLE NO: 3
DEPTH: 41.7 - 43.0
HSD LAB NO: 74/208 D 75/17
DATE: 8 MAY 1975
TRIAXIAL COMPRESSION TEST REPORT
FIGURE 1

①



②



PROJECT: Lake Darling Dam HSD-55-75-45-2

HSD LABORATORY NO: 74/208 D 75/17

BORING NO: 74-628 SAMPLE NO: 3 DEPTH: 41.7 - 43.0 DATE: 8 MAY 1975


MACHINE PRINT OUT

FORMAT AFTER ESO FORM 2089

CONSOLIDATION TEST -- TIME CURVES

FIGURE 3

③



PROJECT: Lake Darling Dam HSD-55-75-45-2

HSD LABORATORY NO: 74/208 D 75/17

BORING NO: 74-628 SAMPLE NO: 3 DEPTH: 41.7 - 43.0 DATE: 8 MAY 1975

MACHINE PRINT OUT

FORMAT AFTER ESO FORM 2089

CONSOLIDATION TEST -- TIME CURVES

FIGURE 4

④



3087





Figure 3

③



PROJECT: Lake Darling Dam HSD-74-45-25-7
 HSD LABORATORY NO: 74/342 & 74/17
 BORING NO: 74-62M SAMPLE NO: 3 DEPTH: 41.7 - 42.8 DATE: 8 APR 1955
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER HSC FORM 1058

FIGURE 4

④





Figure 5

⑦



DESCRIPTION OF SPECIMENS: Clayey sand, SC-SH
 LL 25 PL 19 PI 6 G_m 2.70 TYPE SPECIMEN: UNDISTURBED TYPE TEST Q

REMARKS: MACHINE PRINT OUT
 FORMAT AFTER HSC FORM 1058

PROJECT: Lake Darling Dam HSD-74-45-25-7
 BORING NO: 74-62M SAMPLE NO: 4
 DEPTH: 50.2 - 51.8
 HSD LAB NO: 74/342 DATE: 8 APR 1955
 TRIAXIAL COMPRESSION TEST REPORT
 FIGURE 6

⑧


DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 74-62M

ST. PAUL, MINN. DISTRICT

JUNE 1955

RI-9094796

PLATE NO. 45



CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Clayey sand, SC-2H

LL 25 PL 19 PI 6 Ca = 2.70 TYPE SPECIMENS: UNDISTURBED TYPE TEST 8
REMARKS: MACHINE PRINT OUT
FORMAT AFTER EDC FORM 2088

PROJECT: Lake Darling Dam NCS-1A-75-45-25-F
BORING NO: 74-62H SAMPLE NO: 4
DEPTH: 50.2 - 51.8
HND LAB NO: 74-342 & 75-17
DATE: 9 APR 1975
TRIAxIAL COMPRESSION TEST REPORT
FIGURE 1






Figure 2




PROJECT: Lake Darling Dam NCS-1A-75-45-25-F
HND LABORATORY NO: 74-342 & 75-17
BORING NO: 74-62H SAMPLE NO: 4 DEPTH: 50.2 - 51.8 DATE: 9 APR 1975
CONSOLIDATION TEST -- TIME CURVE
MACHINE PRINT OUT
FORMAT AFTER EDC FORM 2088

⑤



PROJECT: Lake Darling Dam NCS-1A-75-45-25-F
HND LABORATORY NO: 74-342 & 75-17
BORING NO: 74-62H SAMPLE NO: 4 DEPTH: 50.2 - 51.8 DATE: 9 APR 1975
CONSOLIDATION TEST -- TIME CURVE
MACHINE PRINT OUT
FORMAT AFTER EDC FORM 2088

⑥



2087






Figure 4



PROJECT: Lake Darling Dam MS-1A-75-45-20-F
 HRD LABORATORY NO: 74/342 & 75/17
 BORING NO: 74-62H SAMPLE NO: 4 DEPTH: 50.2 - 51.8 DATE: 9 APR 1975
 CONSOLIDATION TEST -- TYPF CURVES
 MACHINE PRINT OUT
 FORMAT AFTER ENF FORM 2088
 FIGURE 4a



LL 26 PL 19 PI 16 C_w = 2.74 TYPE SPECIMEN: UNDISTURBED TYPF TEST Q
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER ENF FORM 2088
 Specimen 4-b was predominantly silt, middle to bottom. Failure occurred at an approx. 40° tilt from within the upper clay material. Gray clay and silt. Some fine sand. Brittle structure, medium consistency. Low roughness at PL, dull shine, fast shape retention.

| SPECIMEN NUMBER | | 1 | 2 | 3 |
|-----------------------------|--|-------|-------|-------|
| INITIAL WATER CONTENT, % | | 23.4 | 23.5 | 23.3 |
| DRY DENSITY, lb/ft³ | | 101.8 | 102.7 | 100.4 |
| SATURATION, % | | 94 | 97 | 98 |
| VOID RATIO | | .68 | .64 | .70 |
| BEFORE SHEAR | | | | |
| WATER CONTENT, % | | 23.3 | 22.9 | 24.4 |
| DRY DENSITY, lb/ft³ | | 101.8 | 102.7 | 100.4 |
| SATURATION, % | | 94 | 94 | 94 |
| VOID RATIO | | .68 | .64 | .70 |
| FINAL BACK PRESSURE, TSF | | .00 | .00 | .00 |
| MINOR PRINCIPAL STRESS, TSF | | 1.00 | 3.00 | 5.00 |
| MAJ DEViator STRESS, TSF | | 3.03 | 4.98 | 1.22 |
| FIN TO MAJ DEV, % | | 24 | 20 | 17 |
| ULT DEViator STRESS, TSF | | 3.03 | 4.98 | 1.22 |
| INITIAL DIAMETER, IN | | 1.392 | 1.391 | 1.386 |
| INITIAL HEIGHT, IN | | 2.975 | 2.991 | 2.982 |


PROJECT: Lake Darling Dam MS-1A-75-45-20-F
 BORING NO: 74-62H SAMPLE NO: 5
 DEPTH: 64.7 - 66.7
 HRD LAB NO: 75/17 DATE: 30 MAY 1975
 TRIAXIAL COMPRESSION TEST REPORT
 FIGURE 1

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 74-62 M
 ST. PAUL, MINN DISTRICT

JUNE 1983

RI-R-8/748

PLATE NO. 8-46






CONTROLLED-STRAIN TEST


DESCRIPTION OF SPECIMENS: Low clay, CL

LL 26 PL 10 PI 16 Gm = 2.74 TYPE SPECIMEN: UNDISTURBED TYPE TEST A
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 2085


PROJECT: Lake Huron Dam
 BORING NO: 74-001 SAMPLE NO: 5
 DEPTH: 64.7 - 66.7
 HED LAB NO: 75/17 DATE: 30 MAY 1975
 TRIAXIAL COMPRESSION TEST REPORT
 FIGURE 1



PROJECT: Lake Huron Dam
 HED LABORATORY NO: 75/17
 BORING NO: 74-001 SAMPLE NO: 5 DEPTH: 64.7 - 66.7 DATE: 30 MAY 1975
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 2085



PROJECT: Lake Huron Dam
 HED LABORATORY NO: 75/17
 BORING NO: 74-001 SAMPLE NO: 5 DEPTH: 64.7 - 66.7 DATE: 30 MAY 1975
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 2085






Figure 3





Figure 4

③



PROJECT: Lake Darling Dam NS-1A-75-66-20-7

NSD LABORATORY NO: 75/17


BORING NO: 74-62H SAMPLE NO: 5 DEPTH: 64.7 - 66.7 DATE: 5 MAY 1955

CONSOLIDATION TEST -- TIME CLAYES

MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2085

FIGURE 5

④



⑤




Figure 10

⑦

DATE: 5 MAY 1955

FIGURE 6


DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
LAKE DARLING DAM
BORING 74-62M

ST PAUL, MINN DISTRICT

JUNE 1955


R1-R-6/746

PLATE NO. 8-47




LC 31 PL 17 PI 14 CM 2.65 THIS SPECIMEN UNDISTURBED TYPE TEST 4
REMARKS: MACHINE PRINT OUT
FORMAT AFTER EDC FORM 2088


PROJECT: Lake Darling Dam MCS-1A-75-43-2
BORING NO: 74-62H SAMPLE NO: 6
DEPTH: 80.2 - 81.9
MID LAB NO: 74-342 DATE: 8 APR 85
M 75 17
TRIAXIAL COMPRESSION TEST REPORT
FIGURE 1




PROJECT: Lake Darling Dam MCS-1A-75-43-2
BORING NO: 74-62H SAMPLE NO: 6
DEPTH: 80.2 - 81.9
MID LAB NO: 74-342 DATE: 8 APR 85
M 75 17
TRIAXIAL COMPRESSION TEST REPORT
FIGURE 2



PROJECT: Lake Darling Dam MCS-1A-75-43-2
MID LABORATORY NO: 74/342 & 75/17
BORING NO: 74-62H SAMPLE NO: 6 DEPTH: 80.2 - 81.9 DATE: 8 APR 85
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER EDC FORM 2088



PROJECT: Lake Darling Dam MCS-1A-75-43-2
MID LABORATORY NO: 74/342 & 75/17
BORING NO: 74-62H SAMPLE NO: 6 DEPTH: 80.2 - 81.9 DATE: 8 APR 85
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER EDC FORM 2088



PROJECT: Lake Darling Dam MCS-1A-75-43-2
MID LABORATORY NO: 74/342 & 75/17
BORING NO: 74-62H SAMPLE NO: 6 DEPTH: 80.2 - 81.9 DATE: 8 APR 85
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER EDC FORM 2088





Figure 9

③



PROJECT: Lake Darling Dam MS-1A-75-45-42-7

HRD LABORATORY NO: 74-342 W 75 17


BORING NO: 74-62M SAMPLE NO: 0 DEPTH: 60.2 - 61.9 DATE: 8 APR 1975

MACHINE PRINT OUT

FORMAT AFTER EDC FORM 2248

FIGURE 10

④



PROJECT: Lake Darling Dam MS-1A-75-45-42-7

BORING NO: 74-62M SAMPLE NO: 7

DEPTH: 65.2 - 67.3

HRD LAB NO: 74-342 W 75 17

DATE: 8 APR 1975

TRIAXIAL COMPRESSION TEST REPORT

FIGURE 11


⑤

DESIGN MEMORANDUM NO 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
LAKE DARLING DAM
BORING 74-62 M
ST. PAUL, MINN. DISTRICT

JUNE 1983

RI-R-8/747

PLATE NO. 8-48




CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Lean clay, CL


LL 40 PL 17 PI 29 C_u = 2.76 TYPE SPECIMEN: UNDISTURBED TYPE TEST
REMARKS: MACHINE PRINT OUT
FORMAT AFTER SBC FORM 2088

PROJECT: Lake Barling Dam HCS-1A-75-45-
BORING NO: 74-62H SAMPLE NO: 7
DEPTH: 95.2 - 97.3
HCS LAB NO: 74-342 DATE: 8 APR 1975
LABORATORY TEST REPORT
FIGURE 12

①




②




PROJECT: Lake Barling Dam HCS-1A-75-45-
HCS LABORATORY NO: 74-342 & 75-17
BORING NO: 74-62H SAMPLE NO: 7 DEPTH: 95.2 - 97.3 DATE: 8 APR 1975
LABORATORY TEST REPORT
FIGURE 14b

③



PROJECT: Lake Barling Dam HCS-1A-75-45-
HCS LABORATORY NO: 74-342 & 75-17
BORING NO: 74-62H SAMPLE NO: 7 DEPTH: 95.2 - 97.3 DATE: 8 APR 1975
LABORATORY TEST REPORT
FIGURE 14c

④



2087




Figure 13





Figure 14



PROJECT: Lake Darling Dam HDS-1A-75-45-82-7

HDS LABORATORY NO: 74-342 W 75.17

BORING NO: 74-62M SAMPLE NO: 7 DEPTH: 95.2 - 97.3 DATE: 8 APR 1975

CONSOLIDATION TEST -- TIME CURVES


MACHINE PRINT OUT

FORMAT AFTER ENG FORM 2088

FIGURE 14a

③

④



PROJECT: Lake Darling Dam HDS-1A-75-45-82-7
HDS Laboratory No. 74-342 W 75.17
BORING NO: 74-62M SAMPLE NO: 8
DEPTH: 9.8 - 11.5
DATE: 8 APR 1975

TRIAxIAL COMPRESSION TEST REPORT

Light brown sandy clay, brittle structure, soft consistency, slightly sensitive. Medium toughness at P_L , dull color, fast color reaction.

PROJECT: Lake Darling Dam HDS-1A-75-45-82-7
HDS Laboratory No. 74-342 W 75.17
BORING NO: 74-62M SAMPLE NO: 8
DEPTH: 9.8 - 11.5
DATE: 8 APR 1975

TRIAxIAL COMPRESSION TEST REPORT

Light brown sandy clay, brittle structure, soft consistency, slightly sensitive. Medium toughness at P_L , dull color, fast color reaction.

PROJECT: Lake Darling Dam HDS-1A-75-45-82-7
HDS Laboratory No. 74-342 W 75.17
BORING NO: 74-62M SAMPLE NO: 8
DEPTH: 9.8 - 11.5
DATE: 8 APR 1975

TRIAxIAL COMPRESSION TEST REPORT

Light brown sandy clay, brittle structure, soft consistency, slightly sensitive. Medium toughness at P_L , dull color, fast color reaction.

PROJECT: Lake Darling Dam HDS-1A-75-45-82-7
HDS Laboratory No. 74-342 W 75.17
BORING NO: 74-62M SAMPLE NO: 8
DEPTH: 9.8 - 11.5
DATE: 8 APR 1975

TRIAxIAL COMPRESSION TEST REPORT

⑦

⑧


DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
LAKE DARLING DAM
BORINGS 74-62M AND 74-63M

ST PAUL, MINN DISTRICT

JUNE 1963

R1-R-5/748

PLATE NO 9-48



LL 30 PL 35 PI 54 Co = 2.71 TYPE SPECIMEN: UNDISTURBED TYPE TEST
REMARKS: MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2089

PROJECT: Lake Darling Dam HEC-20-75-46
Sandy River
BORING NO: T6-6M SAMPLE NO: 5
DEPTH: 9.5 - 11.5
HSD LAB NO: 75-17 DATE: 1 MAY 1975
TRIAXIAL COMPRESSION TEST REPORT
FIGURE 7

①





Figure 10

②



③





Figure 11

④

PROJECT: Lake Darling Dam
HSD LABORATORY #
BORING NO: T6-6M
DATE: 1 MAY 1975

MACHINE PRINT OUT
FORMAT AFTER EBC



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Sandy silt, RL-62

LL 36 PL 19 PE 5 Ca= 2.72 TYPE SPECIMEN: UNDISTURBED TYPE TEST Q

REMARKS: MACHINE PRINT OUT

FORMAT AFTER EDC FORM 2089

Efficiency in sample trimming, unable

to trim third test specimen. Sampled

gray to tan clayey sand and silt. Non-

cohesive fine gravel silt. Brittle struc-

ture, soft consistency, incompressive.

Low toughness at PL, no shine, fast

shear reaction.

PROJECT: Lake Darling Dam MS-25-74-62

BORING NO: 74-63M SAMPLE NO: 8

DEPTH: 15.8 - 17.9

MSD LAB NO: 75/17 DATE 28 MAY 1975

TRIAL COMPRESSION TEST REPORT

FIGURE 10



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Sandy silt, RL-62

LL 36 PL 19 PE 5 Ca= 2.72 TYPE SPECIMEN: UNDISTURBED TYPE TEST R

REMARKS: MACHINE PRINT OUT

FORMAT AFTER EDC FORM 2089

PROJECT: Lake Darling Dam MS-25-74-62


BORING NO: 74-63M SAMPLE NO: 8

DEPTH: 15.8 - 17.9

MSD LAB NO: 75/17 DATE 28 MAY 1975

TRIAL COMPRESSION TEST REPORT

FIGURE 11



PROJECT: Lake Darling Dam MS-25-74-62-62

MSD LABORATORY NO: 75/17


BORING NO: 74-63M SAMPLE NO: 8 DEPTH: 15.8 - 17.9 DATE: 28 MAY 1975

CONSOLIDATION TEST -- TIME CURVES

MACHINE PRINT OUT

FORMAT AFTER EDC FORM 2089

FIGURE 12



PROJECT: Lake Darling Dam MS-25-74-62-62

MSD LABORATORY NO: 75/17

BORING NO: 74-63M SAMPLE NO: 8 DEPTH: 15.8 - 17.9 DATE: 28 MAY 1975

CONSOLIDATION TEST -- TIME CURVES

MACHINE PRINT OUT

FORMAT AFTER EDC FORM 2089

FIGURE 13


DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 74-63 M

ST PAUL, MINN DISTRICT

JUNE 1965

PLATE NO 8-90

RI-A-7329



PROJECT: Lake Darling Dam HES-24-75-46-27

HED LABORATORY NO: 75/17

BORING NO: 74-62H SA FILE NO: 0 DEPTH: 15.5 - 17.9 DATA: 10 MW 10%
CONE RESISTANCE TEST - TYPICALLACER PRINT OUT
FORMAT AFTER ENC FOR

FIG. 1.15

①




Figure 2

②




Figure 3

③





Figure 4

④




AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Sandy clay, CL

LL 27 PL 16 PI 11 Co= 2.73 TYPE SPECIMEN: UNDISTURBED TYPE TEST Q
REMARKS: MACHINE PRINT OUT
FORMAT AFTER EAC FORM 1089

From sandy clay, brittle structure,
not continuous, slightly sensitive.
High toughness at PL, glass thin,
also shows reaction.


OBJECT: Lake Darling Dam HCB-1A-75-45-
Souris River
BORING NO: 74-63M SAMPLE NO: 12
DEPTH: 26.5 - 30.0
MFD LAB NO: 74-342 DATE 5 MAY 1975
75/17
TRIAxIAL COMPRESSION TEST REPORT
FIGURE 4



AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Sandy clay, CL

LL 27 PL 16 PI 11 Co= 2.73 TYPE SPECIMEN: UNDISTURBED TYPE TEST B
REMARKS: MACHINE PRINT OUT
FORMAT AFTER EAC FORM 1089


PROJECT: Lake Darling Dam HCB-1A-75-45-
BORING NO: 74-63M SAMPLE NO: 12
DEPTH: 26.5 - 30.0
MFD LAB NO: 74-342 DATE 5 MAY 1975
75/17
TRIAxIAL COMPRESSION TEST REPORT
FIGURE 5



AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Sandy, silty clay, CL-ML

LL 25 PL 16 PI 7 Co= 2.70 TYPE SPECIMEN: UNDISTURBED TYPE TEST B
REMARKS: MACHINE PRINT OUT
FORMAT AFTER EAC FORM 1089

PROJECT: Lake Darling Dam HCB-1A-75-45-
BORING NO: 74-63M SAMPLE NO: 13
DEPTH: 35.5 - 39.0
MFD LAB NO: 74-342 DATE 8 APR 1975
75/17
TRIAxIAL COMPRESSION TEST REPORT
FIGURE 6



AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Sandy, silty clay, CL-ML

LL 25 PL 16 PI 7 Co= 2.70 TYPE SPECIMEN: UNDISTURBED TYPE TEST B
REMARKS: MACHINE PRINT OUT
FORMAT AFTER EAC FORM 1089

PROJECT: Lake Darling Dam HCB-1A-75-45-
BORING NO: 74-63M SAMPLE NO: 13
DEPTH: 35.5 - 39.0
MFD LAB NO: 74-342 DATE 8 APR 1975
75/17
TRIAxIAL COMPRESSION TEST REPORT
FIGURE 7

DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
LAKE DARLING DAM
BORING 74-63M

ST PAUL, MINN DISTRICT

JUNE 1983

RI-R-8/790

PLATE NO. 8-1





Figure 14



AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENT: Sandy silt, NC-CL

LL 23 PL 19 PI 4 Gm 2.68 TYP: SPECIMEN: UNDISTURBED: TYPE: 1117
REMARKS: MACHINE PRINT OUT
FORMAT AFTER EIC FORM 2069

PROJECT: Lake Darling Bore MCS-1A-75-43-2
BORING NO: 74-63N SAMPLE NO: 21
DEPTH: 50.0 - 52.3
HSD LAB NO: 74-342 DATE: 22 APR 1975
HSD LAB NO: 74-17
TRIAL: COMPRESSIVE TEST REPORT
1117-110






Figure 15




PROJECT: Lake Darling Bore MCS-1A-75-43-2
HSD LABORATORY NO: 74-342 & 74-17
BORING NO: 74-63N SAMPLE NO: 21 DEPTH: 50.0 - 52.3
DATE: 22 APR 1975
HSD LAB NO: 74-342
TRIAL: COMPRESSIVE TEST REPORT
1117-110

PROJECT: Lake Darling Bore MCS-1A-75-43-2
HSD LABORATORY NO: 74-342 & 74-17
BORING NO: 74-63N
SAMPLE NO: 21
DATE: 22 APR 1975
HSD LAB NO: 74-342
TRIAL: COMPRESSIVE TEST REPORT
1117-110



| | 1 | 2 | 3 |
|-----------|-------|-------|-------|
| WRETSY, 1 | 26.7 | 21.9 | 23.3 |
| STV, PCF | 100.3 | 102.9 | 102.3 |
| PCF, 1 | 99 | 99 | 98 |
| STO | .87 | .62 | .64 |
| WRETSY, 1 | 26.2 | 22.8 | 23.0 |
| STV, PCF | 100.3 | 102.9 | 102.2 |
| PCF, 1 | 97 | 98 | 97 |
| STO | .87 | .62 | .64 |
| WRETSY | .00 | .00 | .00 |
| STV, TSF | 1.00 | 3.00 | 3.00 |
| PCF, TSF | 1.78 | 2.53 | 2.52 |
| STO, TSF | .30 | .31 | .30 |
| WRETSY | 1.78 | 2.53 | 2.52 |
| STV | 1.398 | 1.403 | 1.402 |
| PCF | 2.976 | 2.976 | 2.975 |






AXIAL STRAIN, I
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Sandy silt, ML-CL



LL 23 PL 19 P1 4 Gb= 2.68 TYPE SPECIMEN: UNDISTURBED TYPE TEST

REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2089

PROJECT: Lake Darling Dam MCS-1A-75-43-
ED-F
BORING NO: 74-63M SAMPLE NO: 21
DEPTH: 50.0 - 52.3
NRD LAB NO: 74/342 DATE 22 APR 1975
6/75/17
TRIAxIAL COMPRESSION TEST REPORT
FIGURE 11



PROJECT: Lake Huron Dam HDS-2A-75-45-22-F
HED LABORATORY NO: 74/342 & 75/17
BORING NO: 74-62H SAMPLE NO: 21 DEPTH: 50.0 - 53.3 DATE: 22 APR 1975
CONSOLIDATION TEST -- TIME CURVES
WATER, AIR, OIL
TEMPERATURE AND PORE PRESSURE
FIGURE 1b



PROJECT: Lake Darling Dam HCB-28-75-66-BB-F

MED LABORATORY NO: 74/342 & 75/17

DORING NO: 74-GSH SAMPLE NO: 21 DEPTH: SO.O - S2.3 DATE: 08 APR 1975

CONSOLIDATION TEST -- TIME CURVES

MEASURED ORIF COT
DATE OF TEST: 11 APR 1975

PIERCE 12

DESIGN MEMORANDUM NO. 3

GENERAL

FLOOD CONTROL - LAKE DARLING
SOURS RIVER, NORTH DAKOTA

SOILS TEST DATA
LAKE DARLING DAM
BORING 74-63 M

ST. PAUL, MINN. DISTRICT





Figure 7




LL 22 PL 18 PL 4 $G_m = 2.71$ TYPE SPECIMEN: UNDISTURBED TYPE TEST 8

REMARKS: MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2085

Soil: sandy silt, brittle structure,
medium consistency, slightly sensitive
low toughness at PL, shell chips, fast
shrink reaction.

PROJECT: Lake Barling Dam HES-28-75-42
BORING NO: 75-42B SAMPLE NO: 20
DEPTH: 75.0 - 77.5
MND LAB NO: 75/17 DATE: 15 JUL 1975
TAXIAL COMPRESSION TEST REPORT




LL 34 PL 17 PL 17 $G_m = 2.66$ TYPE SPECIMEN: UNDISTURBED TYPE TEST Q

REMARKS: MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2085

Dark gray brittle, soft consistency,
slightly sensitive. Low strength at
PL, no chips, fast shrink reaction.

PROJECT: Lake Barling Dam HES-28-75-42
BORING NO: 75-42B SAMPLE NO: 1
DEPTH: 13.0 - 14.9
MND LAB NO: 75/16 DATE: 15 JUL 1975
TAXIAL COMPRESSION TEST REPORT



LL 34 PL 17 PL 17 $G_m = 2.66$ TYPE SPECIMEN: UNDISTURBED TYPE TEST 8

REMARKS: MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2085

b -value = 0.90

PROJECT: Lake Barling Dam HES-28-75-42
BORING NO: 75-42B SAMPLE NO: 1
DEPTH: 13.0 - 14.9
MND LAB NO: 75/16 DATE: 15 JUL 1975
TAXIAL COMPRESSION TEST REPORT






Figure 5

④



⑦




Figure 4

⑧


DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORINGS 74-63M AND 76-81M

ST. PAUL, MINN. DISTRICT

JUNE 1983

RI-R-8/782


PLATE NO. 6-53



PROJECT: Lake Barling HCB-22-76-02
 HCB LABORATORY NO: 76/116
 BORING NO: 76-01 SAMPLE NO: 1 DEPTH: 13.0 - 14.9 DATE: 15 JUL 1976
 CONSOLIDATION TEST -- TI & CLAYES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 20.6

FIGURE 4a


①



PROJECT: Lake Barling HCB-22-76-02
 HCB LABORATORY NO: 76/116
 BORING NO: 76-01 SAMPLE NO: 1 DEPTH: 13.0 - 14.9 DATE: 15 JUL 1976
 CONSOLIDATION TEST -- TI & CLAYES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 20.6

FIGURE 4b


②



PROJECT: Lake Barling HCB-22-76-02
 HCB LABORATORY NO: 76/116
 BORING NO: 76-01 SAMPLE NO: 1 DEPTH: 13.0 - 14.9 DATE: 15 JUL 1976
 CONSOLIDATION TEST -- TI & CLAYES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 20.6

FIGURE 4c

③



AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMENS: Sandy clay, CL
 LL 46 PL 26 PI 25 Cc = 2.74 TYPE SPEC FOR UNSAT. SOIL TYPE TEST R
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 20.6
 Specimen curved, soft consistency, slightly sensitive. Low to medium strength at PL, shell chips, first shear occurred. Strain up of sample was too small to give consolidation and O curve.
 Swollen = 1.00

⑤




FIGURE 6

⑥





FIGURE 7

⑦



PROJECT: Lake Darling MS-3A-76-02

TEST LABORATORY NO: 76/110

BORING NO: 76-01 SAMPLE NO: 1 CUTTING: 13.0 - 14.9 DATE: 15 JUL 1975


CONTROLLING TEST -- TIT CURVES

MACHINE PRINT OUT

FORMAT AFTER RPT FOR: 20

FIGURE 4c


③



MSD FORM 2857

Figure 5


④



MSD FORM 2857

Figure 10

⑦



MSD FORM 2857

Figure 12


⑧

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 76-01 MU
 ST. PAUL, MINN. DISTRICT

JUNE 1965

PLATE NO. 8-54

R10/20/25 / - - -



DESCRIPTION OF SPECIMENS: Clayey sand, SC

LL 29 PL 15 PI 14 CA=2.66 TYPE SPECIMEN: UNDISTURBED TYPE TEST G

REMARKS: MACHINE PRINT OUT
FORMAT AFTER LAG FORM 2009
Light gray clayey sand with clay seams
of brittle structure, soft consistency,
and slightly sensitive. Low
to medium strength at PL, no shine
and a fast shake reaction.

PROJECT: Lake Belling MCS-1A-76-02


BORING NO: 76-01M SAMPLE NO: 3

DEPTH: 33.0 - 34.9

WD LAB NO: 76/116 DATE: 15 JUL 1976

TRIAxIAL COMPRESSION TEST REPORT

①



DESCRIPTION OF SPECIMENS: Clayey sand, SC

LL 27 PL 15 PI 12 CA=2.66 TYPE SPECIMEN: UNDISTURBED TYPE TEST G

REMARKS: MACHINE PRINT OUT
FORMAT AFTER LAG FORM 2009
Light gray clayey sand of brittle
structure, soft consistency, and
slightly sensitive. Medium strength
at PL, no shine and a fast shake reaction.
B-value = 0.97

PROJECT: Lake Belling MCS-1A-76-02


BORING NO: 76-01M SAMPLE NO: 3

DEPTH: 33.0 - 34.9


WD LAB NO: 76/116 DATE: 15 JUL 1976

TRIAxIAL COMPRESSION TEST REPORT

②



WD LAB NO: 76/116



DESCRIPTION OF SPECIMENS: Fat clay, CL

LL 50 PL 23 PI 30 CA=2.66 TYPE SPECIMEN: UNDISTURBED TYPE TEST G

REMARKS: MACHINE PRINT OUT
FORMAT AFTER LAG FORM 2009

PROJECT: Lake Belling MCS-1A-76-02-03


BORING NO: 76-01M SAMPLE NO: 4

DEPTH: 33.0 - 34.9

WD LAB NO: 76/116 DATE: 5 AUG 1976

TRIAxIAL COMPRESSION TEST REPORT

③



DESCRIPTION OF SPECIMENS: Lake clay, CL

LL 44 PL 21 PI 23 CA=2.66 TYPE SPECIMEN: UNDISTURBED TYPE TEST G

REMARKS: MACHINE PRINT OUT
FORMAT AFTER LAG FORM 2009
Gray, brittle structure, medium
consistency, insensitive. Low
strength at PL, dull shine, slow
shake reaction.
B-value = 0.95

PROJECT: Lake Belling MCS-1A-76-02-03

BORING NO: 76-01M SAMPLE NO: 4

DEPTH: 33.0 - 34.9

WD LAB NO: 76/116 DATE: 5 AUG 1976

TRIAxIAL COMPRESSION TEST REPORT

④






Figure 5

③




Figure 6

④




Figure 7

⑦




Figure 8


DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
LAKE DARLING DAM
BORING 76-81M

PAUL, MISSOURI DISTRICT

JUNE 1983


PLATE NO. 8-55

RI-R-5/784




PROJECT: Lake Marling No. 76-01
 LAB: LABORATORY NO. 76-01
 DATE: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76

①




PROJECT: Lake Marling No. 76-01
 LAB: LABORATORY NO. 76-01
 DATE: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76

②




PROJECT: Lake Marling No. 76-01
 LAB: LABORATORY NO. 76-01
 DATE: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76




PROJECT: Lake Marling No. 76-01
 LAB: LABORATORY NO. 76-01
 DATE: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76

⑤




PROJECT: Lake Marling No. 76-01
 LAB: LABORATORY NO. 76-01
 DATE: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76

⑥



PROJECT: Lake Marling No. 76-01
 LAB: LABORATORY NO. 76-01
 DATE: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76
 TEST: 10-01-76



PROJECT: Lake Darling Dam HCS-1A-76-92-2B-F

HND LABORATORY NO: 76-110

BORING NO: 76-81 SAMPLE NO: 4 DEPTH: 33.0 - 34.9 DATE: 5 AUG 1966


CONSTRUCTION: HCS-1A-76-92-2B-F

MACHINE PRINT OUT

FORMAT AFTER ENR 1-13-1

FIGURE 7

③




ENR 1-13-1

Figure 8


④

SEE NOTE PLATE B-49



ENR 1-13-1

Figure 9



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Fat clay, CH

LL 63 PL 24 PI 29 Cu = 2.6% TYPE SPECIES: UNDIFFERENTIATED TYPE TEST: U

ALPHABET: MACHINE PRINT OUT

FORMAT AFTER ENR 1-13-1

Gray, brittle structure, medium consistency, sensitive. Medium strength at PL, glass to high glass shine, no shale reaction.

PROJECT: Lake Darling Dam HCS-1A-76-92-2B-F

BORING NO: 76-81 SAMPLE NO: 4

DEPTH: 33.0 - 34.9

HND LAB NO: 76-110 DATE: 5 AUG 1966

TRIAXIAL COMPRESSION TEST REPORT

FIGURE 10

⑧


DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 76-81 M

ST. PAUL, MINN. DISTRICT

JUNE 1963

RI-R-8/788

PLATE NO. B-56



LL 63 PL 34 PI 39 Co = 4.04 TYPE SPIKE AND ADJUSTABLE. TYPE TEST A
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 2000
 B-value = 0.99

PROJECT: Lake Barling Dam MCS-1A-76-92-23-7
 BORING NO: 76-01M SAMPLE NO: 6
 DEPT: 60.0 - 61.9
 MVD LAB NO: 76-116 DATE: 5 AUG 1976
 U.S. ARMY CORP OF ENGINEERS
 CIVIL ENGINEERING DIVISION





Figure 12

PROJECT: Lake Barling Dam
 MVD LABORATORY NO: 76
 BORING NO: 76-01 SAM
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 1



PROJECT: Lake Barling Dam MCS-1A-76-92-23-7
 MVD LABORATORY NO: 76/116
 BORING NO: 76-01 SAMPLE NO: 6 DEPTH: 60.0 - 61.9 DATE: 5 AUG 1976
 CONSOLIDATION TEST -- TIME CURVE
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 2000






Figure 15

PROJECT: Lake Barling Dam
 MVD LABORATORY NO: 76
 BORING NO: 76-01 SAM
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 1



PROJECT: Lake Darling Dam WDS-2A-76-92-23-F
 HED LABORATORY NO: 76/116
 BORING NO: 76-81 SAMPLE NO: 0 DEPTH: 60.0 - 61.9 DATE: 5 AUG 1976
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER SBC FORM 2088 FIG BB 13


③



PROJECT: Lake Darling Dam WDS-2A-76-92-23-F
 HED LABORATORY NO: 76/116
 BORING NO: 76-81 SAMPLE NO: 0 DEPTH: 60.0 - 61.9 DATE: 5 AUG 1976
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER SBC FORM 2088 FIG BB 14

④

* SEE NOTE PLATE B-49



AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMENS: Sandy clay, CL
 LL 40 PL 16 PI 25 Cu = 2.65 TYPF SVCE FRI UN-IS*LABLU TYPF T1ST Q
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER SBC FORM 2089
 Gray, brittle, medium consistency,
 slightly fissured. High strength
 at 76, dense shales, no shale reaction.

PROJECT: Lake Darling WDS-2A-76-92
 BORING NO: 76-81M SAMPLE NO: 1
 DEPTH: 16.0 - 18.2
 HED LAB NO: 76/116 DATE 12 AUG 1976
 TRIAXIAL COMPRESSION TEST REPORT
 PLATE 12

⑦




Figure 3

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOUTHERN RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORINGS 76-81M, 76-80M AND
 76-93M
 ST. PAUL, MINN. DISTRICT
 AUG 1976

RI-R-6/766

PLATE 10B-57

①

②







Figure 7

③



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Sandy clay, CL

LL 26 PL 14 PI 13 $C_u = 2.66$ TYPE SPECIES: LUGISLEB TYPE TEST 0

REMARKS: MACHINE PRINT OUT

FORMAT AFTER ENG FORM 2009

Brown, brittle structure, soft consistency, medium strength at PL, dull shine, slow shrink reaction.

PROJECT: Lake Darling HDB-3A-76-02

BORING NO: 76-93M SAMPLE NO: 2

DEPTH: 12.0 - 14.0

HDB LAB NO: 76/116 DATE 13 AUG 69

TETRAHEDRAL COMPRESSION TEST REPORT

FIELD NO

④

SEE NOTE PLATE B-40





Figure 9

⑦



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Clayey sand, SC

LL 26 PL 13 PI 11 $C_u = 2.63$ TYPE SPECIES: LUGISLEB TYPE TEST 4

REMARKS: MACHINE PRINT OUT

FORMAT AFTER ENG FORM 2009

Light brown, brittle structure, insensitive, low strength at PL, dull shine, fast shrink reaction.

PROJECT: Lake Darling HDB-3A-76-02

BORING NO: 76-93M SAMPLE NO: 3

DEPTH: 17.0 - 19.0

HDB LAB NO: 76/116 DATE 13 AUG 69

TETRAHEDRAL COMPRESSION TEST REPORT

FIELD NO

⑧

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 76-93M

BY PAUL, MISSOURI DISTRICT

JUNE 1963

RI-R-5/787

PLATE NO. 8-50




FIG. 11, PLATE 11

Figure 11

①

* SEE NOTE PLATE 8-49





FIG. 12, PLATE 12

Figure 12

③



CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Levee clay, CL

LL 45 PL 19 PI 20 G_w = 2.70 TYPE SPECIMEN: UNDISTURBED TYPE TEST: Q

REMARKS: MACHINE PRINT OUT

FORMAT AFTER EDC FORM 1089

Soils gray structure, medium consistency, noncohesive. Medium strength at PL, dull shine, no shake reaction.

PROJECT: Lake Darling HES-34-76-02

BORING NO: 76-93M SAMPLE NO: 4

DEPTH: 35.0 - 37.0


HED LAB NO: 76/116 DATE 12 AUG 68

AXIAL COMPRESSION TEST REPORT

FIGURE 10

(2)

© SEE NOTE PLATE B-49



CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Clayey sand, SC

LL 56 PL 13 PI 12 G_w = 2.63 TYPE SPECIMEN: UNDISTURBED TYPE TEST: Q

REMARKS: MACHINE PRINT OUT

FORMAT AFTER EDC FORM 1089

Gray, brittle structure, medium consistency, noncohesive. Low strength at PL, dull shine, fast shake reaction.

PROJECT: Lake Darling HES-34-76-02

BORING NO: 76-93M SAMPLE NO: 5

DEPTH: 35.0 - 35.0

HED LAB NO: 76/116 DATE 12 AUG 68

AXIAL COMPRESSION TEST REPORT

FIGURE 11

(4)

DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTASOILS TEST DATA
LAKE DARLING DAM


BORING 76-93 M

ST PAUL, MINN DISTRICT

AGE 003


PLATE NOB-59





RI-R-8/788



ENG 2087

Figure 2






DESIGN MEMORANDUM NO. 3
 FLOOD CONTROL - LAKE DARLING
 SOURS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 78-112 M

ST. PAUL, MINN. DISTRICT

JUNE 1983


RI-R-8/759

PLATE NO. 8-40





BNC 2007

Figure 10



BNC 2007

Figure 13






Figure 8




Figure 9




Figure 11




Figure 12


DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 78-112 M

ST PAUL, MINN DISTRICT

JUNE 1963



RI-R-5/760

PLATE NQB-61





ENG 2087

Figure 19



ENG 2087

Figure 20



10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74

10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74 10-5-74




Figure 14




Figure 15




Figure 16





Figure 17

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 78-113M
 ST. PAUL, MINN. DISTRICT

JUNE 1963

R1-R-5/761

PLATE NO. 8-62



ENC 1000 2007

Figure 1




Figure 2: Gradation Curves. The graph shows a single curve representing the gradation of a material. The x-axis is labeled 'SIEVE SIZE IN INCHES' with values: 0.075, 0.15, 0.3, 0.6, 1.18, 2.0, 4.75, 9.5, 19, 37.5, 75, 150, 300, 600, 1200, 2400, 4800, 9600, 19200. The y-axis is labeled 'PERCENT PASSING' with values from 0 to 100. The curve starts at 100% for 0.075 inch and drops to 0% for 10.0 inch.





Figure 3




Normal Stress, TS

| Specimen No. | Initial Water Content, % | Optimum Water Content, % | Optimum Moisture Ratio | 95% of Max. Density, pcf | Max. Density, pcf |
|--------------|--------------------------|--------------------------|------------------------|--------------------------|-------------------|
| 81 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 82 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 83 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 84 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 85 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 86 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 87 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 88 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 89 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 90 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |

Specimen No. 81
Lake Darling Dam
Project No. 78-117M
Date 22 MAR 1979

Project No. 78-117M
Date 22 MAR 1979
Lake Darling Dam
Project No. 78-117M
Date 22 MAR 1979




Normal Stress, TS

| Specimen No. | Initial Water Content, % | Optimum Water Content, % | Optimum Moisture Ratio | 95% of Max. Density, pcf | Max. Density, pcf |
|--------------|--------------------------|--------------------------|------------------------|--------------------------|-------------------|
| 82 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 83 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 84 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 85 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 86 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 87 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 88 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 89 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 90 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |

AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Clayey gravelly sand, SK

Project No. 78-117M
Date 22 MAR 1979
Lake Darling Dam
Project No. 78-117M
Date 22 MAR 1979



EN 1110-2-1908
55 blows per inch of 3 in. layer, with 5.5 in. hammer and 12 inch drop.
6.0 inch diameter mold

| Specimen No. | Initial Water Content, % | Optimum Water Content, % | Optimum Moisture Ratio | 95% of Max. Density, pcf | Max. Density, pcf |
|--------------|--------------------------|--------------------------|------------------------|--------------------------|-------------------|
| 81 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 82 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 83 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 84 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 85 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 86 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 87 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 88 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 89 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |
| 90 | 12.5 | 8.1 | 1.25 | 123.8 | 125.8 |


DESIGN MEMORANDUM NO. 3
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
LAKE DARLING DAM
BORING 78-117M

ST PAUL, MINN. DISTRICT

JUNE 1983


R1-R-8/762

PLATE NO. 8-63



EAC 9000 2087

Figure 4




1. $\text{SAR}(\text{L}) = \text{L}(\text{SAR})$
 2. $\text{SAR}(\text{L}(\text{SAR})) = \text{SAR}(\text{L}(\text{SAR}))$
 3. $\text{SAR}(\text{L}(\text{SAR})) = \text{SAR}(\text{L}(\text{SAR}))$

1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 2680, 26


THESE RESULTS ARE IN ACCORDANCE WITH
THEORY AND EXPERIMENT. THE RESULTS
OBTAINED IN THE PRESENT STUDY
ARE IN GOOD AGREEMENT WITH THE
RESULTS OBTAINED IN THE PREVIOUS STUDY.

Remolding Conditions:
Optimum Water = 15.5%
95% of Max. Density = 107.6 pcf
Specimens were compacted in 1.4" diam
mold, 8 layers @ 3.8" each.

PROJECT : LAW DURING DOM
 NO. 5-1A-78-59-ED-HF
 PROJECT NO. : 78-117 SAMPLE NO. : 10.
 DATE :
 TIME : 12:10 N - 78 100 714 12 MAR 79
 TITLE : THE FIVE YEAR TEST REPORT



PLUMES A



NORMAL STRESS, TSI


| SPILLAGE NO. 1 | 1 | 2 | 3 |
|--------------------------|-------|-------|-------|
| INITIAL WATER CONTENT, % | 15.2 | 15.3 | 15.4 |
| WATER CONTENT, % | 100.2 | 100.9 | 100.2 |
| WATER CONTENT, % | 89 | 71 | 72 |
| WATER CONTENT, % | 57 | 57 | 57 |
| WATER CONTENT, % | 14.8 | 15.0 | 15.2 |
| WATER CONTENT, % | 102.2 | 108.6 | 112.3 |
| WATER CONTENT, % | 70 | 75 | 84 |
| WATER CONTENT, % | 55 | 53 | 48 |
| WATER CONTENT, % | 1.00 | 1.00 | 1.00 |
| WATER CONTENT, % | 1.00 | 2.00 | 4.00 |
| WATER CONTENT, % | 1.11 | 2.11 | 2.42 |
| WATER CONTENT, % | 29 | 29 | 30 |
| WATER CONTENT, % | 2.11 | 2.11 | 2.42 |
| WATER CONTENT, % | 1.40 | 1.40 | 1.40 |
| WATER CONTENT, % | 2.90 | 3.00 | 2.90 |

AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMENS: Sandy clay, CL

40 PL 14 PL 28 100 2.07 TYPE SPILLAGE No. 10-4 TYPE TEST A

REMARKS: MACHINE PRINT OUT
 FURNISH AFTER ENG FORM 100V
 EXTENSION STRESS CORRECTED
 FOR MEMBRANE RESTRAINT
 REMOLDING CONDITIONS:
 Optimum Water = 15.28
 95% of Max. Density = 105.4 pcf
 Specimens were compacted in 1.4" diam.
 mold, 8 layers @ 3/8" each.
 B Value = 0.99

PROJECT: Lake Darling Dam
 NCS-1A-78-58-ED-WF
 BORING NO: 78-117M SAMPLE NO: 15.16
 DEPTH:
 HOLE LAB NO: 78-100 DATE: 8 MAR 1979
 TRIAXIAL COMPRESSION TEST REPORT



NORMAL STRESS, TSI


| SPILLAGE NO. 2 | 1 | 2 | 3 |
|--------------------------|-------|-------|-------|
| INITIAL WATER CONTENT, % | 15.2 | 15.3 | 15.4 |
| WATER CONTENT, % | 100.2 | 100.9 | 100.2 |
| WATER CONTENT, % | 89 | 71 | 72 |
| WATER CONTENT, % | 57 | 57 | 57 |
| WATER CONTENT, % | 14.8 | 15.0 | 15.2 |
| WATER CONTENT, % | 102.2 | 108.6 | 112.3 |
| WATER CONTENT, % | 70 | 75 | 84 |
| WATER CONTENT, % | 55 | 53 | 48 |
| WATER CONTENT, % | 1.00 | 1.00 | 1.00 |
| WATER CONTENT, % | 1.00 | 2.00 | 4.00 |
| WATER CONTENT, % | 1.11 | 2.11 | 2.42 |
| WATER CONTENT, % | 29 | 29 | 30 |
| WATER CONTENT, % | 2.11 | 2.11 | 2.42 |
| WATER CONTENT, % | 1.40 | 1.40 | 1.40 |
| WATER CONTENT, % | 2.90 | 3.00 | 2.90 |

AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMENS: Sandy clay, CL

44 42 PL 14 PL 28 100 2.07 TYPE SPILLAGE No. 10-4 TYPE TEST A

REMARKS: MACHINE PRINT OUT
 FURNISH AFTER ENG FORM 100V
 EXTENSION STRESS CORRECTED
 FOR MEMBRANE RESTRAINT
 REMOLDING CONDITIONS:
 Optimum Water = 15.28
 95% of Max. Density = 105.4 pcf
 Specimens were compacted in 1.4" diam.
 mold, 8 layers @ 3/8" each.
 B Value = 0.99

PROJECT: Lake Darling Dam
 BORING NO: 78-117M SAMPLE NO: 15.16
 DEPTH:
 HOLE LAB NO: 78-100 DATE: 8 MAR 1979
 TRIAXIAL COMPRESSION TEST REPORT



DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 LAKE DARLING DAM
 BORING 78-117M

ST PAUL, MINN. DISTRICT

JUNE 1963

RI-R-6/763

PLATE NO. 8-64






Figure 6

[illegible]


1997-1998, 1998-1999, 1999-2000, 2000-2001, 2001-2002, 2002-2003, 2003-2004, 2004-2005, 2005-2006, 2006-2007, 2007-2008, 2008-2009, 2009-2010, 2010-2011, 2011-2012, 2012-2013, 2013-2014, 2014-2015, 2015-2016, 2016-2017, 2017-2018, 2018-2019, 2019-2020, 2020-2021, 2021-2022, 2022-2023, 2023-2024, 2024-2025, 2025-2026, 2026-2027, 2027-2028, 2028-2029, 2029-2030, 2030-2031, 2031-2032, 2032-2033, 2033-2034, 2034-2035, 2035-2036, 2036-2037, 2037-2038, 2038-2039, 2039-2040, 2040-2041, 2041-2042, 2042-2043, 2043-2044, 2044-2045, 2045-2046, 2046-2047, 2047-2048, 2048-2049, 2049-2050, 2050-2051, 2051-2052, 2052-2053, 2053-2054, 2054-2055, 2055-2056, 2056-2057, 2057-2058, 2058-2059, 2059-2060, 2060-2061, 2061-2062, 2062-2063, 2063-2064, 2064-2065, 2065-2066, 2066-2067, 2067-2068, 2068-2069, 2069-2070, 2070-2071, 2071-2072, 2072-2073, 2073-2074, 2074-2075, 2075-2076, 2076-2077, 2077-2078, 2078-2079, 2079-2080, 2080-2081, 2081-2082, 2082-2083, 2083-2084, 2084-2085, 2085-2086, 2086-2087, 2087-2088, 2088-2089, 2089-2090, 2090-2091, 2091-2092, 2092-2093, 2093-2094, 2094-2095, 2095-2096, 2096-2097, 2097-2098, 2098-2099, 2099-2100, 2100-2101, 2101-2102, 2102-2103, 2103-2104, 2104-2105, 2105-2106, 2106-2107, 2107-2108, 2108-2109, 2109-2110, 2110-2111, 2111-2112, 2112-2113, 2113-2114, 2114-2115, 2115-2116, 2116-2117, 2117-2118, 2118-2119, 2119-2120, 2120-2121, 2121-2122, 2122-2123, 2123-2124, 2124-2125, 2125-2126, 2126-2127, 2127-2128, 2128-2129, 2129-2130, 2130-2131, 2131-2132, 2132-2133, 2133-2134, 2134-2135, 2135-2136, 2136-2137, 2137-2138, 2138-2139, 2139-2140, 2140-2141, 2141-2142, 2142-2143, 2143-2144, 2144-2145, 2145-2146, 2146-2147, 2147-2148, 2148-2149, 2149-2150, 2150-2151, 2151-2152, 2152-2153, 2153-2154, 2154-2155, 2155-2156, 2156-2157, 2157-2158, 2158-2159, 2159-2160, 2160-2161, 2161-2162, 2162-2163, 2163-2164, 2164-2165, 2165-2166, 2166-2167, 2167-2168, 2168-2169, 2169-2170, 2170-2171, 2171-2172, 2172-2173, 2173-2174, 2174-2175, 2175-2176, 2176-2177, 2177-2178, 2178-2179, 2179-2180, 2180-2181, 2181-2182, 2182-2183, 2183-2184, 2184-2185, 2185-2186, 2186-2187, 2187-2188, 2188-2189, 2189-2190, 2190-2191, 2191-2192, 2192-2193, 2193-2194, 2194-2195, 2195-2196, 2196-2197, 2197-2198, 2198-2199, 2199-2200, 2200-2201, 2201-2202, 2202-2203, 2203-2204, 2204-2205, 2205-2206, 2206-2207, 2207-2208, 2208-2209, 2209-2210, 2210-2211, 2211-2212, 2212-2213, 2213-2214, 2214-2215, 2215-2216, 2216-2217, 2217-2218, 2218-2219, 2219-2220, 2220-2221, 2221-2222, 2222-2223, 2223-2224, 2224-2225, 2225-2226, 2226-2227, 2227-2228, 2228-2229, 2229-2230, 2230-2231, 2231-2232, 2232-2233, 2233-2234, 2234-2235, 2235-2236, 2236-2237, 2237-2238, 2238-2239, 2239-2240, 2240-2241, 2241-2242, 2242-2243, 2243-2244, 2244-2245, 2245-2246, 2246-2247, 2247-2248, 2248-2249, 2249-2250, 2250-2251, 2251-2252, 2252-2253, 2253-2254, 2254-2255, 2255-2256, 2256-2257, 2257-2258, 2258-2259, 2259-2260, 2260-2261, 2261-2262, 2262-2263, 2263-2264, 2264-2265, 2265-2266, 2266-2267, 2267-2268, 2268-2269, 2269-2270, 2270-2271, 2271-2272, 2272-2273, 2273-2274, 2274-2275, 2275-2276, 2276-2277, 2277-2278, 2278-2279, 2279-2280, 2280-2281, 2281-2282, 2282-2283, 2283-2284, 2284-2285, 2285-2286, 2286-2287, 2287-2288, 2288-2289, 2289-2290, 2290-2291, 2291-2292, 2292-2293, 2293-2294, 2294-2295, 2295-2296, 2296-2297, 2297-2298, 2298-2299, 2299-2300, 2300-2301, 2301-2302, 2302-2303, 2303-2304, 2304-2305, 2305-2306, 2306-2307, 2307-2308, 2308-2309, 2309-2310, 2310-2311, 2311-2312, 2312-2313, 2313-2314, 2314-2315, 2315-2316, 2316-2317, 2317-2318, 2318-2319, 2319-2320, 2320-2321, 2321-2322, 2322-2323, 2323-2324, 2324-2325, 2325-2326, 2326-2327, 2327-2328, 2328-2329, 2329-2330, 2330-2331, 2331-2332, 2332-2333, 2333-2334, 2334-2335, 2335-2336, 2336-2337, 2337-2338, 2338-2339, 2339-2340, 2340-2341, 2341-2342, 2342-2343, 2343-2344, 2344-2345, 2345-2346, 2346-2347, 2347-2348, 2348-2349, 2349-2350, 2350-2351, 2351-2352, 2352-2353, 2353-2354, 2354-2355, 2355-2356, 2356-2357, 2357-2358, 2358-2359, 2359-2360, 2360-2361, 2361-2362, 2362-2363, 2363-2364, 2364-2365, 2365-2366, 2366-2367, 2367-2368, 2368-2369, 23

13 4 11 27 9 14 88 4,13 7,9 10 8 8,13 22 13 5

[illegible]

Remolding conditions
Optimum Water 15.3%
95% of Max. Density 106.9 pcf
Specimens were compacted in 1.4' diam
mold, 8 layers @ 1.8" each.

1. NAME Mr. Dong Nam
Address 79-90-3011
City 79-117M State LA Zip 70117
Phone 504-835-1171 Ext. 1171
Business 79-117M State LA Zip 70117
Phone 504-835-1171 Ext. 1171







Figure 2

①




AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMEN: Lean clay, CL

LL 42 PL 19 PI 23 (w = 21.7) SPECIMEN UNDISTURBED TEST NO. 76/115

REMARKS: MACHINE PRINT OUT
 UP AT AFTER 2.00 CONDUCTION
 Brown, medium consistency, medium
 strength at PL, full shine, slow shake
 reaction, brittle structure, no odor.
 Torrance = 0.40 T/SF
 Membrane correction applied to deviator
 stresses.

Soil: Lean clay, CL
 Test No: 76/115
 Date: 7 JUL 1977

②




AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMEN: Lean clay, CL


LL 40 PL 17 PI 21 (w = 2.66) SPECIMEN UNDISTURBED TEST NO. 76/115
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER SDC FORM 2059
 S Value = 0.00

PROJECT: So Line Railroad
 BORING NO: 76-75M SAMPLE NO: 2
 DEPTH: 10.0 FT
 HRC LAB NO: 76/115 DATE: 25 APR 1977
 CRITICAL COMPRESSION TEST REPORT

③



④



SEE NOTE

SDC FORM 2059





Figure 4



LL 46 PL 17 PI 31 Co = 1.00 TYPE SPREADER UNSTABLE TYPE TEST 0

REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORN 2009

PROJECT: See Line Railroad
HCB-16-76-00-25-7
BORING NO: 76-7200 SAMPLE NO: 2
DEPTH: 30.0 - 30.0
HCB LAB NO: 76/115 DATE: 25 APR 1977
TRIAXIAL COMPRESSION TEST REPORT
PLATE 1

SEE NOTE PLATE B-49





Figure 7



LL 65 PL 25 PI 41 Co = 2.05 TYPE SPREADER UNSTABLE TYPE TEST 0

REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORN 2009

PROJECT: See Line Railroad
HCB-16-76-00-25-7
BORING NO: 76-7200 SAMPLE NO: 3
DEPTH: 30.0 - 30.0
HCB LAB NO: 76/115 DATE: 25 APR 1977
TRIAXIAL COMPRESSION TEST REPORT
PLATE 1


DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
SOU LINE RAILROAD
BORING 76-75 M

ST PAUL, MINN. DISTRICT

JUNE 1963

PLATE NO. 6-66

RI-R-2/298



①




Figure 6

ENG . FORM 2002

②




Figure 2

©





Figure 8

ENCLOSURE 2051

⑥



A-1A. STRAIN 1
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMEN
 LL 20 PL 18 FI 2
 REMARKS: MACHINE PREP
 FURNACE AFTER ENG. FOUR
 Gray, soft consistency,
 strength at PL, no shrink
 reaction, brittle struc-
 ture, no odor.





Figure 6



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Lean clay, CL

LL 30 PL 17 PI 19 Ca=2.69 TYPE SPECIMEN: UNDISTURBED TYPE TEST: Q

REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2089Brown, medium consistency, low strength
at PL, dull shine, slow shake reaction,
brittle structure, slightly sensitive.

Turnover = 0.58 TSF

Deviator stresses not corrected for
membrane restraint.PROJECT: See Line Railroad
RCS-1A-76-80-8B-F


BORING NO: 76-75M SAMPLE NO: 5

DEPTH: 40.5 - 42.4

MIL LAB NO: 76/115 DATE: 7 JUL 1977

INITIAL COMPRESSION TEST REPORT

③



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Lean clay, CL

LL 30 PL 17 PI 19 Ca=2.69 TYPE SPECIMEN: UNDISTURBED TYPE TEST: X

REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2089

B Value = 1.00

PROJECT: See Line Railroad
RCS-1A-76-80-8B-F

BORING NO: 76-75M SAMPLE NO: 5

DEPTH: 40.5 - 42.4

MIL LAB NO: 76/115 DATE: 7 JUL 1977

INITIAL COMPRESSION TEST REPORT

④

SEE NOTE PLATE B-49





Figure 8



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Silty sand, SM

LL 30 PL 18 PI 2 Ca=2.72 TYPE SPECIMEN: UNDISTURBED TYPE TEST: Q

REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2089Grey, soft consistency, very wet, low
strength at PL, no shine, rapid shake
reaction, brittle structure, insensitive,
no odor.PROJECT: See Line Railroad
RCS-1A-76-80-8B-F


BORING NO: 76-75M SAMPLE NO: 7

DEPTH: 53.5 - 55.4

MIL LAB NO: 76/115 DATE: 7 JUL 1977

INITIAL COMPRESSION TEST REPORT

⑦



ENG FORM 2087

Figure 7

⑧


DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURS RIVER, NORTH DAKOTA
SOILS TEST DATA
300 LINE RAILROAD
BORINGS 76-75M AND 76-77M

ST PAUL, MINN DISTRICT

JUNE 1983

R1-R-8/786



PLATE NO. B-67




AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Lean clay, CL

LL 40 PL 20 PI 20 Ca = 2.70 TYPE SP: LTR: LS-150, EL: TYPE TEST: L
REMARKS: MACHINE PRINT OUT
FORMAT AFTER INC FORM 2049
Brown, soft consistency, medium
strength at PL, dull shine, no shake
reaction.
S Value = 1.00
No material for "q" tests.


PROJECT: See Line Railroad
HCB-1A-76-00-00-7
BORING NO: 76-7700 SAMPLE NO: 1
DEPTH: 8.5 - 10.4
DATE: 9 MAR 1977
TEST REPORT




| Type of Specimen | |
|------------------|----------------|
| Size | 2.25 in. dia. |
| Condition | Unconsolidated |
| Preparation | Hand |
| Consolidation | None |
| Classification | Lean clay, CL |
| Remarks | |




PROJECT: See Line Railroad HCB-1A-76-00-00-7
LABORATORY NO: 76/115
BORING NO: 76-7700 SAMPLE NO: 1 DEPTH: 8.5 - 10.4 DATE: 9 MAR 1977
TEST REPORT
CONSOLIDATION TEST -- TUE 11.15.15
MACHINE PRINT OUT
FORMAT AFTER INC FORM 2049



PROJECT: See Line Railroad HCB-1A-76-00-00-7
LABORATORY NO: 76/115
BORING NO: 76-7700 SAMPLE NO: 1 DEPTH: 8.5 - 10.4 DATE: 9 MAR 1977
TEST REPORT
CONSOLIDATION TEST -- TUE 11.15.15
MACHINE PRINT OUT
FORMAT AFTER INC FORM 2049



GRADATION CHART



PROJECT: See Line Railroad HCS-1A-76-90-25-F
DSD LABORATORY NO: 76/115
BORING NO: 76-779U SAMPLE NO: 2 DEPTH: 15.0 - 16.9 DATE: 9 DEC 1977
CONSOLIDATION: 115. -- TIME (MIN)
MACHINE PRINT OUT
FORMAT AFTER ENG FOR: 40.8
FIGURE 14

FIGURE 14

⑥



[illegible][illegible]

Figure 11



PROJECT: See Line Railroad NCB-12-76-00-08-V

TEST LABORATORY NO: 76/115

BURING NO: 76-7790 SAMPLE NO: 2 DRYING: 15.0 - 16.9 DATE: 9 MAR 1977

CONSOLIDATION TEST -- TELL CAGES

ACRIME PRINT OUT
JOURNEY AFTER END OF TEST

PAGE 12

12:00 PM

• SEE NOTE PLATE B-42





Figure 1.9



AXIAL STRAIN, ϵ
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Fat clay, CM

LL 94 PL 19 PI 37 COW 2.71 TYPE SP. (1) COW UN ESTIMATED TYPE TEST C

REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 1009
Gray, soft to medium consistency.
Medium strength at FL, dull shine

PROJECT: See Line Railroad
WOB-12-76-00-00-9
B.U.I. NO: 76-7700 SAMPLE NO: 3
DEPTH:
HSD LAB NO: 76/115 DATE 25 APR 1977
TRIAL COMPRESSION TEST REPORT

DESIGN MEMORANDUM NO. 3
GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
SOO LINE RAILROAD
BORING 76-77 M
ST. LOUIS, MISSOURI DISTRICT


JUNE 1983

RI-R-5/760

PLATE NO. 1-6



①




②



Figure 7

⑤



LL 00 PL 23 FI 43

Dark gray, medium consistency. High strength at PL, gloss shine, no shrink reaction. Sample contained some large roots. Torvane = 0.65 T/5V

FOIA(b)(7): See Line MCS-1A-70-00-ED-F

8-12-70 70-7700 C.A. 4

1971: 20.3 - 20.4


THE U.S. DEPARTMENT OF JUSTICE

©




60 70

7. DATE _____



PROJECT: See Line Railroad HCS-1A-76-90-8B-F
 LAB. NO. 76-115
 BORING NO. 76-77M SAMPLE NO. 3 DEPTH: 20.5 - 22.4 DATE: 25 APR 57
 MACHINE PRINT OUT
 FOR AT AFTER ENG FORM 2006


③



PROJECT: See Line Railroad HCS-1A-76-90-8B-F
 LAB. NO. 76-115
 BORING NO. 76-77M SAMPLE NO. 4 DEPTH: 20.5 - 22.4 DATE: 25 APR 57
 MACHINE PRINT OUT
 FOR AT AFTER ENG FORM 2006

④

SEE NOTE PLATE B-49



AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMENS: Fat clay, OH

LL 66 PL 23 PI 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100
 REMARKS: MACHINE PRINT OUT
 FOR AT AFTER ENG FORM 2006
 S value = 0.95

⑦




Figure 3

⑧


DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 SOO LINE RAILROAD
 BORING 76-77M

ST. PAUL, MINN. DISTRICT

JUNE 1963


R1 - R - 5/769

PLATE NO. B-70




PROJECT: See Line Railroad NCS-1A-76-90-2B-7
 DSD LABORATORY NO: 76/115
 BORING NO: 76-7700 SAMPLE NO: 4 DEPTH: 26.5 - 28.4 FEET: 20 MBS 107
 MACHINE PRINT OUT
 FORMAT AFTER EDC FORM 20-4

①




PROJECT: See Line Railroad NCS-1A-76-90-2B-7
 DSD LABORATORY NO: 76/115
 BORING NO: 76-7700 SAMPLE NO: 4 DEPTH: 26.5 - 28.4 FEET: 20 MBS 107
 MACHINE PRINT OUT
 FORMAT AFTER EDC FORM 20-4

②



PROJECT: See Line Railroad NCS-1A-76-90-2B-7
 DSD LABORATORY NO: 76/115
 BORING NO: 76-7700 SAMPLE NO: 4 DEPTH: 26.5 - 28.4 FEET: 20 MBS 107
 MACHINE PRINT OUT
 FORMAT AFTER EDC FORM 20-4

③




AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMENS: Fat clay, OH

LL 86 PL 36 PI 99 Co = 2.75 TYP. SPEC. 1.0 UNLESS NOTED. TYPE TEST: C
 ALARM: MACHINE PRINT OUT
 FORMAT AFTER EDC FORM 20-4
 Comp. uniform consistency, high
 strength at 76, glass shine, no shale
 reaction, slight odor.


PROJECT: See Line Railroad
 NCS-1A-76-90-2B-7
 BORING NO: 76-7700 SAMPLE NO: 5
 DEPTH: 34.5 - 36.4
 HUB LAB NO: 76/115 DATE: 1 MAR 1977
 TRIAXIAL COMPRESSION TEST REPORT

⑤





CLASSIFICATION: Fat clay, OH
 M 85 P 36 S 50
 DEPTH: 34.5 - 36.4
 HUB LAB NO: 76/115
 DATE: 1 MAR 1977
 TRIAXIAL COMPRESSION TEST REPORT

⑥



PROJECT: See Line Railroad
 NCS-1A-76-90-2B-7
 BORING NO: 76-7700 SAMPLE NO: 6
 DEPTH: 34.5 - 36.4
 HUB LAB NO: 76/115
 DATE: 1 MAR 1977
 TRIAXIAL COMPRESSION TEST REPORT


⑦



PROJECT: See Line Railroad WGS-1A-76-90-83-F
 LAB. NO: 76/115
 BORING NO: 76-77M SAMPLE NO: 4 DEPTH: 26.5 - 26.4 DATE: 9 MAR 57
 CONSOLIDATION TEST - TIME PLOTS
 MACHINE PRINT OUT
 FORMAT AFTER ENG. PLOT 21.0
 FIGURE 17

③


SEE NOTE PLATE B-49



| Type of Specimen | | Before Test | | After Test | |
|---------------------------|-------------|-------------------------|-------------------------------------|-------------------|----------|
| Specimen No. | 1.00 | Water Content, % | 39.8 | Water Content, % | 35.1 |
| Overburden Pressure, lb | 0.5 | Void Ratio, e_v | 1.190 | Void Ratio, e_v | 0.993 |
| Pressure, lb | 0.5 | Settlement, in | 92 | Settlement, in | 100 |
| Compression Index, C_c | | Dry Density, γ_d | 78.3 lb/ft ³ | | |
| Classification | FS 61.2, CL | Age of σ_v | = 10 ⁴ min | | |
| PL | 82 | Project | See Line Railroad WGS-1A-76-90-83-F | | |
| PL | 20 | Lab. No. | 76/115 | | |
| Remarks | | | | | |
| | | Boring No. | 76-77M | Sample No. | 3 |
| | | Depth | 24.5 - 26.4 | Date | 9 MAR 57 |
| CONSOLIDATION TEST REPORT | | | | | |

Figure 18

⑦



PROJECT: See Line Railroad WGS-1A-76-90-83-F
 LAB. NO: 76/115
 BORING NO: 76-77M SAMPLE NO: 5 DEPTH: 34.5 - 36.4 DATE: 9 MAR 57
 CONSOLIDATION TEST - TIME PLOTS
 MACHINE PRINT OUT
 FORMAT AFTER ENG. PLOT 21.0
 FIGURE 19

⑧


DESIGN MEMORANDUM NO. 3
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 SOO LINE RAILROAD
 BORING 76-77M

ST. PAUL, MINN. DISTRICT

APR 1963


RI-R-8/770

PLATE NO. B-71



PROJECT: See Line Railroad HCS-1A-76-00-03-7
 LAB LABORATORY NO: 76/115
 BORING NO: 76-7780 SAMPLE NO: 5 DEPTH: 34.5 - 36.4 DATE: 8 MAR 1977
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2000


①




PROJECT: See Line Railroad HCS-1A-76-00-03-7
 LAB LABORATORY NO: 76/115
 BORING NO: 76-7780 SAMPLE NO: 5 DEPTH: 34.5 - 36.4 DATE: 8 MAR 1977
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2000

FIGURE 21

②



ENG Form 2007



CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMEN: Put clay, OH

LL 66 PL 23 PI 61 C= 2.71 TYPE SPECIMEN: UNDETERMINED TYPE TEST
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 1009
 9 values = 1.00

PROJECT: See Line Railroad
 HCS-1A-76-00-03-7
 BORING NO: 76-7780 SAMPLE NO: 6
 DEPTH: 43.5 - 45.4
 DATE: 8 MAR 1977
 THICKNESS COMPRESSION TEST REPORT

⑤





Figure 10


⑥

PROJECT: See Line Railroad
 LAB LABORATORY NO: 76/115
 BORING NO: 76-7780
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2000



SNC Form 2887

Figure 14



AXIAL STRAIN, %


CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Pat clay, OH

LL 64 PL 23 PI 41 $C_u = 2.71$ TYPE SPECIMENS UNDISTURBED TYPE TEST QREMARKS: MACHINE PRINT OUT
FORNAT AFTER SNC FORM 200-9Gray, medium strength at PL, glass
shine, no shake reaction.


PROJECT: See Line Railroad
HCS-1A-76-90-25-F
BORING NO: 76-77M SAMPLE NO: 6
DEPTH: 43.5 - 45.4
MPI LAB NO: 76/115 DATE: 30 MAR 1977
TYPICAL COMPRESSION TEST REPORT
FIGURE 15

SEE NOTE PLATE B-48



PROJECT: See Line Railroad HCS-1A-76-90-25-F
MPI LABORATORY NO: 76/115
BORING NO: 76-77M SAMPLE NO: 6 DEPTH: 43.5 - 45.4 DATE: 30 MAR 1977
CONSOLIDATION TEST -- TYPICAL
MACHINE PRINT OUT
FORNAT AFTER SNC FORM 200-9

FIGURE 16



PROJECT: See Line Railroad HCS-1A-76-90-25-F
MPI LABORATORY NO: 76/115
BORING NO: 76-77M SAMPLE NO: 6 DEPTH: 43.5 - 45.4 DATE: 30 MAR 1977
CONSOLIDATION TEST -- TYPICAL
MACHINE PRINT OUT
FORNAT AFTER SNC FORM 200-9

FIGURE 17

⑧


DESIGN MEMORANDUM NO. 3
GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
SDO LINE RAILROAD
BORING 76-77 M

ST PAUL, MINN DISTRICT

JUNE 1983

R1-R-8/771

PLATE NO. 8-72



PROJECT: See Line Railroad HCS-1A-76-90-23-F
 LAB. LABORATORY NO: 76/115
 BORING NO: 76-7780 SAMPLE NO: 0 DEPTH: 43.5 - 45.4 DATE: 30 MAR 1977
 CONSOLIDATION TEST -- TIME CL VES
 JACQUES PRINT OUT
 FORMAT AFTER EPC FOR: 2..

①






Figure 10

②



PROJECT: See Line Railroad HCS-1A-76-90-23-F
 LAB. LABORATORY NO: 76/115
 BORING NO: 76-7780 SAMPLE NO: 7 DEPTH: 53.5 - 55.4 DATE: 30 MAR 1977
 CONSOLIDATION TEST -- TIME CL VES
 JACQUES PRINT OUT
 FORMAT AFTER EPC FOR: 2000





③




PROJECT: See Line Railroad HCS-1A-76-90-23-F
 LAB. LABORATORY NO: 76/115
 BORING NO: 76-7780 SAMPLE NO: 7 DEPTH: 53.5 - 55.4 DATE: 30 MAR 1977
 CONSOLIDATION TEST -- TIME CL VES
 JACQUES PRINT OUT
 FORMAT AFTER EPC FOR: 2000

④

PROJECT: See Line Railroad
 LAB. LABORATORY NO: 76/115
 BORING NO: 76-7780 SAMPLE NO: 7
 JACQUES PRINT OUT
 FORMAT AFTER EPC FOR: 2000



DESIGN MEMORANDUM NO. 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
SOO LINE RAILROAD
BORINGS 76-77M AND 76-79M



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST


DESCRIPTION OF SPECIMEN: Sandy clay, CL

LL 33 PL 15 PI 10 Ca = 2.69 TYPE: SPECIMEN 1 UNTESTED TYPE: TEST 0

REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2049
Gray, brittle structure, stiff consistency, medium strength at PL, dull shine, medium shake reaction.


PROJECT: See Line Railroad
HCB-1A-76-90-2B-7
BORING NO: 76-TWD SAMPLE NO: 1
DEPTH: 11.0 - 12.9
HCB LAB NO: 76/115 DATE: 7 JUL 1977
TRIAXIAL COMPRESSION TEST REPORT

①



ENG. 100-100

GRADATION CURVES



AXIAL STRAIN, %


CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMEN: Sandy clay, CL

LL 41 PL 15 PI 10


REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2049
Gray, medium to stiff consistency, medium strength at PL, slow shake reaction, takes sand and gravel in diameter.

SEE NOTE PLATE




PROJECT: See Line Railroad HCB-1A-76-90-2B-7
HCB LABORATORY NO: 76/115
BORING NO: 76-TWD SAMPLE NO: 2 DEPTH: 42.0 - 43.2 DATE: 7 JUL 1977
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2049

③



PROJECT: See Line Railroad HCB-1A-76-90-2B-7
HCB LABORATORY NO: 76/115
BORING NO: 76-TWD SAMPLE NO: 2 DEPTH: 42.0 - 43.2 DATE: 7 JUL 1977
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2049

④



PROJECT: See Line Railroad HCB-1A-76-90-2B-7
HCB LABORATORY NO: 76/115
BORING NO: 76-TWD SAMPLE NO: 2 DEPTH: 42.0 - 43.2 DATE: 7 JUL 1977
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2049

⑤





Figure 10



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Sandy clay, CL

LL 41 PL 15 PI 26 G_w = 2.74 TYPE SPECIMENS UNCONSOLIDATED TYPE TEST 9

REMARKS: MACHINE PRINT OUT
 FURNISHED AFTER EDC FORM 2009
 Gray, medium to stiff consistency,
 medium strength at PL, dull shine,
 slow shake reaction. Sample contains
 sand and gravel up to 1-inch
 in diameter.

PROJECT: See Line Railroad
 HCS-1A-76-90-2B-7
 BORING NO: 76-79 SAMPLE NO: 2
 DEPTH: 42.0 - 43.2
 HCS LAB NO: 76/115 DATE: 7 JUL 1977
 TIA LCL COMPRESSION TEST REPORT
 FIGURE 11

* SEE NOTE PLATE 8-49





Figure 13

PROJECT: See Line Railroad HCS-1A-76-90-2B-7
 HCS LABORATORY NO: 76/115
 BORING NO: 76-79 SAMPLE NO: 2 DEPTH: 42.0 - 43.2 DATE: 7 JUL 1977
 CONSOLIDATION TEST -- TIA CLAY
 MACHINE PRINT OUT
 FURNISHED AFTER EDC FORM 2009

⑦

⑧

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 300 LINE RAILROAD
 BORING 76-79 M

ST PAUL, MINN DISTRICT

JUNE 1983

RI-R-8/773

PLATE NO 8-74





Figure 17

①

* SEE NOTE PLATE B-48




PROJECT: See Line Railroad HCB-1A-76-90-82-7
 AND LABORATORY NO: 76/115
 BORING NO: 76-72411 SAMPLE NO: 3 WATER: 53.0 - 54.4 DATE: 7 JUL 1977
 CONSOLIDATION TEST - TEST CURVES

WATER: 53.0 - 54.4
 PROJECT: 76-72411

FIGURE 18

③




PROJECT: Soo Line Railroad HCS-1A-76-90-8B-7
 H&D LABORATORY NO: 76/115
 BORING NO: 76-799M SAMPLE NO: 3 DEPTH: 53.0 - 54.4 DATE: 7 JUL 1977
 CONSOLIDATION TEST -- TIME CURVES
 JACKSON PRINT OUT
 FORMAT AFTER EXP 100: 20.0

FIGURE 18

②

SEE NOTE PLATE B-48



PROJECT: Soo Line Railroad HCS-1A-76-90-8B-7
 H&D LABORATORY NO: 76/115
 BORING NO: 76-799M SAMPLE NO: 3 DEPTH: 53.0 - 54.4 DATE: 7 JUL 1977
 CONSOLIDATION TEST -- TIME CURVES
 JACKSON PRINT OUT
 FORMAT AFTER EXP 100: 20.0

FIGURE 20

④

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 SOO LINE RAILROAD
 BORING 76-79M

ST PAUL, MINN DISTRICT

JUNE 1983

RI-R-5/774

PLATE NO B-75




FIGURE 23

①





FIGURE 22

②




AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Study clay, CL


LL 66 PL 14 FI 30 G_o = 2.70 TYPE SPECIMEN: REMOLDED TYPE TEST
REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2085
Sampling conditions:
System Moisture = 17.0
Mo. Density (100.0) x 100 = 100.0 pcf
Computed by inserting into 1.4th diam.
solid, 0 layers at 1/2" each.

PROJECT: Highway No. 1, Road Base
BORING NO: 74-4077 SAMPLE NO: 1
DEPTH: 1.5 - 8.0
HND LAB NO: 74/248 DATE: 6 DEC 1964
TRIAXIAL COMPRESSION TEST REPORT

③



④



TYPE OF SPECIMEN: Remolded
Size: 4.50 in. dia.
Overburden Pressure: 0
Deviator Stress: 1.35
Classification: Study of
Mo. Density: 100.0
Mo. Density (100.0) x 100 = 100.0 pcf
Computed by inserting into 1.4th diam.
solid, 0 layers at 1/2" each.





Figure 1



CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Sandy clay, CL

LL 66 PL 14 PI 30 Co = 2.70 TYPE SPECIMEN: REMOLDED TYPE TEST 4

REMARKS: MACHINE PRINT OUT

FORMAT AFTER ENG FORM 1089

Remolding Conditions:

Optimum moisture = 17.5%

Max. Amplitude (100.9) \pm 906 = 104.5 psi

Compacted by ramming into 1.6" diam.

mold, 5 layers at 3/8" each.

PROJECT: Highway No. 5, Road Bridge
 BORING NO: 74-46TP SAMPLE NO: 1
 DEPTH: 1.5 - 8.0
 HED LAB NO: 74/345 DATE 8 DEC 1974
 TRIAXIAL COMPRESSION TEST REPORT
 FIGURE 2





Figure 3




PROJECT: Highway No. 5, Road Bridge
 HED LABORATORY NO: 74/345
 BORING NO: 74-46TP SAMPLE NO: 1 DEPTH: 1.5 - 8.0 DATE: 8 DEC 1974
 CONSOLIDATION TEST - TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 1088
 FIGURE 4

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 STATE HIGHWAY NO. 5
 BORINGS 64-10M AND 74-46TP
 ST. PAUL, MINN. DISTRICT

JUNE 1983


RI-R-8/775

PLATE NO. 8-76





PROJECT: **Hwy-12-75-25-25-25**
 HD LABORATORY NO: 74/343 Highway No. 5, Road Base
 BORING NO: 74-4077 SAMPLE NO: 1 DEPTH: 1.5 - 8.0 DATE: 6 DEC 1974
 CONSOLIDATION TEST -- TIME RELATED
 MACHINE PRINT OUT
 FORMAT AFTER ENG FOR: 2046 FILE: 1129

①




PROJECT: **Hwy-12-75-25-25-25**
 HD LABORATORY NO: 74/343 Highway No. 5, Road Base
 BORING NO: 74-4077 SAMPLE NO: 1 DEPTH: 1.5 - 8.0 DATE: 6 DEC 1974
 CONSOLIDATION TEST -- TIME RELATED
 MACHINE PRINT OUT
 FORMAT AFTER ENG FOR: 2046 FILE: 1130

②




AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMEN: Sandy clay, CL
 LL 27 PL 12 PI 15 G_w = 2.73 TYPE SPECIMEN: REMOLDED TYPE TEST: 0
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER ENG FOR: 2046
 Remolding Conditions:
 Opt. moisture (17.9) - 15 = 16.95
 Max. Density (100.1) x 90% = 100.0 per
 Computed by blending into 1.4" diam.
 mold, 6 layers at 3/8" each.

⑤



AXIAL STRAIN, %
 CONTROLLED-STRAIN TEST
 DESCRIPTION OF SPECIMEN: Sandy clay, CL
 LL 27 PL 12 PI 15 G_w = 2.73 TYPE SPECIMEN: REMOLDED TYPE TEST: 0
 REMARKS: MACHINE PRINT OUT
 FORMAT AFTER ENG FOR: 2046
 Remolding Conditions:
 Optimum Moisture = 17.95
 Max. Density (100.1) x 95% = 100.7 per
 Computed by blending into 1.4" diam.
 mold, 6 layers at 3/8" each.

⑥






Figure 1




Figure 4




Figure 3





Figure 11

DESIGN MEMORANDUM NO 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 STATE HIGHWAY NO. 5
 BORING 74-46TP
 ST PAUL, MINN DISTRICT


JUNE 1963

RI-R-8/776

PLATE NO 8-77



①




AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMEN: Clayey sand, SC


LL 35 PL 13 PI 32 G_h = 2.67 TYPE SPECIMEN: Remolded TYPE TEST: 1
REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2009
Remolding conditions:
Optimum moisture = 13.9%
Max. density (117.3) x 95 = 111.3 pcf
Compacted by hand into 1.4" diam.
mold, 8 layers at 3/8" each.

PROJECT: Highway No. 5, Road Hole
Boring No: 74-4777 SAMPLE NO: 1
DEPTH: 1.6 - 8.0
HAW LAB NO: 74/342 DATE: 18 DEC 1974
TRIAxIAL COMPRESSION TEST REPORT
FIGURE 8

②



③




AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMEN: Sandy clay, CL

LL 34 PL 12 PI 32 G_h = 2.67 TYPE SPECIMEN: Remolded TYPE TEST: 1
REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2009
Remolding conditions:
Optimum moisture = 16.3%
Max. density (112.9) x 95 = 107.2 pcf
Compacted by hand into 1.4" diam.
mold, 8 layers at 3/8" each.

PROJECT: Highway No. 5, Road Hole
Boring No: 74-4777 SAMPLE NO: 6
DEPTH: 8.0 - 14.0
HAW LAB NO: 74/342 DATE: 17 JAN 1975
TRIAxIAL COMPRESSION TEST REPORT
FIGURE 9

④



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMEN: Clayey sand, NC

LL 35 PL 13 PI 22 GA-2.67 TYPE: SPILLERS: REINFORCED TYPE TEST: R

REMARKS: MACHINE PRINT OUT

FORMAT AFTER ENG FORM 2045

Sampling Conditions:

Optimum moisture = 13.9%

Max. density (117.2) x 95% = 111.2 pcf

Compacted by hand into 1.4" diam.

mold, 8 layers at 3/8" each.

PROJECT: Highway No. 5, Road Raise



BORING NO: 74-477P SAMPLE NO: 1

DEPTH: 1.8 - 8.0

MAD LAB NO: 74/342 DATE: 18 DEC 1974

TRIAxIAL COMPRESSION TEST REPORT

FIGURE 10



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMEN: Sandy clay, CL

LL 34 PL 12 PI 22 GA-2.67 TYPE: SPILLERS: REINFORCED TYPE TEST: R

REMARKS: MACHINE PRINT OUT

FORMAT AFTER ENG FORM 2045

Sampling Conditions:

Optimum moisture = 16.3%

Max. density (112.9) x 96% = 106.1 pcf

Compacted by hand into 1.4" diam.

mold, 8 layers at 3/8" each.

PROJECT: Highway No. 5, Road Raise

BORING NO: 74-477P SAMPLE NO: 6

DEPTH: 8.0 - 14.0

MAD LAB NO: 74/342 DATE: 17 JAN 1975

TRIAxIAL COMPRESSION TEST REPORT

FIGURE 10

| 1 | 2 | 3 |
|-------|-------|-------|
| 130.2 | 109.9 | 110.0 |
| 71 | 71 | 71 |
| 31 | 31 | 31 |
| 14.2 | 11.6 | 11.9 |
| 121.2 | 112.2 | 112.2 |
| 70 | 75 | 78 |
| 30 | 48 | 48 |
| .00 | .00 | .00 |
| 1.00 | 1.00 | 4.00 |
| 1.44 | 2.49 | 2.81 |
| 30 | 31 | 31 |
| 1.64 | 2.43 | 2.81 |
| 1.400 | 1.400 | 1.400 |
| 3.003 | 3.019 | 2.998 |

TYPE TEST: R

HIGHWAY NO. 5, ROAD RAISE

BORING NO. 74-477P SAMPLE NO. 1

DEPTH: 8.0

MAD LAB NO. 74/342 DATE: 18 DEC 1974

TRIAxIAL COMPRESSION TEST REPORT

FIGURE 9

| 1 | 2 | 3 |
|-------|-------|-------|
| 130.2 | 109.9 | 110.0 |
| 71 | 71 | 71 |
| 31 | 31 | 31 |
| 14.2 | 11.6 | 11.9 |
| 121.2 | 112.2 | 112.2 |
| 70 | 75 | 78 |
| 30 | 48 | 48 |
| .00 | .00 | .00 |
| 1.00 | 1.00 | 4.00 |
| 1.44 | 2.49 | 2.81 |
| 30 | 31 | 31 |
| 1.64 | 2.43 | 2.81 |
| 1.400 | 1.400 | 1.400 |
| 3.003 | 3.019 | 2.998 |

TYPE TEST: R

HIGHWAY NO. 5, ROAD RAISE

BORING NO. 74-477P SAMPLE NO. 6

DEPTH: 14.0

MAD LAB NO. 74/342 DATE: 17 JAN 1975

TRIAxIAL COMPRESSION TEST REPORT

FIGURE 9

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 STATE HIGHWAY NO. 5
 BORING 74-477P

ST PAUL, MINN DISTRICT

JUNE 1983

RI-R-8/777

PLATE NO 6-78




Figure 7

①




Figure 5

②




Figure 1

⑤




Figure 4

⑥




Figure 3

AXIAL STRAIN

CONTROLLED-STRESS

DESCRIPTION OF

LL 31 PL 15

REMARKS: JACKET

TURNED AFTER

Had, brown sandy

gravel patches,

consistency, loose

consistency at PL,

shale reaction.


PROJECT:

NO. LABORATORY

BORING NO: 74

JACKET TEST

FORMAT AFTER




CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Sandy clay, CL

LL 31 PL 15 PI 16 Co= 2.77 TYPE SPECIMEN: UNDISTURBED TYPE TEST Q
REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2039

Mod. brown sandy clay, some sand and gravel pebbles. Brittle structure, still consistency, insensitive, medium toughness at PL, no shine, sluggish shake reaction.


PROJECT: HSB-1A-75-25-48-B
Highway No. 5, Road Bridge
BORING NO: 74-49M SAMPLE NO: 11
DEPTH: 25.5 - 27.6
NRD LAB NO: 74/342 DATE: 17 JAN 1975
TRIAXIAL COMPRESSION TEST REPORT
FIGURE 3




CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Sandy clay, CL

LL 31 PL 15 PI 16 Co= 2.77 TYPE SPECIMEN: UNDISTURBED TYPE TEST R
REMARKS: MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2039

PROJECT: HSB-1A-75-25-48-B
Highway No. 5, Road Bridge
BORING NO: 74-49M SAMPLE NO: 11
DEPTH: 25.5 - 27.6
NRD LAB NO: 74/342 DATE: 17 JAN 1975
TRIAXIAL COMPRESSION TEST REPORT
FIGURE 4



PROJECT: HSB-1A-75-25-48-B
NRD LABORATORY NO: 74/342 Highway No. 5, Road Bridge
BORING NO: 74-49M SAMPLE NO: 11 DEPTH: 25.5 - 27.6 DATE: 17 JAN 1975
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2038
FIGURE 5




PROJECT: HSB-1A-75-25-48-B
NRD LABORATORY NO: 74/342 Highway No. 5, Road Bridge
BORING NO: 74-49M SAMPLE NO: 11 DEPTH: 25.5 - 27.6 DATE: 17 JAN 1975
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER ENG FORM 2038
FIGURE 6

DESIGN MEMORANDUM NO 3 GENERAL
FLOOD CONTROL - LAKE DARLING
SOURIS RIVER, NORTH DAKOTA
SOILS TEST DATA
STATE HIGHWAY NO. 5
BORINGS 74-47TP AND 74-49M
ST. PAUL, MINN. DISTRICT

JUNE 1983

RI-R-8/778


PLATE HSB-79



PROJECT: HCS-1A-75-25-23-B
 HCS LABORATORY NO: 74/342 Highway No. 5, Road Raise
 BORING NO: 74-00H DATE: 11 DEPT: 25.5 - 27.6 DATE: 17 JAN 1975
 CONSOLIDATION TEST -- TENSILE

JACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2066


FIGURE 4c



2067

Figure 2

②




PROJECT: HCS-1A-75-25-23-B
 HCS LABORATORY NO: 74/342 Highway No. 5, Road Raise
 BORING NO: 74-00H DATE: 11 DEPT: 25.5 - 27.6 DATE: 17 JAN 1975
 CONSOLIDATION TEST -- TENSILE

JACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2066

FIGURE 7b

③



PROJECT: HCS-1A-75-25-23-B
 HCS LABORATORY NO: 74/342 Highway No. 5, Road Raise
 BORING NO: 74-00H DATE: 11 DEPT: 25.5 - 27.6 DATE: 17 JAN 1975
 CONSOLIDATION TEST -- TENSILE

JACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2066

FIGURE 7c

④

PROJECT: HCS-1A-75-25-23-B
 HCS LABORATORY NO: 74/342 Highway No. 5, Road Raise
 BORING NO: 74-00H DATE: 11 DEPT: 25.5 - 27.6 DATE: 17 JAN 1975
 CONSOLIDATION TEST -- TENSILE


JACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2066

ASTAL STRA
 CONTROLLED-STR
 DESCRIPTION 00

LL 57 PL 28

REMARKS: ROAD
 FORMAT AFTER

Gray - Brown Soil
 black structure
 section of some
 center down. 00
 throughout. 00
 from center to
 low velocity. 00
 high plane shear
 Specimen from 00



AXIAL STRAIN, %

CONTROLLED-STRAIN TEST

DESCRIPTION OF SPECIMENS: Fat clay, CH

LL 57 PL 21 PI 36 G_s = 2.75 TYPE SPECIMENS: UNDISTURBED TYPE TEST Q

REMARKS: MACHINE PRINT OUT

FORMAT AFTER SMC FORM 2089

Gray-brown fat clay. Friction, brittle. Shrinkage from center to bottom section of core. Some sample disturbance center down. Calcareous stringers throughout. Considerably more moist from center to top. Medium consistency. Incompressible. Medium toughness at PL. High gloss shine, no shade reaction. Specimen from upper portion.

PROJECT: HW-14-75-25-2B-4

Highway No. 5, Road Raise


BORING NO: 74-50M SAMPLE NO: 4

DEPTH: 10.0 - 12.2

HW-14-75-25-2B-4 DATE: 1 JAN 1975


AXIAL COMPRESSION TEST REPORT

FIGURE 5



| Type of Specimen | Undisturbed | Disturbed | After Test |
|----------------------------|-------------------------------|-----------|------------|
| State | 4.64 in. dia. 1.00 in. height | | |
| Overburden Pressure, p_o | 7/100 lb | 29.5 lb | 26.8 lb |
| Permeability, k_v | 7/100 lb | 0.876 lb | 0.751 lb |
| Consolidation Index, C_c | | 33 | 32 |
| Classification | Fat clay, CH | | |
| Moisture Content, w | 32.6 | 32.9 | 31.5 |
| Shrinkage, s | 1.417 | 1.418 | 1.422 |
| Void Ratio, e | 2.965 | 2.970 | 2.939 |

Figure 7



PROJECT: HW-14-75-25-2B-4
 HW LABORATORY NO: 74/342 Highway No. 5, Road Raise
 BORING NO: 74-50M SAMPLE NO: 4 DEPTH: 10.0 - 12.2 DATE: 17 JAN 1975
 MACHINE PRINT OUT
 FORMAT AFTER SMC FORM 2089




Figure 4


DESIGN MEMORANDUM NO 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 STATE HIGHWAY NO. 5
 BORINGS 74-49M AND 74-50M

ST. PAUL, MINN. DISTRICT

JUNE 1968

RI-R-6/773

PLATE NO 6-56



AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Lean clay, CL


LL 60 PL 36 PI 34 G_o = 2.70 TYPE SPECIMEN: UNDISTURBED TYPE TEST Q

REMARKS: MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2069

Dark brown lean clay, mottled orange brown and gray. Soft consistency, plastic structure, slightly sensitive. Medium toughness at 70, dull shine, and sluggish shakedown reaction.

PROJECT: Highway No. 5, Road Bridge
BORING NO: 74-008 SAMPLE NO: 7
DEPTH: 16.8 - 19.0
NED LAB NO: 74/342 DATE: 6 DEC 57
TRIAXIAL COMPRESSION TEST REPORT
FIGURE 1

①




AXIAL STRAIN, %
CONTROLLED-STRAIN TEST
DESCRIPTION OF SPECIMENS: Lean clay, CL

LL 60 PL 36 PI 34 G_o = 2.70 TYPE SPECIMEN: UNDISTURBED TYPE TEST R

REMARKS: MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2069


PROJECT: Highway No. 5, Road Bridge
BORING NO: 74-008 SAMPLE NO: 7
DEPTH: 16.8 - 19.0
NED LAB NO: 74/342 DATE: 6 DEC 57
TRIAXIAL COMPRESSION TEST REPORT
FIGURE 2

②




PROJECT: Highway No. 5, Road Bridge
NED LABORATORY NO: 74/342
BORING NO: 74-008 SAMPLE NO: 7
DEPTH: 16.8 - 19.0 DATE: 6 DEC 57
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2069
FIGURE 3

③




PROJECT: Highway No. 5, Road Bridge
NED LABORATORY NO: 74/342
BORING NO: 74-008 SAMPLE NO: 7
DEPTH: 16.8 - 19.0 DATE: 6 DEC 57
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2069
FIGURE 4

④



PROJECT: Highway No. 5, Road Bridge
NED LABORATORY NO: 74/342
BORING NO: 74-008 SAMPLE NO: 7
DEPTH: 16.8 - 19.0 DATE: 6 DEC 57
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2069
FIGURE 5



PROJECT: Highway No. 5, Road Bridge
NED LABORATORY NO: 74/342
BORING NO: 74-008 SAMPLE NO: 7
DEPTH: 16.8 - 19.0 DATE: 6 DEC 57
CONSOLIDATION TEST -- TIME CURVES
MACHINE PRINT OUT
FORMAT AFTER EBC FORM 2069
FIGURE 6





Figure 3

③



PROJECT: HSB-1A-75-35-3B-8
 HSB LABORATORY NO: 74/342 Highway No. 5, Road Bridge
 BORING NO: 74-50M SAMPLE NO: 7 DEPTH: 16.8 - 19.0 DATE: 4 DEC 1974
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2088

FIGURE 3a

④





Figure 5

⑦




⑧

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 STATE HIGHWAY NO. 5
 BORING 74-50M
 ST. PAUL, MINN. DISTRICT


JUNE 1983

RI-R-8/780


PLATE NO. 8-51




PROJECT: HSB-75-75-25-25-25
 HIGHWAY No. 5, Road No. 11
 BORING NO: 74-008 SAMPLE NO: 11
 DEPTH: 27.0 - 30.0
 HAD LAB NO 74/248 DATE 18 DEC 1974
 TRIAXIAL COMPRESSION TEST REPORT
 FIGURE 1




PROJECT: HSB LABORATORY NO: 74-008
 BORING NO: 74-008
 MACHINE PRINT OUT
 FORMAT AFTER EDC FORM 1089



PROJECT: HSB-75-75-25-25-25
 HSB LABORATORY NO: 74/248 Highway No. 5, Road No. 11
 BORING NO: 74-008 SAMPLE NO: 11 DEPTH: 27.0 - 30.0 DATE: 18 DEC 1974
 CONSOLIDATION TEST -- TIME CLAY
 MACHINE PRINT OUT
 FORMAT AFTER EDC FORM 1089




PROJECT: HSB LABORATORY NO: 74-008
 BORING NO: 74-008
 MACHINE PRINT OUT
 FORMAT AFTER EDC FORM 1089



PROJECT: **WIS-75-25-28-2**
 HND LABORATORY NO: 74/342 Highway No. 5, Road No. 11
 BORING NO: 74-50M SAMPLE NO: 11 DEPTH: 27.8 - 30.0 DATE: 18 DEC 1974
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2088

FIGURE 3a


③



PROJECT: **WIS-75-25-28-2**
 HND LABORATORY NO: 74/342 Highway No. 5, Road No. 11
 BORING NO: 74-50M SAMPLE NO: 11 DEPTH: 27.8 - 30.0 DATE: 18 DEC 1974
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE PRINT OUT
 FORMAT AFTER ENG FORM 2088


FIGURE 3b

④



PROJECT: **WIS-75-25-28-2**
 HND LABORATORY NO: 74/342 Highway No. 5, Road No. 11
 BORING NO: 74-50M SAMPLE NO: 11 DEPTH: 40.0 - 42.5
 TRIAXIAL COMPRESSION TEST REPORT
 FIGURE 5

⑦



PROJECT: **WIS-75-25-28-2**
 HND LABORATORY NO: 74/342 Highway No. 5, Road No. 11
 BORING NO: 74-50M SAMPLE NO: 11 DEPTH: 40.0 - 42.5
 TRIAXIAL COMPRESSION TEST REPORT
 FIGURE 6

⑥

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURIS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 STATE HIGHWAY NO. 5
 BORING 74-50M
 ST PAUL, MINN. DISTRICT

JUNE 1983

RI-R-5/781

PLATE NO. 6-62





Figure 7

①



PROJECT: HSB-14-75-35-22-4
 HSB LABORATORY NO: 74/342 Highway No. 5, Road Station
 BORING NO: 74-008 SAMPLE NO: 15 DEPTH: 40.0 - 42.5 FEET DATE: 6 DEC 1974
 MACHINE PRINT OUT
 FORMAT AFTER ENR FORM 2088

PROJECT: HSB-14-75-35-22-4
 HSB LABORATORY NO: 74-008
 BORING NO: 74-008
 MACHINE PRINT OUT
 FORMAT AFTER ENR 1

②





Figure 8

③



④

AD-A136 229

LAKE DARLING FLOOD CONTROL PROJECT SOURIS RIVER NORTH
DAKOTA GENERAL PROJ..(U) CORPS OF ENGINEERS ST PAUL MN
ST PAUL DISTRICT JUN 83


3/3

UNCLASSIFIED


F/G 8/7

NL

| | | | | |
|--|--|--|--|---------|
| | | | | END |
| | | | | DATE |
| | | | | ENTERED |
| | | | | 1 84 |
| | | | | DTIC |




MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A




PROJECT: HSB-24-75-25-25-2
 MED LABORATORY NO: 74/342 Highway No. 5, Road Station
 BORING NO: 74-50M SAMPLE NO: 15 DEPTH: 49.0 - 49.5 DATE: 6 DEC 1974
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 1088

③




PROJECT: HSB-24-75-25-25-2
 MED LABORATORY NO: 74/342 Highway No. 5, Road Station
 BORING NO: 74-50M SAMPLE NO: 18 DEPTH: 49.0 - 49.5 DATE: 6 DEC 1974
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 1088

④



PROJECT: HSB-24-75-25-25-2
 MED LABORATORY NO: 74/342 Highway No. 5, Road Station
 BORING NO: 74-50M SAMPLE NO: 15 DEPTH: 49.0 - 49.5 DATE: 6 DEC 1974
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 1088



PROJECT: HSB-24-75-25-25-2
 MED LABORATORY NO: 74/342 Highway No. 5, Road Station
 BORING NO: 74-50M SAMPLE NO: 18 DEPTH: 49.0 - 49.5 DATE: 6 DEC 1974
 MACHINE PRINT OUT
 FORMAT AFTER EBC FORM 1088

⑦

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 STATE HIGHWAY NO. 5
 BORING 74-50M
 ST. PAUL, MINN. DISTRICT

JUNE 1993
 PLATE NO. 8-63

RI-R-9/782





Figure 1



PROJECT: HWS-22-75-25-25-25


HWS LABORATORY NO: 74-248

BORING NO: 74-248 SAMPLE NO: 18 DEPTH: 47.5 - 50.0 DATE: 11 DEC 1974

CONSOLIDATION TEST -- TIME CURVES

MASSIVE PRINT OUT
FORMAT AFTER ENG FORM 2048


FIGURE 2



PROJECT: **W-22-73-22-2**
 H&D LABORATORY NO: 74/342
 BORING NO: 74-222 SAMPLE NO: 10 DEPTH: 47.5 - 50.0 DATE: 18 DEC 1974
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE: RAIST OUT
 FORMAT: AFTER EEC FORM 2028

FIGURE 3a

②



PROJECT: **W-22-73-22-2**
 H&D LABORATORY NO: 74/342
 BORING NO: 74-222 SAMPLE NO: 10 DEPTH: 47.5 - 50.0 DATE: 18 DEC 1974
 CONSOLIDATION TEST -- TIME CURVES
 MACHINE: RAIST OUT
 FORMAT: AFTER EEC FORM 2028

FIGURE 3b

④

DESIGN MEMORANDUM NO. 3 GENERAL
 FLOOD CONTROL - LAKE DARLING
 SOURS RIVER, NORTH DAKOTA
 SOILS TEST DATA
 STATE HIGHWAY NO. 5
 BORING 74-50M

ST PAUL, MINN. DISTRICT

JUNE 1955

R1-R-5/783

PLATE NO. 8-84

2